ADDENDUM NO. 1

May 26, 2016

Marion Campus Sidewalk Replacement

Ivy Tech Community College
261 Commerce Drive
Marion, Indiana 46953

Prepared by:

GEA Architects, LLC
108 E. Jackson Street
Muncie, Indiana 47305-2806
765.289.9155
pkiser@geaarchitects.com

TO: ALL INTERESTED BIDDERS OF RECORD

This Addendum No. 1 forms part of the Contract Documents and modifies the original Bidding Documents dated May 19, 2016. Failure to acknowledge receipt of this addendum on the Supplement to Bid Form may subject Bidder to disqualification.

CHANGES TO THE PROJECT MANUAL

Section 000260

1. Replace Section 000260 "Supplement to Bid Form 96" with new Section 000260, attached.

Section 012300

1. Add the following text to paragraph 3.1 SCHEDULE OF ALTERNATES

   "H. Alternate No. 7: Saw cut existing concrete at dashed line designated on sheet A1.0-Rev1; remove existing concrete up to the dashed line, leaving in place all existing concrete beyond dashed line in the area surrounding the existing scissor lift. Scissor lift and surrounding concrete shall remain. Form an expansion joint between existing and new concrete. Pin new concrete to existing concrete using #4 bars at 24" o.c."

CHANGES TO THE DRAWING

Sheet A1.0

1. See revisions noted on Sheet A1.0-Rev1, attached.

CLARIFICATIONS / GENERAL INFORMATION

1. The public bid opening has been re-located: Bids will be publicly opened and read aloud in **Administrative Conference Room 156** in the Fisher Building, 345 S. High St., Muncie, IN.

2. The following is a list of contractors who attended the pre-bid conference on May 26, 2016:

Name	*Company*	*Email address*	*Phone #*
Keith Sullivan	Keith Sullivan	keithsullivaninc@sbcglobal.net	765-664-1145
Eric Graft	Brooks Construction	elgraft@brooks1st.com	260-478-1990
Justin Wiley	Bowman Construction	jwiley.bowman@gmail.com	765-661-7784

END OF ADDENDUM NUMBER ONE

SECTION 000260 - SUPPLEMENT TO BID FORM 96 (REVISED PER ADDENDUM #1)

EXPLANATORY NOTE:

The Indiana State Board of Accounts Bid Form 96 shall be completed in its entirety and shall be used for the Base Bid. This form is to be used as a supplement to Form 96 and shall be included with the Contractor's Bid.

TO: **IVY Tech Community College**
East Central Region VI
345 South High Street
Muncie, Indiana 47305

FOR: **Marion Campus Sidewalk Replacement**
IVY Tech Community College
261 Commerce Drive
Marion, Indiana 46953

BIDDER: _____

ADDRESS: _____

_____

TELEPHONE: _____

EMAIL: _____

The Undersigned, having visited the site of proposed construction of this Project, hereby proposes to furnish all materials, labor, tools, equipment and services required to complete this Project in accordance with the Contract Documents prepared by GEA Architects.

BASE BID: (Amount must exactly match Base Bid Amount on Bid Form 96)

_____

_____Dollars ($_____)

ALTERNATES: As described in Section 012300 "Alternates".

A. **Alternate # 1**: Remove existing concrete walk and replace with new 4" thick concrete walk. (Approx. 955 sq. ft.)

ADD / DEDUCT (Circle one) _____

_____Dollars ($_____)

Alternate # 2: Remove existing concrete walk and replace with new 4" thick concrete walk. (Approx. 1291 sq. ft.)

ADD _____

_____Dollars ($_____)

Alternate # 3: Remove existing concrete pad loading dock with curbs and replace with new 12" thick concrete pad loading dock with curbs. (Approx. 1947 sq. ft.)

ADD _____

_____Dollars ($_____)

Alternate # 4: Remove existing concrete walk and integral curb and replace with new 4" thick concrete walk and 18" integral curb. (Approx. 1418 sq. ft. and 241 LF of curb)

ADD _____

_____Dollars ($_____)

Alternate # 5: Remove existing concrete walk and integral curb and replace with new 4" thick concrete walk and 18" integral curb. (Approx. 3189 sq. ft. and 130 LF of curb)

ADD _____

_____Dollars ($_____)

Alternate # 6: Remove existing concrete walk and integral curb and replace with new 4" thick concrete walk and 18" integral curb. (Approx. 1488 sq. ft. and 186 LF of curb)

ADD _____

_____Dollars ($_____)

Alternate # 7: Saw cut existing concrete at dashed line designated on sheet A1.0-Rev1. Remove existing concrete up to the dashed line, leaving in place all existing concrete beyond dashed line in the area surrounding the existing scissor lift. Scissor lift and surrounding concrete to remain. Form an expansion joint between existing and new concrete. Pin new concrete to existing concrete using #4 bars at 24" o.c.

ADD / DEDUCT _____

_____Dollars ($_____)

ADDENDA RECEIVED:

Receipt of Addenda number(s) _____ through _____ inclusive, is hereby acknowledged.

COMPLETION TIME

If awarded the contract, we could begin construction within _____ calendar days of receipt of the executed Agreement.

We estimate completion time for the project to be _____ calendar days, assuming that the award of Contract allows the start of construction within 60 days of the bid opening and that we are not delayed by causes beyond our control.

CONTRACTOR'S STATEMENT OF PRE-BID CONFERENCE ATTENDANCE

The Bidder hereby states that the following individual represented their firm in attendance at the Pre-bid Conference:

_____

ADDITIONAL DOCUMENTS

The following documents shall be included with this Bid Form Supplement in order to qualify as a responsible and responsive bid.

Contractor's Bid for Public Work – Form No. 96 (Revised 2013 as prescribed by State Board of Accounts).
Bid Security, in the form of a bid bond, in the amount of 10% of the Base Bid amount.
Sub-Contractors List

GUARANTEE OF PRICES

By signing the Bid Form, the Bidder agrees to guarantee their prices for ninety (90) consecutive days from submittal date and to enter into Agreement with the Owner to perform the work for the stated Bid Sums at any time during this period. By signing the Bid Form, the undersigned agrees to begin work promptly and have the work substantially completed within the time period allocated as identified herein.

SIGNATURE AND NOTARIZATION

Bidder to complete:

I (we) hereby affirm and certify under penalties of perjury that the facts and information contained in the foregoing Bid and the attached submittals are true and correct to the best of my (our) knowledge and belief.

Dated at _____ this _____ day of _____, 2016.

NAME OF ORGANIZATION:_____

AUTHORIZED SIGNATURE:_____

PRINTED NAME:_____

TITLE:_____

NOTARY to complete:

ACKNOWLEDGEMENT

STATE OF _____)

COUNTY OF _____)

Before me, a Notary Public, personally appeared the above-named

_____

and swore that the statements in the foregoing Bid and the attached submittals are true and correct.

Subscribed and sworn to before me this _____ day of _____, 2016.

_____
Notary Public

My commission expires:_____

County of Residence: _____

(Seal)

SUBCONTRACTORS LIST

A. The following work will be performed (or provided) by subcontractors and their performance of the Work will be coordinated by the Contractor.

B. The Bidder will make no changes to this list after submission without a written request by the bidder and approval by the Owner.

TRADE / PORTION OF WORK	SUBCONTRACTOR

END OF SECTION 000260