



Addendum #1

Huntington City Building Façade Repairs

Addendum #1

Date: June 17, 2015
Project: Huntington City Building Façade Repairs

Pages: 3 (8-1/2x11) pages
Bid Dates: **June 27, 2016**

General Note:

This addendum is to be considered part of the plans and specifications for this project. Items changed or added by this addendum are to take precedence over the items or descriptions of the work in the project manual and the drawings. Items not mentioned in this addendum are to remain as described in the original plans and specifications.

Successful bidders will receive complete drawings with addendum items included and merged into a final set.

Clarifications

1. Sealant 5 year warranty in specifications is correct.
2. West hose tower brick repair J is to include removing and reconstructing the entire depth of the brick wall, not just brick veneer.
3. Dutchman repairs should be tooled to match surrounding stone to remain.
4. New Limestone joints are to use rope style joint to match existing.
5. Absolutely no smoking or other substance abuse will be tolerated on the property.
6. No road closure permitting costs will be required by contractor, city will address this if needed.
7. There are 3 man doors into the building in use. East elevation police entrance must remain accessible to the public at all times. The city building has a door on both the east and west side, one of the 2 doors must remain open at all times, when 1 door is blocked to public entry the contractor must place signage directing to other entry point. Even when closed to public access the door must be able to be used for emergency exiting from the building at all times.
8. Work hours may be from 7:00 AM – 8:00 PM only.
9. Water and electric will be provided on site for use by contractor.
10. The power lines along the north will have to be turned off for lifts to be used here, that will be taken care of by city but must be scheduled in advance of needing the shut off.
11. There is not a specific project schedule although all work must be complete and closed out by the end of 2016. The contractor is expected to work continuously on



Addendum #1 Huntington City Building Façade Repairs

the project once beginning (do not stretch the construction schedule over several months).

Drawing Set 1 Items: **Sheet R201**

1. Sills at 3rd floor windows show clouds but no mark, these are all to have repair S.

Other Notes

1. Pre bid sign-in attached.

HUNTINGTON PRE BID SIGN IN

JUNE 15, 2016



NAME	COMPANY	EMAIL
Jason Crain	Blue River Environmental	Richie.Byrd@brellc.net
Anthony Goodnight	City of Huntington	anthony.goodnight@huntington.in.us
Adam Cuttriss	City of Huntington	adam.cuttriss@huntington.in.us
Keith Roberts	WELLS MASONRY RESTORATION, INC. 317-672-7790	Keith.roberts@wellsmasonry.com
Rick Wells	" " "	rick.wells@wellsmasonry.com
JEFF MEYER	Midwest Maintenance, Inc. 937-773-9286	jeff@midwestmaintenance.com
Mike Hipkiss	Blakleys 317-600-1195	mike.hipkiss@blakleys.com
Brian Gottschalk	Atlas Building Sys. 248-563-3166	briangottschalk@atlasbuilding.com
Franklin Bault	Ionic cut stone 812-829 3416 call 812-821-2442	Ionic cut stone
KEVIN MONTGOMERY	krM	