



**Addendum #5
Pendleton Community Public Library
Renovation Project**

Date: April 3, 2020
Project: Pendleton Community Public Library
Project #: 19109
Pages: 1 of 2(8-1/2x11) pages
Bid Dates: **Tuesday, April 7, 2020 at 2:00 pm (prevailing local time)**

General Notes:

The original Specifications and Drawings dated March 10, 2020 for the project referenced above are amended as noted in this final Addendum No. 5. Receipt of this Addendum and any subsequent Addenda must be acknowledged on the Bid Form. Items changed or added by this addendum are to take precedence over the items or descriptions of the work in the project manual and the drawings. Items not mentioned in this addendum are to remain as described in the original plans and specifications.

Addendum #1 – issued March 17, 2020; 5 pages
Addendum #2 – issued March 25, 2020; 14 pages
Addendum #3 – issued March 31, 2020; 6 pages
Addendum #4 – issued April 02, 2020; 16 pages

Specifications Items:

01 77 00 -4 – Close out Procedures

Part 3 – EXECUTION – ADD THE FOLLOWING:

- C. Attic Stock: Additional material and accessories designated in the design specifications below and may be found in specific specification sections also:
 - 1. Provisions to be as follows:
 - a. Carpet – 5% of each color and pattern installed
 - b. Resilient Flooring – 5% of each color and pattern installed, including wall base
 - c. Wallcovering - 25 LF of each color and pattern of wall covering
 - d. Tile – 1% of each size, color, and surface finish, but not less than 1 full panel of each type
 - e. Ceiling Tile – 24 count of ceiling tile
 - f. Paint – 1 gallon for each color



**Addendum #5
Pendleton Community Public Library
Renovation Project**

2. Items not considered Attic Stock:
 - a. Any item not identified in the design specifications in the Attic Stock section.
 - (i) Perishable materials i.e. adhesives.
 - (ii) Project leftovers i.e. pipe, conduit, electrical boxes, floor tile, ceiling tile, carpet.
 - (iii) Casement items i.e. cabinets, millwork, office components.
3. Paint/Perishable Material:
 - a. Contract documents shall require the painting Contractor to store all left-over paint until final completion

08 71 00 – Door Hardware

1. Approved Equal – Rockwood Door Hardware
 - a. 300 Main St. Rockwood PA. Ph: 800-458-2424 – submitted by ASSA ABLOY
 - b. Products approved: Rockwood Flushbolts, Door Trim, Protection Plates, Stops and Holders.

08 43 13 -2 – Aluminum-Framed Storefront

1. To clarify – Finish of Aluminum frames to be clear anodized to match exiting.

Drawing Items:

Sheet A8-1- Door Schedule

1. Revision to Glazing Schedule –
 - a. Clarification - VG-1 and VG-2 are all to follow specifications for glazing strength and thickness, NOT what is shown on the A8-1 Glazing schedule.

Q&A

Attachments: N/A

END