

HCCSC HNHS Family and Consumer Science Renovation

Project # 2022.0033

November 17, 2023

ADDENDUM NO. A-2

This addendum is issued as a supplement to the plans and specifications and shall be considered an integral part of the same. Acknowledgement of receipt of this addendum is required on the Bid Form.

Item: A-2.1

Location: General

Description: The epoxy floor system is to be installed by "other" (Dancer Concrete Design) and is NOT to be included in the Contract. The General Contractor shall coordinate with Dancer Concrete the schedule for installation.

Item: A-2.2

Location: Sheet G1.1 – HAZARDOUS MATERIAL PLAN – FIRST FLOOR

Description: In the adjacent classroom(s), 125, 126, 128, 129, 130, to the east and west of the project space, are chalkboard(s) that are fixed to the demountable wall system that will be removed by others and is NOT to be included in the Contract. Contractor shall coordinate with Owner for installation of new white boards that will be provided and installed by Owner.

Item: A2.3

Location: Sheets A5.1 – ARCHITECTURAL – WALL SECTIONS AND DETAILS and A11.1 – ARCHITECTURAL - FIRST FLOOR FINISH PLAN

Description: Typical Perimeter Wall Section 1 / A5.1 shows gypsum board on both sides of the new metal stud wall; however, the Room Finish Schedule does not indicate the paint finish to use on the opposite side of the new wall from the project site. The contractor shall paint BOTH sides of the new perimeter walls with (P-1) Sherwin Williams, color: 7557 Summer White, Finish: Semi-Gloss and install rubber base (RB-1) on BOTH sides of the new walls. See Sheet A11.1, and specifications for additional information.