

Project: Fort Wayne International Airport CHA Project No.: 075494.000

Construct Taxiway G Extension & Demolish Taxiway C2

AIP No. 3-18-0022-XX

Date: June 21, 2024

The following addendum items modify, change, delete from or add to, the requirements of the contract documents for this project. The articles contained in the addendum take precedence over the requirements of the previously published contract documents. Where any article of the contract specifications or any detail of the contract drawings is modified or any paragraph, subparagraph or clause thereof is modified or deleted by the articles contained in this addendum, the unaltered provisions of that article, paragraph, subparagraph or clause shall remain in effect.

ITEM NO. 1 – SPECIFICATIONS

General Note – Unless noted to be reissued with this addendum, the following specifications revisions will be incorporated as part of the "Issued for Construction" specification booklet.

Section AB – Advertisement for Bids

Revision: The first paragraph on Page AB-1 is revised to read as follows:

The Fort Wayne-Allen County Airport Authority will receive sealed bids until 11:00 AM eastern time on the <u>3rd</u> <u>10th</u> day of <u>July 2024</u>, at the offices of the Airport Authority, Suite 209, 3801 W. Ferguson Road, Fort Wayne, Indiana, 46809 for the following:

The Bid Opening has been revised to **Wednesday**, **July 10**, **2024 at 11 AM (local time)** with this Addendum. Given the Independence Day holiday on July 4, 2024, the Owner is requesting that all questions be submitted no later than no later than 5:00 PM (eastern) on June 28, 2024, to provide sufficient time for an Addendum, if necessary, to be issued to plan holders ahead of the bid opening date.

Section P – Itemized Proposal

Reissued:

It has been discovered that pages P-17 thru P-26 (in PDF) along with the Excel spreadsheet provided under Addendum No. 2 has several instances where proposed quantities did not reflect correctly. Consequently, rather than revision specific items, sheets P-17 through P-26 are being reissued with Addendum No. 3 to avoid any confusion or discrepancy in both PDF and Excel formats.

Please discard previous iterations of the Itemized Proposal and utilize pages P-17 through P-26 issued with this Addendum. A revised Excel spreadsheet will be made available on Eastern Engineering's website in conjunction with this Addendum, including the date of this Addendum and its corresponding Addendum number.

ITEM NO. 2 – PLANS

General Note – Unless noted to be reissued with this addendum, the following plan revisions will be incorporated as part of the "Issued for Construction" plan set.

Sheet G1.3.1 – Sheet Index and Estimate of Quantities

Revision: Estimate of Quantity Tables have been updated to reflect changes outlined in Item No. 1 for Section P, Itemized Proposal.

ITEM NO. 3 – QUESTIONS

Question #1: Due to the significant changes in the scope of work and the 4th of July Holiday week,

can the owner push the bid date back to the following Wednesday, July 10th to allow

adequate time to review and price?

Response #1: Please refer to bid opening extension discussed under Item No. 1, Section AB.

Question #2: Can the excel version of addendum #2 be provided? It is currently not available on

Eastern Engineering plan room.

Response #2: Yes, the Excel spreadsheet for Addendum No. 2 should be available; however, please

discard and replace with version issued (and uploaded to Eastern's website) with this

Addendum.

Question #3: Bid items 149 and 151 appear to be duplicate items, Portland Cement Concrete

Pavement -15"-16" Depth Isolated Panel (Undistributed) -150 SY. Please clarify the difference between these two items. Also, bid items 146 and 147 also appear to be

duplicate items.

Response #3: Refer to Itemized Proposal corrections noted under Item No. 1, Section P.

Sincerely,

Nathan Lienhart, P.E.

Senior Project Manager

06/21/2024 NOTANA 06/21/2024 NOTANA 06/21/2024 NOTANA



Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Base Bid - Construct Taxiway G Extension

Project Milestone: A

Addendum No. 3

Date: June 21, 2024

ITEM NO.	PROJECT SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION
			St	andard I	Pay Items		
1	C-100	CONTRACTOR QUALITY CONTROL PROGRAM	1	LS			
2	C-102	INSTALLATION AND REMOVAL OF SILT FENCE	400	LFT			
3	C-102	INSTALLATION AND REMOVAL OF FABRIC DROP INLET PROTECTION	5	EACH			
4	C-105	MOBILIZATION	1	LS			
5	C-105	ENGINEER'S FIELD OFFICE	5	МО			
6	P-101	PAVEMENT REMOVAL - FULL DEPTH HMA SHOULDER (±8" HMA ON VARIABLE DEPTH AGGREGATE BASE AND 9" SOIL-CEMENT BASE)	1,030	SYD			
7	P-101	PAVEMENT REMOVAL - PCCP (±15" PCCP WITH ±6" HMA BASE)	1,900	SYD			
8	P-101	REMOVE MITL ASSEMBLY, SALVAGE FIXTURE	15	EACH			
9		REMOVE MITL FIXTURE, ISOLATION TRANSFORMER, AND COVER BASE CAN WITH SOLID LID	25	EACH			
10	P-101	REMOVE L-850C HIRL FIXTURE AND ISOLATION TRANSFORMER, ABANDON FOUNDATION BASE CAN IN PLACE	2	EACH			
11	P-101	REMOVE ELEVATED HIRL ASSEMBLY, SALVAGE FIXTURE	2	EACH			
12	P-101	REMOVE ELEVATED RGL ASSEMBLY, SALVAGE FIXTURE	1	EACH			
13	P-101	REMOVE ELEVATED RGL FIXTURE AND TRANSFORMER, CAP BASE CAN WITH L-867B STEEL LID	2	EACH			
14	P-101	REMOVE AIRFIELD GUIDANCE SIGN AND TRANSFORMER, SALVAGE SIGN AND ABANDON FOUNDATION IN PLACE	6	EACH			
15	P-101	REMOVE AIRFIELD GUIDANCE SIGN AND FOUNDATION, SALVAGE PANELS AND SIGN FRAMES	5	EACH			
16	P-101	REMOVE CONDUIT AND CABLE	1,820	LFT			
17	P-101	REMOVE CABLE	410	LFT			
18	P-101	REMOVE REINFORCED CONCRETE PIPE (UP TO 30-INCH DIAMETER)	818	LFT			
19	P-101	REMOVE STORM STRUCTURE	2	EACH			
20	P-101	REMOVE UNDERDRAIN PIPE (4"-6" DIA.)	1,080	LFT			

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Base Bid - Construct Taxiway G Extension

Project Milestone: Addendum No. 3

Date:

June 21, 2024

ITEM NO.	PROJECT SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION
21	P-101	REMOVE UNDERDRAIN CLEANOUT	3	EACH			
22	P-152	UNCLASSIFIED EXCAVATION	7,964	CYD			
23	P-154	SUBBASE COURSE	3,170	CYD			
24	P-307	CEMENT-TREATED PERMEABLE BASE COURSE (6" DEPTH)	15,100	SYD			
25	P-307	GEOTEXTILE SOIL-SEPARATION LAYER	5,300	SYD			
26	P-307	BOND BREAKER	10,000	SYD			
27	P-1U3	HOT-MIX ASPHALT (HMA) PAVEMENT - 2" SURFACE COURSE (GRADATION 2)	590	TON			
28	P-403	HOT-MIX ASPHALT PAVEMENT - 3" BINDER COURSE (GRADATION 1)	885	TON			
29	P-501	CEMENT CONCRETE PAVEMENT (16" DEPTH)	9,280	SYD			
30	P-501	REINFORCEMENT FOR ODD SHAPED PANELS	1,750	SYD			
31	P-603	EMULSIFIED TACK COAT	400	GAL			
32	P-605	JOINT SEALING FILLER	10,100	LFT			
33	P-620	REMOVAL OF EXISTING PAVEMENT MARKINGS	7,000	SFT			
34	P-620	SURFACE PREPARATION FOR APPLICATION OF NEW PAVEMENT MARKINGS	18,100	SFT			
35	P-620	RUNWAY AND TAXIWAY MARKING - YELLOW (FULL APPLICATION)	5,000	SFT			
36	P-620	RUNWAY AND TAXIWAY MARKING - BLACK (FULL APPLICATION)	10,300	SFT			
37	P-670	RUNWAY AND TAXIWAY MARKING - THERMOPLASTIC SURFACE PAINTED RUNWAY HOLD POSITION SIGN	1,300	SFT			
38	P-620	PAVEMENT MARKING - WHITE (FULL APPLICATION)	1,500	SFT			
39	P-620	REFLECTIVE MEDIA	720	LBS			
40	D-701	REINFORCED CONCRETE PIPE - 45 INCH x 29 INCH, ELLIPTICAL, CLASS IV	449	LFT			

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Base Bid - Construct Taxiway G Extension

Project Milestone: Addendum No. 3

Date:

June 21, 2024

ITEM NO.	PROJECT SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION
41	D-701	REINFORCED CONCRETE PIPE - 53 INCH x 34 INCH, ELLIPTICAL, CLASS IV	369	LFT			
42	D-705	PERFORATED UNDERDRAIN, 6- INCH PVC, COMPLETE	2,150	LFT			
43	D-705	UNDERDRAIN CLEANOUT, TYPE I	4	EACH			
44	D-705	UNDERDRAIN CLEANOUT, TYPE II	5	EACH			
45	D-751	INDOT TYPE D MANHOLE	1	EACH			
46	D-751	INDOT TYPE M MANHOLE	1	EACH			
47	T-901	HYDROMULCH SEEDING	400	KSFT			
48	1108	NO. 8 AWG, 5KV, L824, TYPE C CABLE, INSTALLED IN DUCT BANK OR CONDUIT	6,000	LFT			
49	L-108	NO. 6 AWG, SOLID, BARE COPPER COUNTERPOISE WIRE, INSTALLED IN TRENCH, ABOVE THE DUCT BANK OR CONDUIT, INCLUDING CONNECTIONS/TERMINATIONS	3,600	LFT			
50	L-110	NON-ENCASED, ELECTRICAL CONDUIT, 1-WAY, 2-INCH, IN TURF	1,100	LFT			
51	L-110	CONCRETE ENCASED, ELECTRICAL CONDUIT, 1-WAY, 2-INCH	2,200	LFT			
52	L-110	CONCRETE ENCASED, ELECTRICAL CONDUIT, 4-WAY, 2-INCH	330	LFT			
53	L-115	L-867E BASE CAN HANDHOLE, ELECTRIC OR CONTROL	2	EACH			
54	1-125	L-861T, INSTALL NEW ELEVATED LED TAXIWAY MITL FIXTURE ON NEW BASE, IN SHOULDER PAVEMENT	39	EACH			
55	L-125	L-861T, INSTALL ELEVATED LED TAXIWAY MITL FIXTURE ON NEW BASE, IN TURF	7	EACH			
56	L-125	INSTALL SALVAGED L-862 ELEVATED FIXTURE AND NEW L-830 ISOLATION TRANSFORMER WITH ADAPTER RING (L-868 TO L-867) ON EXISTING BASE CAN	2	EACH			
57	I-125	INSTALL NEW L-850C INCANDESCENT HIRL FIXTURES ON NEW BASE CAN, IN TAXIWAY PAVEMENT	2	EACH			
58	1-175	L-858, INSTALL NEW LED 1-MODULE SIZE 3 GUIDANCE SIGN ON NEW FOUNDATION	3	EACH			
59	1-125	L-858, INSTALL NEW LED 2-MODULE SIZE 3 GUIDANCE SIGN ON NEW FOUNDATION	2	EACH			

Fort Wayne-Allen County Airport Authority **Fort Wayne International Airport** Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 **Base Bid - Construct Taxiway G Extension**

Project Milestone: Addendum No. 3

					Date:	June 21, 2024	
ITEM NO.	PROJECT SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION
60	L-125	L-858, INSTALL NEW LED 3-MODULE SIZE 3 GUIDANCE SIGN ON NEW FOUNDATION	4	EACH			
61	1-175	L-858, INSTALL NEW LED 3-MODULE SIZE 3 GUIDANCE SIGN ON EXISTING FOUNDATION	1	EACH			
62	L-125	REPLACE PANELS ON EXISTING GUIDANCE SIGNS	15	EACH			
63	1-175	L-804, INSTALL NEW ELEVATED LED RGL ASSEMBLY ON NEW BASE IN NEW TAXIWAY SHOULDER HMA PAVEMENT	3	EACH			
64	MST-02	MAINTENANCE OF TRAFFIC	1	LS			
65	MST-03	CONSTRUCTION ENGINEERING	1	LS			
66	MST-04	PROJECT SECURITY	1	LS			
			ı				
		Standard Pay Item Subtotal					
			11	! - 4 ! . 4 -	d Dev Harris		
		T	Una	Istribute	ed Pay Items		
67	MST-06	HAUL ROUTE REPAIR (ALLOWANCE)	1	ALLOW	Forty-thousand dollars and zero cents	\$40,000.00	\$40,000.00
68	P-152	UNDERCUT UNSUITABLE MATERIAL (UNDISTRIBUTED)	800	CYD			
69	P-152	SPECIAL SUBGRADE TREATMENT (UNDISTRIBUTED)	400	CYD			
70	P-155	LIME TREATED SUBGRADE (UNDISTRIBUTED)	15,100	SYD			
71	P-155	LIME (UNDISTRIBUTED)	640	TON			
		Undistributed Pay Item Subtotal					
		T	<u> </u>		T		
		Total Base Bid Amount					

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Additive Alternate No. 1 - Demolish Taxiway C2

Project Milestone: Addendum No. 3

Date: June 21, 2024

ITEM NO.	PROJECT SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION
1107			Stand	ard Pay	Items		
72	P-101	PAVEMENT REMOVAL - PCCP (±15" PCCP WITH ±6" HMA BASE)	6,900	SYD			
73	P-101	PAVEMENT REMOVAL - FULL DEPTH HMA SHOULDER (±8" HMA ON VARIABLE DEPTH AGGREGATE BASE AND ±9" SOIL-CEMENT BASE)	2,150	SYD			
74	P-101	REMOVE IN-PAVEMENT HIRL BASE CAN ASSEMBLY	2	EACH			
75	P-101	REMOVE MITL BASE CAN ASSEMBLY IN TURF	13	EACH			
76	P-101	REMOVE MITL BASE CAN ASSEMBLY IN SHOULDER PAVEMENT	12	EACH			
77	P-101	REMOVE CONDUIT AND CABLE	2,000	LFT			
78	P-101	REMOVE AIRFIELD GUIDANCE SIGN FOUNDATION ASSEMBLY	6	EACH			
79	P-101	REMOVE 4"-4 WAY DUCT BANK	170	LFT			
80	P-101	REMOVE ELECTRICAL HANDHOLE	2	EACH			
81	P-101	REMOVE RGL BASE CAN ASSEMBLY	2	EACH			
82	P-152	BORROW EXCAVATION	6,932	CYD			
83	P-154	SUBBASE COURSE	600	CYD			
84	P-403	2" BITUMINOUS ASPHALT MIXTURE SURFACE COURSE (GRADATION 2)	140	TON			
85	P-403	3" BITUMINOUS ASPHALT MIXTURE BINDER COURSE (GRADATION 1)	210	TON			
86	P-603	EMULSIFIED TACK COAT	100	GAL			
87	P-605	JOINT SEALING FILLER	500	LFT			
88	D-705	PERFORATED UNDERDRAIN, 6- INCH PVC, COMPLETE	400	LFT			
89	D-705	UNDERDRAIN CLEANOUT, TYPE I	2	EACH			
90	T-901	HYDROMULCH SEEDING	200	KSFT			
91	MST-03	ADDITIONAL CONSTRUCTION ENGINEERING	1	LS			

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Additive Alternate No. 1 - Demolish Taxiway C2

Addendum No. 3 Project Milestone:

					Date:	June 21	, 2024
NO.	PROJECT SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION
92	L-108	NO. 8 AWG, 5KV, L824, TYPE C CABLE, INSTALLED IN DUCT BANK OR CONDUIT	600	LFT			
93		NO. 6 AWG, SOLID, BARE COPPER COUNTERPOISE WIRE, INSTALLED IN TRENCH, ABOVE THE DUCT BANK OR CONDUIT, INCLUDING CONNECTIONS/TERMINATIONS	600	LFT			
94	L-110	CONCRETE-ENCASED, ELECTRICAL CONDUIT, 1-WAY, 2-INCH	400	LFT			
95	L-125	INSTALL SALVAGED L-862 ELEVATED FIXTURE AND NEW L-830 ISOLATION TRANSFORMER ON NEW BASE CAN	2	EACH			
96	L-125	BASE BID CREDIT - EXISTING MITL SOLID LID INSTALLATION	-25	EACH			
97	L-125	BASE BID CREDIT - EXISTING GUIDANCE SIGN SOLID LID INSTALLATION	-6	EACH			
98	L-125	BASE BID CREDIT - RGL SOLID LID INSTALLATION	-2	EACH			
99	1 1-175	BASE BID CREDIT - INSTALL L-862 ELEVATED FIXTURE WITH ADAPTER RING ON EXISTING BASE CAN	-2	EACH			
	Γ		1			T	
		Standard Pay Item Subtotal					
			انسفان مانا	but ad Da			
			Undistri	outea Pa	tems .		
	Г						
		Undistributed Pay Item Subtotal					
	1		1			·	
		Total Additive Alternate No. 1 Amount					

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Additive Alternate No. 2 - Relocate Runway 5-23 Hold Position Locations

Project Milestone: Addendum No. 3

Date: June 21, 2024

			Dute. June 21,		-,						
	PROJECT SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION				
	Standard Pay Items										
100	P-101	REMOVE ELEVATED RGL ASSEMBLY, SALVAGE FIXTURE	18	EACH							
101	P-101	REMOVE AIRFIELD GUIDANCE SIGN AND FOUNDATION, SALVAGE PANELS AND SIGN FRAMES	12	EACH							
102	P-101	REMOVE CONDUIT AND CABLE	5,400	LFT							
103	P-620	REMOVAL OF EXISTING PAVEMENT MARKINGS	24,000	SFT							
104	P-620	SURFACE PREPARATION FOR NEW MARKINGS	35,300	SFT							
105	P-620	RUNWAY AND TAXIWAY MARKING - YELLOW (FULL APPLICATION)	9,300	SFT							
106	P-620	RUNWAY AND TAXIWAY MARKING - BLACK (FULL APPLICATION)	18,900	SFT							
107	P-620	RUNWAY AND TAXIWAY MARKING - THERMOPLASTIC SURFACE PAINTED RUNWAY HOLD POSITION SIGN	4,600	SFT							
108	P-620	PAVEMENT MARKING - WHITE (FULL APPLICATION)	2,500	SFT							
109	P-620	REFLECTIVE MEDIA	1,300	LBS							
110	L-108	NO. 8 AWG, 5KV, L824, TYPE C CABLE, INSTALLED IN TRENCH, DUCT BANK, OR CONDUIT	2,800	LFT							
111	L-108	NO. 6 BDSC COUNTERPOISE, INSTALLED IN TRENCH	1,200	LFT							
112	L-110	NON-ENCASED, ELECTRICAL CONDUIT, 1-WAY, 2-INCH, IN TURF	1,200	LFT							
113	L-115	INSTALL NEW L-867B BASE CAN HANDHOLE, ELECTRIC OR CONTROL	10	EACH							
114	L-125	L-858, INSTALL NEW LED 1-MODULE SIZE 3 ILS BOUNDARY SIGN ON EXISTING FOUNDATION	1	EACH							
115	L-125	L-858, INSTALL NEW LED 2-MODULE SIZE 3 GUIDANCE SIGN ON NEW FOUNDATION	2	EACH							
116	L-125	L-858, INSTALL NEW LED 3-MODULE SIZE 3 GUIDANCE SIGN ON NEW FOUNDATION	7	EACH							
117	L-125	L-858, RELOCATE LED 3-MODULE SIZE 3 GUIDANCE SIGN ON NEW FOUNDATION	1	EACH							
118	L-125	L-804, INSTALL NEW ELEVATED LED RGL ASSEMBLY ON NEW BASE IN NEW TAXIWAY SHOULDER HMA PAVEMENT	6	EACH							
119	L-125	L-804, INSTALL NEW ELEVATED LED RGL ASSEMBLY ON NEW BASE IN TURF	12	EACH							
120	L-125	REPLACE PANELS ON EXISTING GUIDANCE SIGNS	1	EACH							

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Additive Alternate No. 2 - Relocate Runway 5-23 Hold Position Locations

Project Milestone: Addendum No. 3

					Date: June 21, 2024		1, 2024				
	PROJECT SPEC. REF.		QUANTITY	UNIT	UNIT PRICE (WORDS)	UNIT PRICE	EXTENSION				
121	MST-02	ADDITIONAL MAINTENANCE OF TRAFFIC	1	LS							
122	MST-03	ADDITIONAL CONSTRUCTION ENGINEERING	1	LS							
123	MST-04	ADDITIONAL PROJECT SECURITY	1	LS							
124	L-125	BASE BID CREDIT - REPLACE PANELS ON EXISTING GUIDANCE SIGNS	-20	EACH							
		Standard Pay Item Subtotal									
	•										
			Undist	tributed	Pay Items						
		Undistributed Pay Item Subtotal									
				_							
		Total Additive Alternate No. 2 Amount									

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Additive Alternate No. 3 - Rehabilitate Taxiway C Between West Apron and Runway 14-32

Project Milestone:

Date:

Addendum No. 3

June 21, 2024

ITEM PROJECT QUANTITY UNIT UNIT PRICE DESCRIPTION UNIT PRICE (WORDS) **EXTENSION** NO. SPEC. REF. **Standard Pay Items** JOINT SEALING FILLER 126 P-620 REMOVAL OF EXISTING PAVEMENT MARKINGS 5,240 SFT 5,240 SFT 127 SURFACE PREPARATION FOR NEW MARKINGS 128 P-620 RUNWAY AND TAXIWAY MARKING - YELLOW (FULL APPLICATION) 2,600 SFT 129 P-620 RUNWAY AND TAXIWAY MARKING - BLACK (FULL APPLICATION) 2,700 SFT REFLECTIVE MEDIA 130 P-620 300 LBS MST-02 ADDITIONAL MAINTENANCE OF TRAFFIC 1 LS 131 LS 132 MST-03 ADDITIONAL CONSTRUCTION ENGINEERING 1 MST-04 ADDITIONAL PROJECT SECURITY 133 1 LS PST-505 WELDED WIRE FABRIC SYD 134 390 PST-505 REMOVE EXISITNG PCCP 15"-16" DEPTH ISOLATED PANEL 1,180 SYD 135 136 PST-505 PORTLAND CEMENT CONCRETE PAVEMENT - 15" - 16" DEPTH ISOLATED PANEL 1,180 SYD 137 PST-505 EXISTING PCCP JOINT SPALL REPAIR (EQUAL TO OR LESS THAN 4" DEPTH) 72 SFT PST-505 EXISTING PCCP CORNER SPALL REPAIR (EQUAL TO OR LESS THAN 4" DEPTH) 138 17 SFT PST-505 EXISTING PCCP POPOUT/CORE HOLE REPAIR (EQUAL TO OR LESS THAN 4" DEPTH) SFT 139 1 CLEAN AND RESEAL JOINTS - LONGITUDINAL AND TRANSVERSE IN EXISTING PCCP 140 PST-505 17.620 LFT JOINT WIDTH 1" OR LESS CLEAN AND RESEAL JOINTS - LONGITUDINAL AND TRANSVERSE IN EXISTING PCCP -141 PST-505 2.080 LFT JOINT WIDTH GREATER THAN 1" AND NOT GREATER THAN 2" CLEAN AND RESEAL JOINTS - EXPANSION AND ISOLATION JOINTS - JOINT WIDTH 142 PST-505 1,040 LFT NOT GREATER THAN 2" 143 PST-505 HMA PAVEMENT TO PCCP INTERFACE JOINT (TYPE "Y") LFT Standard Pay Item Subtotal

Fort Wayne-Allen County Airport Authority Fort Wayne International Airport Fort Wayne, Indiana

FWA Construct Taxiway G Extension & Demolish Taxiway C2 Additive Alternate No. 3 - Rehabilitate Taxiway C Between West Apron and Runway 14-32

Project Milestone: Addendum No. 3

June 21, 2024 Date: ITEM PROJECT NO. SPEC. REF. DESCRIPTION QUANTITY UNIT PRICE (WORDS) UNIT PRICE **EXTENSION** UNIT **Undistributed Pay Items** 144 P-152 UNDERCUT UNSUITABLE MATERIAL (UNDISTRIBUTED) 20 CYD 20 CYD 145 P-152 SPECIAL SUBGRADE TREATMENT (UNDISTRIBUTED) 40 146 PST-505 WELDED WIRE FABRIC (UNDISTRIBUTED) SYD PST-505 ROUTE AND SEAL CRACKS IN EXISTING PCCP (UNDISTRIBUTED) 1,000 LFT 147 148 PST-505 REMOVE EXISTING PCCP 15"-16" DEPTH ISOLATED PANEL (UNDISTRIBUTED) 150 SYD PORTLAND CEMENT CONCRETE PAVEMENT - 15" - 16" DEPTH ISOLATED PANEL 149 PST-505 150 SYD (UNDISTRIBUTED) EXISTING PCCP JOINT SPALL REPAIR (EQUAL TO OR LESS THAN 4" DEPTH) 150 PST-505 10 SFT (UNDISTRIBUTED) EXISTING PCCP CORNER SPALL REPAIR (EQUAL TO OR LESS THAN 4" DEPTH) 151 PST-505 SFT (UNDISTRIBUTED) **Undistributed Pay Item Subtotal Total Additive Alternate No. 3 Amount** SUBMITTED BY: TITLE: ADDRESS: **END OF ITEMIZED PROPOSAL**