





People-first places.

Client Name:	Fort Wayne Community Schools
Project Name:	Wayne HS Dining - 20230232
Date:	10/17/2024

ADDENDUM NO. 1

This addendum is issued as a supplement to the plans and specifications and shall be considered an integral part of the same.

Item: Location: Description:	1.01 Specifications, Table of Contents SECTION 09 91 23 - INTERIOR PAINTING and SECTION 09 51 00 - ACOUSTICAL CEILINGS removed from table of contents.
Item: Location: Sheet Description:	1.02 Drawings, Sheet G10.1 - Project Cover Drawing Sheet P4.1 added to the Working Drawing Index.
Item: Location: Description:	1.03Drawings, Sheet A1.1F & S1.1FNorth walls of Dining shown on plan to have offset thickened slab. Demolition plan modified sawcut area to more accurately reflect these changes.
Item: Location: Description:	1.04 Drawings, Sheets A2.1F, A10.1 Modified partition types to not extend up to deck.
Item: Location: Description:	1.05Drawings, Sheets A2.1F, A10.2Updated floor plan and elevations to reflect relocated kitchen equipment, refer to the attached revised drawings.
Item: Location: Description:	1.06Drawings, Sheet A6.2 - Booth DetailsProvide mock up of (1) back to back booth as indicated prior to proceeding with other booth or banquette sections.
Item: Location: Description:	1.07 Drawings, Sheet A9.1F - Reflected Ceiling Plan Clarification provided for finish tags and missing ceiling heights tagged. Refer to revised drawings attached.

Item:	1.08 Drawings, Sheet A10.2 - Interior Elevations & Casework Sections
Location: Description:	Drawings, Sheet A10.2 - Interior Elevations & Casework Sections
2 comption.	Sections of tile install to be done as mock up for approval prior to final installation as noted on elevations.
Item:	1.09
Location:	Drawings, Sheet A11.1F - Floor Finish Plan
Description:	Countertops revised to be QZ-1 & QZ-2.
Item:	1.10
Location:	Drawings, Sheet A11.1F - Floor Finish Plan
Description:	CWT-4 revised to be Color Wheel Mosaic.
Item:	1.11
Location:	General, Pre-Bid Meeting 10.14.2024 Minutes
Description:	The Pre-Bid Meeting Minutes from October 14, 2024, are attached and considered part of the contract documents.
Item:	1.12
Location:	General, Requests for Information, Bidding Documents
Description:	The attached RFI log include points of clarification that were addressed or have been responded to in this addendum.
Item:	1.13
Location:	Master Schedule, Section 01 01 15 Schedule
Description:	The preliminary schedule provided is to be considered part of the contract documents. The schedules start and finish dates cannot be adjusted.
Item:	1.14
Location:	FWCS Testing and Assessment Schedule, Section 01 01 15 Schedule
Description:	The attached Testing and Assessment Schedule dates will impact the Master Schedule for this project. Work may be limited or prohibited during these dates.
Item:	1.15
Location:	Hot Work Permit, Section 01 01 41 Project Work Rules
Description:	The attached hot work permit program shall be implemented within the project's requirements.
Item:	
Location:	Bid Form, Section 00 03 00 Bid Form
Description:	The attached Bid Form has been updated to reflect the requirements for breakout pricing. This breakout is for accounting purposes only. State the cost of each of the three (3) areas of work as shown on the Work Area Breakdown Plan.

Each contractor is responsible for incorporating all changes into their bid.

Respectfully submitted,

And Aflatter

JMH/SKH

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

	SECTION 00 00 01 – TITLE PAGE
	SECTION 00 00 02 – TABLE OF CONTENTS
	SECTION 00 00 03 – LIST OF DRAWINGS SHEETS
	SECTION 00 00 04 – LIST OF TECHINICAL SPECIFICATIONS
	SECTION 00 01 00 – INSTRUCTION TO BIDDERS
	SUBCONTRACTOR / MATERIAL SUPPLIER LIST (SAMPLE INCLUDED)
	SECTION 00 01 15 - LIST OF DRAWING SHEETS
	SECTION 00 03 00 – BID FORM
	SECTION 00 05 00 – AGREEMENT
	HAGERMAN, INC., STANDARD SUBCONTRACT WORK ORDER
	STANDARD FORM OF AGREEMENT BETWEEN
	CONTRACTOR AND SUBCONTRACTOR (AIA DOCUMENT
	A401 – 2017)
	HAGERMAN, INC., WORK ORDER EXHIBITS AND ATTACHMENTS
	SECTION 00 31 10 - ELECTRONIC DOCUMENTS
D	IVISION 01 - GENERAL REQUIREMENTS
	······································

SECTION 01 01 10 – SUMMARY WORK

- SECTION 01 01 15 SCHEDULE (See attached preliminary Construction Schedule)
- SECTION 01 01 25 PAYMENT

APPLICATION AND CERTIFICATE FOR PAYMENT (G702 sheet for subcontracts and Purchase

Orders.) Sample Included.

- SECTION 01 01 41 PROJECT WORK RULES A COPY OF THE ENTIRE HAGERMAN SAFETY MANUAL IS AVAILABLE AT HTTPS://THEHAGERMANGROUP.COM/SAFETY. THE PASSWORD TO USE IS "safety"
- SECTION 01 10 00 CLOSEOUT PROCEEDURES
- SECTION 01 20 20 OPERATION AND MAINTENANCE DATA
- SECTION 01 23 00 ALTERNATES
- SECTION 01 30 00 PROJECT RECORD DOCUMENTS
- SECTION 01 33 00 SUBMITTAL PROCEDURES
- SECTION 01 35 00 BIM PROTOCOL
- SECTION 01 35 53 SECURITY PROCEDURES
- SECTION 01 40 00 QUALITY REQUIREMENTS
- SECTION 01 42 00 REFERENCES
- SECTION 01 60 00 PRODUCT REQUIREMENTS
- SECTION 01 73 00 EXECUTION
- SECTION 01 79 00 DEMONSTRATION AND TRAINING

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 41 19 - SELECTIVE STRUCTURE DEMOLITION

DIVISION 03 - CONCRETE

SECTION 03 30 00 - CAST-IN-PLACE CONCRETE

DIVISION 04 - MASONRY

NOT APPLICABLE

DIVISION 05 - METALS

SECTION 05 05 19 - POST-INSTALLED ANCHORS SECTION 05 12 00 - STRUCTURAL STEEL FRAMING

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

SECTION 06 41 16 - PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

SECTION 07 21 00 - THERMAL INSULATION

DIVISION 08 - OPENINGS

SECTION 08 11 13 - HOLLOW METAL DOORS AND FRAMES SECTION 08 14 16 - FLUSH WOOD DOORS SECTION 08 14 23 - IMPACT RESISTANT DOORS SECTION 08 31 13 - ACCESS DOORS AND FRAMES SECTION 08 33 13 - COILING COUNTER DOORS SECTION 08 36 13 - SECTIONAL DOORS SECTION 08 41 13 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS SECTION 08 71 00 - DOOR HARDWARE SECTION 08 80 00 - GLAZING

DIVISION 09 - FINISHES

SECTION 09 22 16 - NON-STRUCTURAL METAL FRAMING SECTION 09 29 00 - GYPSUM BOARD SECTION 09 30 13 - CERAMIC TILING SECTION 09 51 23 - ACOUSTICAL TILE CEILINGS SECTION 09 65 13 - RESILIENT BASE AND ACCESSORIES SECTION 09 65 19 - RESILIENT TILE FLOORING SECTION 09 68 13 - TILE CARPETING SECTION 09 84 33 - SOUND-ABSORBING WALL UNITS SECTION 09 84 36 - SOUND-ABSORBING CEILING UNITS SECTION 09 91 00 - PAINTING SECTION 09 93 00 - STAINING AND TRANSPARENT FINISHING

DIVISION 10 - SPECIALTIES

SECTION 10 26 00 - WALL AND DOOR PROTECTION SECTION 10 28 00 - TOILET, BATH, AND LAUNDRY ACCESSORIES SECTION 10 51 13 - METAL LOCKERS

DIVISION 11 - EQUIPMENT

NOT APPLICABLE

DIVISION 12 - FURNISHINGS

SECTION 12 36 61.16 - SOLID SURFACING COUNTERTOPS

DIVISION 13 - SPECIAL CONSTRUCTION

NOT APPLICABLE

DIVISION 14 - CONVEYING EQUIPMENT

NOT APPLICABLE

DIVISION 21 - FIRE SUPPRESSION

SECTION 21 10 00 - WATER-BASED FIRE-SUPRESSION SYSTEMS

DIVISION 22 - PLUMBING

SECTION 22 05 17 - SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING SECTION 22 05 18 - ESCUTCHEONS FOR PLUMBING PIPING SECTION 22 05 19 - METERS AND GAGES FOR PLUMBING PIPING SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT SECTION 22 05 53 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT SECTION 22 07 19 - PLUMBING PIPING INSULATION SECTION 22 11 16 - DOMESTIC WATER PIPING SECTION 22 11 16 - DOMESTIC WATER PIPING SPECIALTIES SECTION 22 13 16 - SANITARY WASTE AND VENT PIPING SECTION 22 13 19 - SANITARY WASTE PIPING SPECIALTIES SECTION 22 14 13 - FACILITY STORM DRAINAGE PIPING SECTION 22 14 23 - STORM DRAINAGE PIPING SPECIALTIES

DIVISION 23 - HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)

SECTION 23 05 17 - SLEEVES AND SLEEVE SEALS FOR HVAC PIPING SECTION 23 05 18 - ESCUTCHEONS FOR HVAC PIPING SECTION 23 05 19 - METERS AND GAUGES FOR HVAC PIPING AND EQUIPMENT SECTION 23 05 29 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT SECTION 23 05 53 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT SECTION 23 05 93 - TESTING, ADJUSTING, AND BALANCING FOR HVAC SECTION 23 07 13 - DUCT INSULATION SECTION 23 07 19 - HVAC PIPING INSULATION SECTION 23 11 23 - FACILITY NATURAL-GAS PIPING SECTION 23 21 13 - HYDRONIC PIPING SECTION 23 23 00 - REFRIGERANT PIPING SECTION 23 31 13 - METAL DUCTS SECTION 23 33 00 - AIR DUCT ACCESSORIES SECTION 23 36 00 - AIR TERMINAL UNITS SECTION 23 37 13 - DIFFUSERS, REGISTERS, AND GRILLES SECTION 23 41 00 - PARTICULATE AIR FILTRATION

DIVISION 25 - INTEGRATED AUTOMATION

NOT APPLICABLE

DIVISION 26 - ELECTRICAL

SECTION 26 05 19 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES SECTION 26 05 26 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS SECTION 26 05 29 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS SECTION 26 05 33 - RACEWAYS AND BOXES FOR ELECTRICAL EQUIPMENT SECTION 26 05 44 - SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING SECTION 26 05 53 - IDENTIFICATION FOR ELECTRICAL SYSTEMS SECTION 26 24 16 - PANELBOARDS SECTION 26 27 26 - WIRING DEVICES SECTION 26 51 19 - LED INTERIOR LIGHTING

DIVISION 27 - COMMUNICATIONS

SECTION 27 15 00 - COMMUNICATIONS HORIZONTAL CABLING

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

NOT APPLICABLE

DIVISION 31 - EARTHWORK

NOT APPLICABLE

DIVISION 32 - EXTERIOR IMPROVEMENTS

NOT APPLICABLE

DIVISION 33 - UTILITIES

NOT APPLICABLE

DIVISION 34 - TRANSPORTATION

NOT APPLICABLE

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

NOT APPLICABLE

DIVISION 40 - PROCESS INTEGRATION

NOT APPLICABLE

DIVISION 41 - MATERIAL PROCESSING AND HANDLING EQUIPMENT

NOT APPLICABLE

DIVISION 42 - PROCESS HEATING, COOLING, AND DRYING EQUIPMENT

NOT APPLICABLE

DIVISION 43 - PROCESS GAS AND LIQUID HANDLING, PURIFICATION AND STORAGE EQUIPMENT

NOT APPLICABLE

DIVISION 44 - POLLUTION CONTROL EQUIPMENT

NOT APPLICABLE

DIVISION 45 - INDUSTRY-SPECIFIC MANUFACTURING EQUIPMENT

NOT APPLICABLE

DIVISION 46 - WATER AND WASTEWATER EQUIPMENT

NOT APPLICABLE

DIVISION 48 - ELECTRICAL POWER GENERATION

NOT APPLICABLE



Fort Wayne Community Schools WAYNE DINING & KITCHEN





WE ARE YOUR SCHOOLS

<u>OWNER</u> Fort Wayne Community Schools 1519 Catalpa Street Fort Wayne, IN 46802 Voice:(260) 467-2521

Contact: Joshua Summers, Capital Projects Coordinator email: Joshua.Summers@fwcs.k12.in.us



ARCHITECT, INTERIORS, M&E ENGINEERS Design Collaborative, Inc. 200 East Main Street Suite 600 Fort Wayne, IN 46802 Voice: (260) 422-4241

Contacts: Jeremiah Hatfield, Architectural Project Manager email: jhatfield@designcollaborative.com

Molly Schultz, Project Architect email: mschultz@designcollaborative.com

Jessica Rossow, Interior Designer email: jrossow@designcollaborative.com

Jason Baker, Mechanical Engineer email: jbaker@designcollaborative.com

Shalina Gupta, Electrical Engineer

email: sgupta@designcollaborative.com



FORT WAYNE, INDIANA

BID SET SEPTEMBER 13, 2024

PROJECT TEAM



BUILDING A **BETTER** FUTURE

Hagerman Inc. 510 W. Washington Blvd. Fort Wayne, IN 46802 Voice:(260) 424-1470

Contact: Chris Moore email: CMoore@Hagermangc.com

Nikki Holt, Project Manager email: NHolt@Hagermangc.com



STRUCTURAL & CIVIL ENGINEERS Engineering Resources, Inc. 4175 New Vision Drive Fort Wayne, IN 46845 Voice:(260) 490-1025

Contacts: Dan Schenkel, PE, SE , Structural Engineer email: dan@eri.consulting

Mark Reinhard, P.E., LEED AP BD+C, Civil Engineer email: mark@eri.consulting



Contacts: Jim Kessenich Jr., Project Manager email: jkessenich@vorndranconsulting.com



GENERAL PROJECT COVER SHEET 10/17/2024 G0.1 GENERAL INFORMATION G0.2 CODE STUDY & LIFE SAFETY PLANS G1.1 **GENERAL NOTES & PARTITION TYPES** G2.1 PHASING PLANS G3.1 STRUCTRUAL STRUCTURAL NOTES S0.1 FOUNDATION PLAN - UNIT F S1.1F FOUNDATION DETAILS S1.2 LOW ROOF FRAMING PLAN - UNIT F S2.1F STRUCTURAL DETAILS S3.1 JOIST REINFORCEMENT DETAILS S4.1 S5.1 MASONRY DETAILS ARCHITECTURAL

ARCHIT	LUINAL	
10/17/2024	A1.1F	DEMOLITION FLOOR PLAN - MAIN LEVEL - UNIT F
10/17/2024	A2.1F	FLOOR PLAN - MAIN LEVEL - UNIT F
	A5.1	WALL SECTIONS
	A5.2	WALL SECTIONS @ OH DOORS
	A6.1	ENLARGED DETAILS
	A6.2	BOOTH DETAILS
	A6.3	'RAFT' CEILING DETAILS
	A7.1	FRAME ELEVATIONS, SCHEDULES & DETAILS
10/17/2024	A9.1F	REFLECTED CEILING PLAN - MAIN LEVEL - UNIT F
	A9.2	REFLECTED CEILING PLAN - DETAILS
10/17/2024	A10.1	INTERIOR ELEVATIONS
10/17/2024	A10.2	INTERIOR ELEVATIONS & CASEWORK SECTIONS
	A11.1F	FLOOR FINISH PLAN - MAIN LEVEL - UNIT F

PLUMBING

P1.0F	PLUMBING DEMOLITION PLAN - UNDERGROUND - UNIT F
P1.1F	PLUMBING DEMOLITION PLAN - MAIN LEVEL - UNIT F
P2.0F	PLUMBING PLAN - UNDERGROUND - UNIT F
P2.1F	PLUMBING PLAN - MAIN LEVEL - UNIT F
P3.1	ENLARGED PLUMBING PLANS - BOILER ROOM
P3.2	ENLARGED PLUMBING PLANS - KITCHEN
P3.3	ENLARGED PLUMBING PLANS - CORNER CAFE
(P4,1	
P5.1	PLUMBING DETAILS
P6.1	PLUMBING SCHEDULES

MECHANICAL

M1.1F	MECHANICAL DEMOLITION PLAN - MAIN LEVEL - UNIT F
M1.4F	MECHANICAL DEMOLITION PLAN - ROOF - UNIT F
M1.5	ENLARGED MECHANICAL DEMOLITION PLANS - BOILER ROOM
M1.8	ENLARGED MECHANICAL DEMOLITION PLAN - MECHANICAL F54
M2.1F	MECHANICAL PLAN - MAIN LEVEL - UNIT F
M2.4F	MECHANICAL PLAN - ROOF LEVEL - UNIT F
M3.1	ENLARGED MECHANICAL PLANS - BOILER ROOM
M5.1	MECHANICAL DETAILS
M6.5	MECHANICAL SCHEDULES
M8.1	HVAC CONTROLS

WORKING DRAWING INDEX

ELECTRICAL	
E1.1F	ELECTRICAL DEMOLITION PLAN - MAIN LEV
E2.1F	POWER PLAN - MAIN LEVEL - UNIT F
E2.4	POWER PLAN - ROOF
E3.1F	LIGHTING PLAN - MAIN LEVEL - UNIT F
E5.1	ELECTRICAL DETAILS
E5.2	ELECTRICAL DETAILS
E6.1	RISER DIAGRAM
E6.2	PANEL SCHEDULES
E6.3	ELECTRICAL SCHEDULES

KITCHEN HOOD SYSTEM

KH1	KITCHEN HOOD SYSTEM
KH2	KITCHEN HOOD SYSTEM
KH3	KITCHEN HOOD SYSTEM
KH4	KITCHEN HOOD SYSTEM
KH5	KITCHEN HOOD SYSTEM
KH6	KITCHEN HOOD SYSTEM
KH7	KITCHEN HOOD SYSTEM
KH8	KITCHEN HOOD SYSTEM
KH9	KITCHEN HOOD SYSTEM
KH10	KITCHEN HOOD SYSTEM
KH11	KITCHEN HOOD SYSTEM
KH12	KITCHEN HOOD SYSTEM
KH13	KITCHEN HOOD SYSTEM
KH14	KITCHEN HOOD SYSTEM
KH15	KITCHEN HOOD SYSTEM
KH16	KITCHEN HOOD SYSTEM
KH17	KITCHEN HOOD SYSTEM
KH18	KITCHEN HOOD SYSTEM
KH19	KITCHEN HOOD SYSTEM
KH20	KITCHEN HOOD SYSTEM
KH21	KITCHEN HOOD SYSTEM
KH22	KITCHEN HOOD SYSTEM
KH23	KITCHEN HOOD SYSTEM

KH24 KITCHEN HOOD SYSTEM

FOODSERVICE EQUIPMENT

FS1.0	Foodservice Notes, Symbols & Legends
FS1.1	Foodservice Equipment Layout & Schedule
FS1.2	Foodservice Equipment Special Conditions
FS2.0	Foodservice Equipment Spot Location Layout
FS2.1	Foodservice Equipment Spot Location Layout
FS2.2	Foodservice Equipment Spot Location Layout
FS5.0	Foodservice Equipment Details & Elevations
FS5.1	Foodservice Equipment Details & Elevations
FS5.2	Foodservice Equipment Details & Elevations
FS5.3	Foodservice Equipment Details & Elevations
FS5.4	Foodservice Equipment Details & Elevations
FS5.5	Foodservice Equipment Details & Elevations
FS5.6	Foodservice Equipment Details & Elevations



FOODSERVICE CONSULTANT Vorndran & Associates 7670 Shasta Drive Indianapolis, IN 46217 Voice:(317) 677-3475




ш

ATI




G0.1






PLAN NOTES THIS SHEET: PROVIDE 24" WIDE x 12" THICK THICKENED SLAB UNDER ALL NEW MASONRY WALLS. SEE DTL. #12/S1.2 SEE ARCHITECTURAL DRAWINGS FOR ADDITIONAL DIMENSIONS AND WALL CONSTRUCTION INFORMATION. NO HORIZONTAL CONSTRUCTION / COLD JOINTS, OTHER THAN THOSE SHOWN IN THE FOUNDATION DETAILS, ARE ALLOWED IN THE FOUNDATION UNLESS APPROVED IN WRITING BY THE STRUCTURAL ENGINEER. . COORDINATE REQUIRED PIPE SLEEVES WITH CIVIL, MECHANICAL, ELECTRICAL, PLUMBING DRAWINGS. LOWER FOOTING AS REQ'D. AT UNDERGROUND UTILITIES PER #8/S1.2 (TYP.) THAT WOULD OTHERWISE PASS THROUGH THE FOOTING. FOR PIPES THAT PASS BELOW STRIP FOOTINGS AND THICKENED SLABS, PLACE PIPE IN A PIPE SLEEVE THAT IS 2 SIZES LARGER AND FILL VOIDS BETWEEN PIPE AND SLEEVE WITH A COMPRESSIBLE MATERIAL AS REQUIRED BY THE PLUMBING CODE. SEE CIVIL AND PLUMBING


DRAWINGS. SEE S1.2 FOR TYPICAL CONSTRUCTION AND CONTROL JOINTS DETAILS IN SLABS ON GRADE. COORDINATE CONCRETE FLOOR SLAB FINISH WITH ARCHITECTURAL DRAWINGS.








S1.1F








	DEMOLITION KEYNOTES
D 101	REMOVE VCT/CARPET FLOORING AND BASE COMPLETE. PRE FOR NEW FINISHES INDICATED.
D 102	REMOVE THICK-SET QUARRY TILE, MORTAR BED, AND BASE C CONTRACTOR TO CLEAN EXISTING CONCRETE SLAB AND INFI CONCRETE FILL AS REQUIRED FOR NEW FLOOR FINISH INSTA SCHEDULED.
D 103	EXISTING FLOORING TO REMAIN, PROTECT DURING CONSTRU ACTIVITIES.
D 104	SAWCUT & REMOVE PORTION OF SLAB AS INDICATED. SEE ST ELECTRICAL, PLUMBING, AND KITCHEN EQUIPMENT DRAWING INFORMATION. SEE FINISH SCHEDULE FOR NEW FLOORING FI LOCATIONS OF EXISTING UTILITIES AND MODIFY SAWCUT ARE
D 105	REMOVE THICK-SET QUARRY TILE, MORTAR BED, AND BASE C SAWCUT & REMOVE SLAB AS REQUIRED FOR MEP SCOPE. PR QUARRY TILE INSTALLATION.
D 401	DEMO GLAZED CMU BLOCK WALLS.
D 402	PROTECT EXISTING STEEL COLUMNS DURING DEMOLITION
D 501	REMOVE GYPSUM BOARD AND STUD WALL PARTITION(S) COM PORTION AS INDICATED)
D 502	REMOVE CMU WALL PARTITION(S) COMPLETE (OR PORTION A PROVIDE NEW LINTEL AS REQUIRED. SEE STRUCTURAL.
D 504	REMOVE PORTION OF WALL FOR NEW WINDOW / DOOR/ EQUII AS SHOWN, SEE RENOVATION PLAN. PROVIDE NEW LINTEL A: STRUCTURAL.
D 701	REMOVE DOOR(S) AND FRAME COMPLETE. REPAIR JAMBS TO FINISHES OR INFILL CMU MATCHING EXISTING COURSING WH
D 703	REMOVE EXISTING DOOR (AND TRANSOM OR LOUVER PANEL APPLICABLE). EXISTING FRAME TO REMAIN. PATCH/ REPAIR I AS REQUIRED AND PREPARE TO RECEIVE NEW DOOR (AND TF OR LOUVER AS SCHEDULED).
D 704	REMOVE EXISTING ENTRY SYSTEM IN ITS ENTIRETY, INCLUDI SEALANT, FASTENERS, DOOR HARDWARE, AND FLOOR STOPS EXISTING OPENING FOR NEW CONSTRUCTION.
D 711	DEMO EXISTING COILING DOOR IN ITS ENTIRETY.
D 801	REMOVE CASEWORK/ CABINETRY/ COUNTER IN ITS ENTIRETY INDICATED). PATCH AND REPAIR WALL SURFACE THAT WILL F TO MATCH EXISTING.
D 802	REMOVE ALL KITCHEN EQUIPMENT, TYP. THIS ROOM. VERIFY EQUIPMENT IS TO BE DISPOSED OR RETURNED TO OWNER.
D 803	REMOVE METAL LOCKERS AND TRIM COMPLETE.
D 804	RELOCATE COPIER TO LOCATION SHOWN ON RENOVATION PL
D 806	REMOVE WALL MOUNTED SHELVING AND ASSOCIATED HARD
D 807	REMOVE ALL TOILET ACCESSORIES, TOILET PARTITIONS (PAR COMPLETE, AS INDICATED), MIRRORS, AND MISC. WALL MOUN
D 810	REMOVE WALL MOUNTED FIRE EXTINGUISHER AND SALVAGE RENOVATION PLANS FOR NEW LOCATIONS.
D 815	REMOVE FIRE EXTINGUISHER CABINET. SALVAGE NEWER FIR EXTINGUISHERS/CABINETS FOR REUSE. SEE RENOVATION PL
D 901	REMOVE SUSPENDED ACOUSTICAL TILE CEILING PADS, GRID, ACCESSORIES COMPLETE.
D 902	REMOVE EXISTING GYP / PLASTER CEILNG COMPLETE.
D 903	SALVAGE EXISTING WIREWORKS CEILING FOR REUSE, SEE RE
D 904	REMOVE SUSPENDED ACOUSTICAL TILE CEILING AS REQUIRE MECHANICAL SCOPE. REINSTALL GRID AND PADS AFTER WOR
MD 01	REMOVE WASHER AND DRYER AND ASSOCIATED PLUMBING/E DRAWINGS FOR MORE INFORMATION.
PD 01	REMOVE PLUMBING FIXTURES AND RELATED ACCESSORIES. WITH PLUMBING.
PD 02	RELOCATE ROOF DRAIN, SEE PLUMBING DRAWINGS.
PD 03	REMOVE & RELOCATE MOP SINK AND TMV TO NEW LOCATION RENOVATION PLAN.










	GENERAL CONSTRUCTION NOTES
1.	REFER TO GENERAL INFORMATION SHEET G0.2 FOR SYMBOLS LEGI
1.	ABBREVIATIONS.
2.	CONTRACTORS INSTALLED WORK IS TO COMPLY WITH ALL LOCAL, S NATIONAL BUILDING CODES AND THE AMERICANS WITH DISABILITY
3.	CONTRACTORS ARE TO OBTAIN ALL NECESSARY PERMITS REQUIRE THE PROJECT.
4.	CONTRACTORS SHALL FULLY REVIEW ALL PROJECT DOCUMENTS A INFORMATION AS REQUIRED FOR SUBMITTALS. CONTRACTORS ARE TO REVIEW THE FULL EXTENT OF THE WORK PRIOR TO EXECUTION
5.	DO NOT SCALE THE DRAWINGS. PLEASE FORWARD ALL QUESTIONS CLARIFICATION OF DIMENSIONS TO THE ARCHITECT/ ENGINEER FOR RESOLUTION.
6.	NOTIFY ARCHITECT IMMEDIATELY OF ANY DISCREPANCIES PRIOR T DRAWING PREPARTION, MATERIAL FABRICATION AND/OR INSTALLA
7.	CONTRACTOR SHALL INCLUDE A SIGNED AUTHORIZATION WITH ALL EQUIPMENT SHOP DRAWING SUBMITTALS INDICATING THAT FIELD D WERE OBTAINED AND ARE ACCURATE TO THE BEST OF THEIR KNOW
8.	CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS & CONDITIONS THE PROJECT PRIOR TO MATERIAL FABRICATION & INSTALLATION. (OMMISSIONS AND/OR DISCREPANCIES SHALL BE BROUGHT TO THE THE ARCHITECT/ ENGINEER IMMEDIATELY FOR RESOLUTION AND P PROCEEDING WITH THE WORK.
9.	CONTRACTOR SHALL COORDINATE ALL WORK WITH THE EQUIPMEN MANUFACTURER TO ENSURE APPROPRIATE WALL BLOCKING REQU SUPPORT OF THE EQUIPMENT AND ROUGH IN CLEARANCE REQUIR EQUIPMENT INSTALLATION AND USE.
10.	CONTRACTOR TO LAY OUT AND MARK ALL WALLS AND OPENINGS P CONSTRUCTION. ANY DISCREPANCIES SHALL BE REPORTED TO TH IMMEDIATELY FOR RESOLUTION.
11.	DETAILS AND NOTES ON THESE PAGES MAY BE GENERALIZED AND TO AID THE CONTRACTOR IN EVALUATION OF THIS WORK AS REQU CONSTRUCTION, BUT DRAWINGS SHALL NOT BE HELD TO BE ALL IN CONTRACTOR TO PERFORM FIELD ALTERATIONS, PATCHING AND P FOR ALL NEW WORK AS REQUIRED WHETHER OR NOT IT IS SPECIFI THESE DRAWINGS. CONSULT WITH PRODUCT MANUFACTURER FOR REQUIREMENTS OF INSTALLATION.
12.	IT IS PREFERRED THAT ALL CONTRACTORS UTILIZE THE SAME FIRE CONTRACTOR FOR THE FIRESTOPPING SCOPE OF WORK. SEE THE NOTES ON THE LIFE SAFETY PLAN FOR MORE INFORMATION.
13	ALL MASONRY CUTTING/INFILL IS INTENDED TO ALIGN TO EXISTING JOINTS AT 16" O.C., REQUEST CLARIFICATION FROM ARCHTECT IF L NOT ALLOW.
	PLAN CONSTRUCTION KEYNOTES
33000-19	THICKENED EDGE SLAB DOWELLED INTO EXISTING ADJACENT STRUCTURAL
42000-3	PROVIDE BULLNOSE CMU UNITS AT CORNER, TYP. IN KITCHEN
42000-5	6" RECESS IN NEW CMU WALL FOR MONITOR NICHE. VERIFY SI MONITOR SIZE.
42000-6	NEW 4" CMU WALL TIED TO EXISTING EXTERIOR WALL.
42000-8	NEW CMU SOAPS AROUND EXISTING COLUMN
42000-11	ASSUME 25 SF OF JOINTS AT DEMO'D CHASE TO BE RETOOLED REQUIRED AT DEMO'D WALL AND SINK.
93000-15	CWT-5 TO BE INSTALLED ON COLD BARS. BOTTOM EDGE OF TIL SCHLUTER ECK-E.
104413-1	FIRE EXTINGUISHER CABINET, FULLY RECESSED. MOUNTING H

#	DESCRIPTION	MODEL	MFGR.	CON
1	1 1/4" DIAM. GRAB BAR, 18" LONG	B-5806 x 18	BOBRICK	
2	1 1/4" DIAM. GRAB BAR, 36" LONG	B-5806 x 36	BOBRICK	
3	1 1/4" DIAM. GRAB BAR, 48" LONG	B-5806 x 48	BOBRICK	
4.2	TOILET TISSUE HOLDER, DOUBLE ROLL, SURFACE-MOUNTED	RT23	CONTINENTAL	
5	SANITARY NAPKIN DISPOSAL	6140	RUBBERMAID	
8	LIQUID SOAP DISPENSER, MANUAL, WALL MOUNT	9390	IMPACT	BY OWNER
9	PAPER TOWEL DISPENSER, MANUAL, WALL MOUNT	B-263	BOBRICK	
11	18" x 36" ANGLE FRAME MIRROR	B-165 1836	BOBRICK	











DETAIL KEYNOTES

SHOP FABRICATED FLUSH PLASTIC LAMINATE FACED PANELING. 1/2" PARTICLE 64219-2 BOARD SUBSTRATE WITH PLASTIC LAMINATE FACE, REFER TO FINISH PLANS FOR LAMINATE SELECTION. SECURE LAMINATE PANELS TO SUBSTRATE USING FRY REGLET MILLWORK CLEAT SYSTEM. AT OUTSIDE CORNERS OF LAMINATE PANELS, PROVIDE FRY REGLET 64219-4 MWROSC50 MILLWORK POST OUTSIDE CORNER WITH CLEAR ANODIZED FINISH. 24"X24" SUSPENDED ACOUSTICAL TILE [ACT] SYSTEM. SEE REFLECTED CEILING 95123-1 PLAN FOR SIZE & LOCATIONS 98433-7 AWP-1 ZINTRA ACOUSTICAL WALL PANEL ADHERED TO WALL WITH MANUFACTURER'S APPROVED ADHESIVE. PANELS TO BE TRIMMED TO FIT AS SHOWN IN ELEVATION, EDGES BUTTED TO EACH OTHER.

110000-3 OWNER FURNISHED MOBILE CASEWORK / FURNITURE.










REFLECTED CEILING PLAN - MAIN LEVEL - UNIT F SCALE: 1/8" = 1'-0"


GENERAL RCP NOTES
SEE GENERAL INFORMATION SHEET G0.2 FOR TYPICAL SYMBOLS. MECHANICAL AND ELECTRICAL DRAWINGS FOR ADDITIONAL COOR INFORMATION.
ALL SUSPENDED ACOUSTICAL CEILING TILE TO BE 11' 0 A.F.F., UNL OTHERWISE.
ALL ELEVATION MARKS MEASURED FROM DESIGNATED FINISH FLO SURFACE.
FACE OF ALL BULKHEADS TO BE PAINTED PNT-8, UNLESS NOTED O REFLECTED CEILING PLAN
BOTTOM OF ALL GYP. BOARD CEILING TO BE PAINTED PNT-8 WITH F UNLESS NOTED OTHERWISE ON REFLECTED CEILING PLAN


	REFLECTED CEILING PLAN KEYNOTE
42000-1	INFILL WALL WITH CMU TO MATCH EXISTING. PATCH WITH WH
95100-1	ACOUSTICAL CEILING BAFFLES SUSPENDED BETWEEN LINEAF
95123-4	4" PREFINISHED COMPASSO EDGE TRIM, OR EQUAL. PROVIDE CEILING OPENING FOR OH SECTIONAL DOOR.
95123-5	9" PREFINISHED COMPASSO EDGE TRIM, OR EQUAL. PROVIDE PERIMETER OF CEILING CLOUD.
95123-6	6" PREFINISHED COMPASSO EDGE TRIM, OR EQUAL. PROVIDE PERIMETER OF CEILING CLOUD.
110000-5	24X24 CEILING MOUNTED PROJECTOR PLATE. COORDINATE F WITH OWNER. SEE ELECTRICAL SHEETS FOR POWER/DATA IN
110000-12	STRUCTURE SUSPENDED OVERHEAD PROJECTOR, PROVIDE E POST MOUNT PROJECTOR STEM MOUNTED TO UNISTRUT SEC BOTTOM CHORD OF JOIST. COORDINATE FINAL LOCATION WIT ELECTRICAL SHEETS FOR POWER/DATA INFORMATION.
114000-7	NEW KITCHEN HOOD, SEE MECHANICAL
115213-1	STRUCTURE MOUNTED MOTORIZED PROJECTION SCREEN, 11 FORMAT WITH OWNER (HD OR WIDE).
233113-1	METAL TRIM TO MATCH VENT HOOD.
265100-1	LIGHT FIXTURE, SEE ELECTRICAL













4 F100 DINING - SOUTH SCALE: 1/4" = 1'-0"



									42000 	
90	0162-3	90162-3	00162-2	1	4200	0-9	9	D162-2	- 4 C	

	INTERIOR ELEVATION KEYNOTES
42000-1	INFILL WALL WITH CMU TO MATCH EXISTING. PATCH WITH WHOLE CMU
42000-9	NEW CMU AT NEW HM FRAME OPENINGS IN EXISTING WALL. DO NOT R BOTTOM COURSE. GROUT AND DOWEL NEW CMU INTO EXISTING BOTT SEE STRUCTURAL. MAINTAIN AND PROTECT EXISTING TERRAZZO BASE
62023-4	1-1/4" THICK MAPLE, EASED EDGES, CLEAR LAQUER FINISH. SECURED 2 RICHELIEU K-R650 KOLOSSUS HEAVY-DUTY ALUMINUM BRACKETS.
64116-1	SHOP FABRICATED PLASTIC LAMINATE FACED BASE CABINETS. CABINE LOCK CYLINDER ACCEPTING OWNER'S BEST 7-PIN CORE.
64219-2	SHOP FABRICATED FLUSH PLASTIC LAMINATE FACED PANELING. 1/2" F BOARD SUBSTRATE WITH PLASTIC LAMINATE FACE, REFER TO FINISH I LAMINATE SELECTION. SECURE LAMINATE PANELS TO SUBSTRATE US REGLET MILLWORK CLEAT SYSTEM.
64219-4	AT OUTSIDE CORNERS OF LAMINATE PANELS, PROVIDE FRY REGLET M MILLWORK POST OUTSIDE CORNER WITH CLEAR ANODIZED FINISH.
83313-1	MOTORIZED OVERHEAD COILING COUNTER DOOR, REFER TO SECTION SPECIFICATIONS.
90162-2	EXISTING TERRAZZO BASE TO REMAIN.
90162-3	NEW TERRAZZO BASE TO MATCH EXISTING
95100-1	ACOUSTICAL CEILING BAFFLES SUSPENDED BETWEEN LINEAR LIGHTS
98433-1	2" THICK SOUND-ABSORBING WALL PANEL WITH SQUARE EDGE. BASIS KINETICS NOISE CONTROL, INC. "HARDSIDE PANELS", MIN NRC 0.95. VE FABRIC: GUILFORD OF MAINE FR701 2100, COLOR: PEARL 481.
98433-3	2" THICK SOUND-ABSORBING WALL PANEL WITH SQUARE EDGE. BASIS KINETICS NOISE CONTROL, INC. "HARDSIDE PANELS", MIN NRC 0.95. VE FABRIC: GUILFORD OF MAINE FR701 2100, COLOR: STEEL GREY 471.
98433-7	AWP-1 ZINTRA ACOUSTICAL WALL PANEL ADHERED TO WALL WITH MAN APPROVED ADHESIVE. PANELS TO BE TRIMMED TO FIT AS SHOWN IN E EDGES BUTTED TO EACH OTHER.
104413-1	FIRE EXTINGUISHER CABINET, FULLY RECESSED. MOUNTING HEIGHT I REQUIREMENTS.
105113-10	NEW SINGLE TIER 12" WIDE X 60" HIGH X 12" DEEP METAL LOCKERS WI TOP.
110000-2	OWNER FURNISHED/CONTRACTOR INSTALLED TV / DISPLAY MONITOR. ROUGH-INS FOR POWER AND DATA. COORDINATE FINAL MOUNTING H OWNER.
110000-3	OWNER FURNISHED MOBILE CASEWORK / FURNITURE.
120000-2	OWNER PROVIDED AND INSTALLED FURNISHINGS.
123661-1	SOLID SURFACE COUNTERTOP. SEE FINISH PLANS & SCHEDULE FOR L TYPES. SEE A10. SERIES SHEETS FOR COUNTER HEIGHTS.
262416-1	ELECTRICAL PANELS, SEE ELECTRICAL
005400 4	




265100-1 LIGHT FIXTURE, SEE ELECTRICAL












BOH SERVING WEST

/ SCALE: 1/4" = 1'-0"


8







- LINE OF WALL



3




0 0


-


man

1


		(PNT-1)
		CWT-2
hunn	<u> </u>	





















	INTERIOR ELEVATION KEYNOTES
3000-8	SCHLUTER DESIGN LINE DECORATIVE BORDER PROFILE TO BE TOP EDGE OF EXPOSED TILE IN SERVING AREA.
3000-12	CWT-4 TO BE INSTALLED ON FRONT OF SERVING. BOTTOM EDG RECEIVE SCHLUTER ECK-E.
3000-13	CWT-5 & CWT-6 TO BE INSTALLED ON FRONT OF SERVING. BOT TILE TO RECEIVE SCHLUTER ECK-E.
3000-14	CWT-6 TO BE INSTALLED ON FRONT OF SERVING. BOTTOM EDG RECEIVE SCHLUTER ECK-E.
10000-2	OWNER FURNISHED/CONTRACTOR INSTALLED TV / DISPLAY MC PROVIDE ROUGH-INS FOR POWER AND DATA. COORDINATE FIN HEIGHT WITH OWNER.
23661-1	SOLID SURFACE COUNTERTOP. SEE FINISH PLANS & SCHEDULE

BE INSTALLED AT
GE OF TILE TO
TTOM EDGE OF
GE OF TILE TO
IONITOR.
FINAL MOUNTING
LE FOR
R HEIGHTS.





A10.2



	FINISH LEGEND
ACOUSTICA	L WALL PANEL
AWP-1	MDC WALL, ZINTRA ACOUSTIC PANEL, STYLE: DIAMONT, COLOR: CADET, SHEET SIZE: 9' X 4' X 1"
CARPET	
CPT-1	MILLIKEN, COLLECTION: REMIX REMASTERED, STYLE: BASS LINE, COLOR: BSL140-120 CUE UP
	WITH AZUL, SIZE: 1M X 1M, INSTALL: QUARTER-TURN
CERAMIC W	ALL TILE
CWT-1	DALTILE, COLLECTION: SHOWSCAPE: STYLE: REVERSE DOT, COLOR: CURRANT SH17, SIZE: 12" X 24", INSTALL: BRICK, GROUT: MAPEI KERAPOXY, COLOR: PEARL GRAY 5019
CWT-2	DALTILE, COLLECTION: COLOR WHEEL, STYLE: LINEAR, COLOR: ARTIC WHITE 0190, SIZE: 6" X
	18", INSTALL: BRICK, GROUT: MAPEI KERAPOXY, COLOR: PEARL GRAY 5019
CWT-3	DALTILE, COLLECTION: COLOR WHEEL, STYLE: LINEAR, COLOR: SUEDE GRAY 0182, SIZE: 6" X 18" INSTALL: BRICK_GROUT: MAPELKERAPOXY, COLOR: PEARL GRAY 5019
CWT-4	CDALTILE, COLLECTION: COLOR WHEEL MOSAIC, STYLE: STRAIGHT JOINT, COLOR: BLACK K111, SIZE: 1" X 6", INSTALL: VERTICAL, GROUT: MAPEI KERAPOXY, COLOR: PEARL GRAY 5019
CWT-5	DALTILE, COLLECTION: COLOR WHEEL RETRO, STYLE: 3D CUBE, COLOR: WATERFALL 0169,
	SIZE: 2" X 3". GROUT: MAPEI KERAPOXY, COLOR: PEARL GRAY 5019
CWT-6	DALTILE, COLLECTION: COLOR WHEEL MOSAIC, STYLE: HEXAGON, COLOR: CURRANT SH17, SIZE: 1.5", GROUT: MAPEI KERAPOXY, COLOR: PEARL GRAY 5019
0000	
CORNER GI CG-1	JARD ACROVYN, FS-20 ACROVYN 4000 CORNER GUARD, COLOR: MUSHROOM #305, INSTALLED FROM
	TOP OF BASE TO CEILING
FABRIC	
FAB-1	CARNEGIE, PATTERN: MAZE PRINT, COLOR: 6994 103, 54" WIDE
PAINT	
PAINT PNT-1	PPG, COLOR: FWCS SPECIAL UMBER, FINISH: GLOSS
PNT-2	WAYNE BLUE, PANTONE #283C, FINISH: GLOSS
PNT-3	PPG, COLOR: 1001-5 DOVER GRAY, FINISH: SEMI-GLOSS
PNT-4	PPG, COLOR: 1001-7 BLACK MAGIC, FINISH: FLAT
PNT-5	WAYNE RED, PANTONE #: TBD, FINISH: GLOSS
PNT-6	PPG, COLOR: 1007-6 COOL CHARCOAL, FINISH: GLOSS
PNT-7	PPG, COLOR: 1001-6 KNIGHT'S ARMOR, FINISH: SEMI-GLOSS
PNT-8	PPG, COLOR: 1001-1 DELICATE WHITE, FINISH: FLAT
PLASTIC LA	
PL-1	WILSONART, COLOR: RIVER CHERRY 7937-38, FINISH: FINE VELVET
QUARRY TII	
QT-1	DALTILE, COLLECTION: QUARRY TILE, COLOR: ARID GRAY 0Q42, FINISH: ABRASIVE, SIZE: 6" X 6", GROUT: MAPEI KERAPOXY, COLOR: BLACK 5010
QTB-1	DALTILE, COLLECTION: QUARRY TILE, COVE BASE Q3565, COLOR: ARID GRAY 0Q42, SIZE: 5" X 6"
QUARTZ	~~~~~~~ }
QZ-1	
QZ-2	CORIAN, COLOR: SMOKED QUARTZITE
	TILE FLOOR
RT-1	PATCRAFT, COLLECTION: ADMIX, COLOR: SEA URCHIN 00590, SIZE: 36" X 36"
RT-2	PATCRAFT, COLLECTION: ADMIX, COLOR: SCALLOP 00520, SIZE: 36" X 36"
RUBBER BA	
RB-1	TARKETT, TRADITIONAL 4" BASE, COLOR: 20 CHARCOAL
SOLID SURF	FACE
SS-1	NOT USED
SS-2	WILSONART, COLOR: CARBONE MARMO 9914SS
STAINED CO	DNCRETE
SC-1	PREP & CLEAN CONCRETE SURFACE, GRIND TO CLASS B FINE/SAND AGGREGATE, POLISH TO A
	LEVEL 1 400 GRIT FINISH - SATIN, STAIN WITH DYED PIGMENT, COLOR: TBD, SEAL WITH DENSIFIER & STAIN GUARD
SC-2	PREP & CLEAN CONCRETE SURFACE, GRIND TO CLASS B FINE/SAND AGGREGATE, POLISH TO A
	LEVEL 1 400 GRIT FINISH - SATIN, STAIN WITH DYED PIGMENT, COLOR: TBD, SEAL WITH











Renovation of Wayne HS Kitchen and Cafeteria <u>Pre-Bid Meeting Minutes – October 14, 2024</u>

I. Project Team

<u>Construction Manager</u> – Hagerman Inc. Chris
Freiburger, Director of Estimating
Office: (260) 424-1470 /email: <u>cfreiburger@hagermangc.com</u>
Courtney Boyd, Assistant Project Manager
Office: (260) 424-1470 /email: <u>cboyd@hagermangc.com</u>
Jacqueline Adams, Project Coordinator
Office: (260) 424-1470 /email: <u>jadams@hagermangc.com</u>
Jacob Buckland, Estimator
Office: (260) 424-1470 /email: <u>ibuckland@hagermangc.com</u>

Architect: Design Collaborative 200 E Main Street STE 600 Fort Wayne, IN 46802 Phone: (260) 422-4241 Contact Person: Molly Schultz, Associate Architect Email: <u>mschultz@designcollaborative.com</u>

Owner:

Fort Wayne Community Schools Contacts: Josh Summers, Capital Projects Coordinator & John Hudson, Coordinator of Design Controls Emails: joshua.summers@fwcs.k12.in.us ; john.hudson@fwcs.k12.in.us

II. Project Description

a. Renovations to include new a new prep kitchen, serving and dining area remodel. A test kitchen and café eating area will also be constructed along with modifications to the student services office.

III. Document Access

Bid documents can be obtained through Eastern Engineering and Building Connected.

IV. Bid Packages

See Section 01 11 00 – "Bid Items" for Bid Item breakdowns.

Bid Item #1- Masonry Bid Item #2- Steel Fabrication and Erection Bid Item #3- General Trades Bid Item #4- Glazing and Window Storefronts Bid Item #5- Metal Stud Framing, Drywall, and Ceilings **Bid Item #6- Drywall Finishes and Painting** Bid Item #7- Wall and Flooring Tile **Bid Item #8- Polished Concrete Bid Item #9- Fire Protection Bid Item #10- Mechanical** Bid Item #11- Electrical/Fire Alarm/Low Voltage **Bid Item #12- Kitchen Equipment** Bid Item #13- Doors, Frames, and Hardware **Bid Date:** November 7, 2024 Bid Time: 2:00 p.m. EST

V. BID FORM "See PDF in Bid Documents"

- Each contractor before submitting a bid shall examine the drawings carefully and read the specification and additional contract documents before submitting their bid. No allowance or exceptions will be made to a bidder because of lack of knowledge or understanding of these documents.
- Bidders shall <u>not</u> be allowed to submit and clarifications or exclusions lists as parts of their bid.
- All bid packets shall be endorsed with the title of work, the name of the bidder, bid item(s) number, and date of mailing or presentation.
- Bids shall be lump sum.
- ALL BIDDERS MUST BE PREQUALIFIED THROUGH HAGERMAN PRIOR TO BID DAY SUBMISSIONS.
- Fort Wayne Community Schools is <u>tax exempt</u> and as such, Indiana State Gross retail and Use Tax shall not be included in your bids.
- There is no wage scale requirement for this project.
- P&P bonds will be required for this project.
- The bid form will be updated to include a breakdown per project area by grouping below:
 - Serving/Kitchen/Test Kitchen-Café
 - Dining and Banquette Seating Areas
 - Guidance-Student Services

VI. Instruction to Bidders:

- Thursday, November 7, 2024 at 2:00 PM
- Email questions prior to bid to: Chris Freiburger at cfreiburger@hagermangc.com

Bids shall be hand delivered to:

Fort Wayne Community Schools C/O: Front Desk Attn: Jacob Buckland 1519 Catalpa St. Fort Wayne, IN 46802

- All bids <u>MUST</u> be received <u>NO LATER</u> than the date/time listed on the bid form.
- Bids Shall be held for 60 days.
- Copy of Bid Form located in the Front-End bid documents. Review all addendums as bid form is subject to revisions and will be posted in addendums.
- Last questions to be submitted by 2:00pm, Thursday, October 31, 2024.

VII. Schedule

•

- See the attached preliminary construction schedule.
 - Start and finish dates for areas cannot be adjusted. Any overtime required to meet these dates shall be included in the bid.

VIII. Badging and Security

• Please reference section 01 35 53 for information regarding badging and security. All personnel working onsite will be required to participate in the Safe Vendor Background Check information.

RFI Log

Project Nan	e Renovation of Wayne Kitchen and Cafeteria	Addendum No. 1	Publish to bidders on 01/17/2024
Project Addres	s 9100 Winchester Rd. Fort Wayne, IN 46819		
Archite	ct Design Collaborative		
Construction Manag	Pr Hagerman, Inc.	Bid Date	November 7, 2024 at 2:00pm

RFI #	Status	Description of Request	Received By	Responsible Party	Date Submitted	Due Date	Response Date	
001	Complete	Clarification of glazing scope in each package.	Hagerman	Hagerman	10/8/2024	10/15/2024	10/14/2024	 HM glass will be in BP #4 (Glazing Lites also BP #13 Storefront windows in BP #4 Breath Guards will be part of BP # 4.) 2" aluminum frame screen wall w
002								
003								
004								
005				2012				
006								

HAGERMAN

Response

ng), Wood Door Lites will be supplied by the wood door supplier (BP #13), FRP Door

P #12 – Food Service Equipment I will be in BP #4



					Dan					2024			1											20	25									_
.ine	Name	Duration	Start	Finish	Percent complete	Predecessors	4 11		25 2	9	December .6 <mark>1</mark> 23		30 (nuary 20	27 3		uary 17 124	3	Marc 10 17	ch 7 <u>1</u> 24	31		pril 4 <mark>1</mark> 21	28	M 12	ay 19 2	6 2	June 19 June		30 7	July 14	1 28	
_							-7 -	6 -5	-4 -3	3 -2	-1	1	2	3 4	5	6	7 8	9 1	10 11	12	13 14	15	16	17 18	19	20 21	22	23 24	25	26 27	28 2	30	31 3	32 33
1 V	Nayne HS Kitchen and Cafeteria Renovations	217d 6.5h	11/1/2024	9/3/2025								k	И									1			1	00000								#
2	Procurement	109d	11/1/2024	3/28/2025				M				1										ŧ.						-			; ,			4
3	Issue Subcontract/PO Agreements	5d	11/14/2024 *	11/20/2024			3				+	9										ļ												1
4	Permitting	15d	11/1/2024 *	11/21/2024								k r		1																				
5	Submit Product Data, Shop Drawings, and Material Samples to Owner/Architect	50d	12/2/2024 *	2/4/2025				м	5													ļ												
6	Material Procurement	20w	11/14/2024 *	3/28/2025			6																			+		+					+	4
7	Milestone Summary	158d 6.5h	12/23/2024	8/4/2025							7	1																						4
8	Mobilization		12/23/2024 *	12/23/2024							8	8	Ø							\square				É			\square							T
9	Phase 1- Serving and Prep Kitchen		12/23/2024	12/23/2024							9.	2										i		4			Π				i			
10	Phase 2- Test Kitchen and Cafe Seating		12/23/2024	12/23/2024							10	8										İ		Ø										T
11	Phase 3a- Warewashing/Electrical, Dining, and Guidance		12/23/2024	12/23/2024							11																							
12	Phase 3b- Banquette Seating		12/23/2024	12/23/2024							12	ļ.										i		Ø	i						1			i
13	Substancial Completion		8/1/2025	8/1/2025								8	Ø									İ											13 <	\$
14	Owner Occupy		8/4/2025	8/4/2025																		ļ		- Z	!						!		14	10
15	Construction	180d 6.5h	12/23/2024	9/3/2025							15	ř.												Ź				-						+
	NOTE: OVERTIME (2ND SHIFT) + WEEKEND MAY BE REQUIRED											2	Ø									ļ		ł										
16	Phase 1- Serving and Prep Kitchen	133d 6.5h	12/23/2024	6/30/2025							16	1	И									1		4							┡┿		+	+
17	Prep Kitchen	132d 6.5h	12/23/2024	6/27/2025							17				-		-		80,800				-	- 2		-		-					-	4
18	FWCS Remove Existing Equipment and Property	5d	12/23/2024 *	12/26/2024		68 SS					18											ł												
19	Mobilization	10d	12/26/2024	1/8/2025		18						19							+									+					+	ŧ
20	Build Temporary Partitions	2d	1/8/2025	1/10/2025		68 SS						8	2						-		+							+						4
21	Install Temp Power	3d	1/8/2025	1/13/2025		68 SS						4	2	1					-									-						4
22	GPRS Scan	2d	1/20/2025	1/21/2025		71 SS						ł		2	22				+		+							_					+	4
23	Demo of Existing Finishes/MEPF	15d	1/6/2025	1/24/2025		70 SS							23						-					4				_					+	4
24	Slab Demolition + Sawcutting	15d	1/14/2025	2/3/2025		72 SS -5d						8		24			-		-	\square	-	-				-	\square	-	\square	-		+	-	i
25	Structural Steel Modifications	10d	1/21/2025	2/3/2025		74 SS						ĺ		T	25		+		+		+					+		-		+				4
26	MEP Underground Demolition	5d	2/4/2025	2/10/2025		24									Ĩ	26			+		+	ļi		7		+	H	+		+			+	4
27	MEP Underground Rough-in	10d	1/31/2025	2/13/2025		73										27			+		+					+		-		+				ŧ
28	Verify Rough-in Locations	1d	2/17/2025	2/17/2025		76											28		-	H	+			Į.			Π							
29	Underground Inspection	3d	2/18/2025	2/20/2025		28											29		+		+	1				+		+		+				1
Viles	tone Appearances		1		1			i			i	1			P		i	<u>'</u>		<u> </u>	1	ŀ				i	<u>i </u>	ł		i	•			
0																																		
	or: Courtney Boyd Start Dat	te: 11/1	/2024																	Su	mmary	Task					Ta	sk						d Buffer

Run Date: 11/1/2024 Page: 1



Milestone



31 32 33	Name Prep for Slab Pourback Slab Infill Lay Block Walls Install Hollow Metal Frames Complete Exterior Masonry Window Modifications	Duration 3d 4d 10d	Start 2/18/2025 2/21/2025	Finish 2/20/2025	complete	Predecessors	11 18					30 6	13 20	0 27	3 1	10 17	24 3		17 24	31								23 30			28 4	11
31 32 33	Slab Infill Lay Block Walls Install Hollow Metal Frames	4d		2/20/2025			-0 -J	-4 -	3 -2	-1	1	2 3	3 4	5 6	7		10 1	12	13 14		16 1	18	19 20	21	12 23	24 2	20	27 28	29 3	0 31	32 3	
32 33	Lay Block Walls Install Hollow Metal Frames	4d 10d	2/21/2025			28										30	\vdash			ł												Τ
33	Install Hollow Metal Frames	10d		2/26/2025		30										31				ΗI			i					i			i i	Τ
			2/27/2025	3/12/2025		31											32			-		Ø	i I					ļ				
34	Complete Exterior Masonry Window Modifications	3d	3/13/2025	3/17/2025		32												33	╞┼╴				1								7	Τ
		3d	3/13/2025	3/17/2025		32												34	\vdash	-												Τ
35	Install New SF Windows	2d	3/18/2025	3/19/2025		34												35	1 +	T.											7	
36	Block Fill CMU Walls	3d	3/18/2025	3/20/2025		34												36	1-	+			÷i									
37	Install Glazing	2d	3/21/2025	3/24/2025		36													37	Li Tr											7	Τ
38	MEPF In-Wall Rough-in	10d	3/13/2025	3/26/2025		32												38		\parallel			-	\square					H			
39	Prime and Paint Walls + Hardlid Ceiling/Bulkheads	5d	3/21/2025	3/27/2025		36													39													
40	Frame Chase Walls	1d	3/31/2025	3/31/2025		85 SS													4	ю —					-					-	H	
41	Drywall Hang + Finish at Chase Walls	3d	4/1/2025	4/3/2025		40														41			+								7	
42	Install Ceiling Grid	7d	3/28/2025	4/7/2025		39													42		\vdash		+	H								
43	MEPF Overhead Rough-in	10d	3/27/2025	4/9/2025		38													43				+	\square						-	H	Τ
44	MEPF Overhead Inspection	3d	4/10/2025	4/14/2025		43														i	44		-					-			7	
45	Drop ACT Pads	5d	4/8/2025	4/14/2025		42					2									4											7	
46	MEPF Final Fixture Install	10d	4/4/2025	4/17/2025		42 SS 5d														46		\blacksquare			+							
47	Install Quarry Tile + Base	5d	4/18/2025	5/1/2025		46															47	1		\square		Η						
48	Specialties + Lockers + Misc. Accessories	3d	5/2/2025	5/6/2025		47																	48								7	Τ
49	MEPF Final Trim Install	5d	5/2/2025	5/8/2025		47														i			49							-	7	
50	Set Kitchen Equipment	6d	5/2/2025	5/9/2025		47														į			50	\vdash			-	į				Τ
51	Doors and Hardware	2d	5/12/2025	5/13/2025		50																	51	1						-		
52	Pre-Punch	2d	5/14/2025	5/15/2025		51																		52						+		Τ
53	Final Hook-up/Connection for Serving Equipment	7d	5/12/2025	5/20/2025		50														i			53					-				
54	Punchlist Corrections	5d	5/16/2025	5/22/2025		52														Ì			i	54							Hi	
55	Ansul Hood Certification for Kitchen Hood	3d	5/21/2025	5/23/2025		53														Ì			i	55				-ļ			ļ	
56	Construction Clean	3d	5/23/2025	5/27/2025		54																	-		6							
57	Equipment Start-up/Programming	7d	5/26/2025	6/3/2025		55																			57				+			
58	Fire Alarm + Sprinkler Test	3d	6/4/2025	6/6/2025		57														i.					5	8		i	\square			
59	Final Clean	3d	6/9/2025	6/11/2025		58														į.						59				•	L	\downarrow
	ne Appearances Start Milestone																			!			!									
	: Courtney Boyd Start Dat te: 11/1/2024 Finish Da Data Dat	te: 9/3/	/2025															1 H	ummary ammocl xpandeo	k Task					Task Progre Critica	essed Ta	sk				Buffer	



					Percent		No	wember		2024	Dere	ember			January			February			March			Apr	202	15		May			h	ne			July			August	_
Line	Name	Duration	Start	Finish	complete Pre	edecessors		18	25 2		16	23	30	6	13 20	27	3 10 7	17	24		0 17	24		14	21	28 5	5 12	2 19	26	2	9	16 2	3 30	7	14		28 4	11	
60	Final + Health Inspections	3d	6/12/2025	6/16/2025		59	-/ -	0 -5	-7	-5 -2	-1		_			5 0		0 9	10	11	12 1.	14	13	10 1	Ž	15	20 2	1 4	2 23		60			5 25		4	32		-
61	Final Punch	1d	6/17/2025	6/17/2025		60						ł											i					T			61	H	i	\mp	F	H	1	T	
62	Punchlist Corrections	5d	6/18/2025	6/24/2025		61																	i		1		+	╈			6	2	H	+	\vdash	F	-	1	
63	Equipment Training	2d	6/23/2025	6/24/2025		62 SS 3d						1									1		ļ	1	Ø		+	╈				63	Ļ	+	\vdash	Ħ	-	1	
64	Owner Furniture Move-in	3d	6/25/2025	6/27/2025		63				1											1			1	Ź		+	╈				64		ŧ	ŧ	긐	1	1	
65	Serving Area	133d 6.5h	12/23/2024	6/30/2025							65	C													1		-	-	-	-				ŧ	F	≓	4	+	
66	Mobilization	15d	12/23/2024 *	1/8/2025							66												i		Ø			T					i	T	Π	Π	Ť	T	
67	Remove FWCS Existing Equipment and Property	15d	12/23/2024 *	1/8/2025		66 SS					67																	T					i	T	Π	\square	1	T	
68	Build Temporary Partitions	2d	1/8/2025	1/10/2025		67						ł		68									-		Ű								ļ			\square	1		
69	Install Temp Power	3d	1/8/2025	1/13/2025		67						4		69 1											12		+	Ŧ						Ŧ	=	\exists	1		
70	Demo of Existing Finishes/MEPF	10d	1/6/2025 *	1/17/2025		68							7	0																			ł						
71	GPRS Scan	1d	1/20/2025	1/20/2025		70						1			71				-				i		Ø								i						
72	Slab Demolition + Sawcutting	5d	1/21/2025	1/27/2025		71						2			-5d 72		\square	_					ļ					Τ					ļ	Τ		\square	1		
73	MEP Underground Demolition	3d	1/28/2025	1/30/2025		72						4				73							!		Ø			Τ					!			\square			
74	Structural Steel Modifications	10d	1/21/2025	2/3/2025		72 SS						ł			74		\vdash	_			+			+			+	+				-		+	F	H	-		
75	MEP Underground Rough-in	10d	1/31/2025	2/13/2025		73						4				75					-				Ø								Ì			\square			
76	Verify Rough-in Locations	1d	2/14/2025	2/14/2025		75						ł					7	6			+	4	i		4								i						
77	MEP Underground Inspections	3d	2/17/2025	2/19/2025		76												77			+	+		+			÷	÷	+	-		+	1	÷	F	\exists	4	T	
78	Prep for Slab Pourback	3d	2/17/2025	2/19/2025		76						4						78			+	+1			Ø			T					!			\square	1		
79	Slab Infill	2d	2/20/2025	2/21/2025		78						1						79			+	H														\square			
80	Lay Block Walls	10d	2/24/2025	3/7/2025		79						1						8	0		+	-		-	4			Τ					i		\square	\square	1		
81	Install Hollow Metal Frames	2d	3/10/2025	3/11/2025		80						ł								81	┡			+			4	Ŧ						Ŧ	=		=		
82	Block Fill CMU Walls	7d	3/10/2025	3/18/2025		80						4								82				+			干	Ŧ		-		+		Ŧ	\square	\exists	4		
83	MEPF In-Wall Rough-in	15d	3/3/2025	3/21/2025		80 -5d						ł							83			-		-		H							-			\square			
84	MEP In-Wall Inspection	3d	3/24/2025	3/26/2025		83															8	4	-				+	Ŧ						Ŧ	\square	\exists	4		
85	Frame Bulkheads	3d	3/31/2025	4/2/2025		87 SS						ě										85		+				ıŢ					ł	Τ		\square			
86	MEPF Overhead Rough-in	15d	3/17/2025	4/4/2025		83 SS 10d															86						+	-					į						
87	Install RAFT Ceiling Supports	6d	3/31/2025	4/7/2025		86 SS 10d						4										87	-	+			+	-					ļ	Τ		\square	1		
88	MEPF Overhed Inspection	3d	4/7/2025	4/9/2025		86						8											88	┡			+	Ŧ		-		+		Ŧ	=		4		
89	Drywall Hang + Finish at Hardlid Ceilings + Bulkheads	7d	4/3/2025	4/11/2025		85																	89				+	+	-										
										+					+	+		+						+			+	+			\square	\uparrow	ļ	+	\square	\square	Ť	+	-
	tone Appearances							- 1														1	·			<u> </u>													
			1														_						la		_		_	_											_
	or: Courtney Boyd Start Da pate: 11/1/2024 Finish Da																					mary T imock 1							Task Progr		l Task						Buffe	er Task	:
Page:																						anded							Critic				٠				Mile		
		-																																					



ine	Name	Duration	Start	Finish	Percent	redecessors	vember	 2024	Decembe			Janua		Febr		Ma	arch	I		April	2025	1	May		1	June		1	Jul			Au
		Durution	otait		complete ^r		18 5 -5		16 23 -1	1	30 6 2		7 3		24 3 10 11	10	17 24 13 1	4 1	16	14			12 1 21		2	9 16 25 2	23 16 27	30 7 28			28 32	
90	Prime and Paint Walls + Hardlid Ceiling/Bulkheads	7d	4/3/2025	4/11/2025		89 SS												90	r					┥								
91	Lay Wall Tile	7d	4/14/2025	4/29/2025		90				2	Ø							ļ	91		$\frac{1}{7}$	<u> </u>	\square		+			!			!	
92	Install PLAM for Raft Ceiling	6d	4/17/2025	5/1/2025		91 SS 3d				4										92				+	+	+	<u> </u>		+	+	H	
93	Install Ceiling Grid + ACT	12d	4/14/2025	5/6/2025		90				ł									93				\square	+							H	
94	Install Resilient Tile Flooring + Base	5d	4/30/2025	5/6/2025		91				ł								ł			X94					•		i			i	
95	MEPF Final Device Install	10d	4/28/2025	5/9/2025		93 SS 5d				1	9							į			95											L
96	Set Kitchen Serving Equipment	7d	5/7/2025	5/15/2025		94												!			4	96		+			1	!			!	L
97	Install Doors and Hardware	3d	5/16/2025	5/20/2025		96				ľ.													97	⊢								L
98	Install Tile at Kitchen Serving Equipment	5d	5/16/2025	5/22/2025		96					1							l			4		98					i			H	L
99	MEPF Final Trim Install	5d	5/16/2025	5/22/2025		96				Į.								ļ					99							t	H	L
00	Final Hook-up/Connection for Serving Equipment	7d	5/16/2025	5/26/2025		96												ļ			4		100								ļ	L
01	Install Solid Surface at East/West Counter	3d	5/23/2025	5/27/2025		98				1								-												t	1	L
02	Install Overhead Doors	5d	5/21/2025	5/27/2025		97				8											7		102								H	L
03	Equipment Start-up/Programming	7d	5/27/2025	6/4/2025		100				2											4			103					1		i	
04	Fire Alarm + Sprinkler Test	5d	6/5/2025	6/11/2025		103												i							104			ŀ	+		i	L
05	Final + Health Inspections	3d	6/12/2025	6/16/2025		104												ĺ			4				1	05		İ			ļ	L
06	Install Specialty Finishes (TVs, Signage, Etc)	3d	6/17/2025	6/19/2025		105				Ĭ.								-								106	-			H		L
07	Equipment Training + Owner Move-in	7d	6/20/2025	6/30/2025		106															4					10	7				H	L
08	Phase 2- Test Kitchen and Cafe Seating	84d	3/28/2025	7/30/2025						ł							10	8			Ź	1						I			H	L
109	Test Kitchen/ Cafe Seating	84d	3/28/2025	7/30/2025													10	9			4	!						!				
10	Remove FWCS Property	2d	3/28/2025 *	3/31/2025						1							11	0				!									!	L
11	Install Temp Partition in Main Cooridor	2d	3/28/2025	3/31/2025		110 SS											11	1												$\frac{1}{1}$		L
12	Install Temp Power	1d	4/1/2025	4/1/2025		110				2	1							112			4											L
13	Demo of Existing Finishes/MEPF	3d	4/2/2025	4/4/2025		112				1	Ø							113	ŀ		7	<u>i </u>						i			li	L
14	GPRS Scan	1d	4/7/2025	4/7/2025		113												11	4 H		4										Li	L
15	Sawcut and Remove Concrete	3d	4/8/2025	4/10/2025		114				ł								1	15	╞		<u>.</u>		\pm	\vdash		+			+		L
16	Thickened Slab Modifications	3d	4/8/2025	4/10/2025		114												1	16	╞				\pm						+		
17	MEP Underground	5d	4/8/2025	4/14/2025		114				Į.	Ø							1	17													L
18	Slab Infill	2d	4/15/2025	4/16/2025		117												l	11		4		\square								li	L
19	MEP Underground Inspections	3d	4/15/2025	4/17/2025		117				Į.		_						ļ	11	9				+							Ħ	L
										2	Ø							-			7	!						!				L
Vilest	one Appearances Start Milestone 																															
-	r: Courtney Boyd Start Dat	te: 11/1	/2024				 									s	ummar	y Task						Task								
	ate: 11/1/2024 Finish Data Data		/2025													H	lammo	ck Tasl	c.					Prog	ressed	Task					Buf	fer 1



1 F 2 L 3 C 4 M	Name Install Hollow Metal Frames Frame Stud Walls+Hardlid Ceilings/Bulkheads ay Block Walls Drywall Hang + Finish MEP In-Wall Rough-in MEP In-Wall Rough-in Inspection Block Fill CMU Walls	Duration 3d 4d 5d 3d 7d	Start 4/17/2025 4/29/2025 4/29/2025 5/5/2025	Finish 4/28/2025 5/2/2025 5/5/2025	complete	118 120		25 2	-1		30 6		20 27 5 6	3 10 5 7		24 3 10 1		7 24 13 14	15 1	6 17	21 28 18 19			26 2 23 2						28 4 32 3
1 F 2 L 3 C 4 M	Frame Stud Walls+Hardlid Ceilings/Bulkheads .ay Block Walls Drywall Hang + Finish MEP In-Wall Rough-in MEP In-Wall Rough-in Inspection	3d 4d 5d 3d 7d	4/29/2025 4/29/2025	5/2/2025 5/5/2025		120			-	Å		<u> </u>		· · ·						v	<u> </u>									
2 L 3 C 4 N 5 N	Ay Block Walls Drywall Hang + Finish MEP In-Wall Rough-in Inspection	4d 5d 3d 7d	4/29/2025	5/5/2025				+ +												120	H					1 1				
3 C 4 N 5 N	Jrywall Hang + Finish MEP In-Wall Rough-in MEP In-Wall Rough-in Inspection	5d 3d 7d				400			\square	4									1		121		+	H	+	+		H	-	H
4 N 5 N	IEP In-Wall Rough-in IEP In-Wall Rough-in Inspection	3d 7d	5/5/2025	= = 10000	I I	120				1	2										122	h۱ 🗄					i			
5 N	MEP In-Wall Rough-in Inspection	7d		5/7/2025		121				1											12		+		+				-	4
			5/2/2025	5/12/2025		122 SS 3d				2	Ø										124		•							
6 B	Block Fill CMU Walls	3d	5/13/2025	5/15/2025		124				4												125			+	\square			-	H
		3d	5/13/2025	5/15/2025		124				ĺ									i		Z	126					i			i
7 Ir	nstall Overhead Grill Supports	2d	5/16/2025	5/19/2025		126																	27 H				i			İ
B N	MEPF Overhead Inspection	3d	5/16/2025	5/20/2025		125				Ě												1 11	28		\pm					-
9 N	MEPF Overhead Rough-in	7d	5/13/2025	5/21/2025		124																129			\pm					Ħ.
0 Ir	nstall Glazing	5d	5/20/2025	5/26/2025		127				1													130	ŀ I			i			i
1 P	Prep Floor for Polished Concrete	2d	5/27/2025	5/28/2025		130																	13	14						Ĺ
2 Ir	nfill Terrazzo/Patching at Corridor	2d	5/29/2025	5/30/2025		133 SS				1									ļ.					132	\pm					1
3	Grind + Stain + Polish Concrete	5d	5/29/2025	6/4/2025		131																		133						
4 P	Prime and Paint Walls + Hardlid Ceiling/Bulkheads	4d	6/5/2025	6/10/2025		133																		134	4		ľ			
5 Ir	nstall Vinyl Base	2d	6/11/2025	6/12/2025		134				2															135	╞┼┼				1
6 Ir	nstall Overhead Grill	2d	6/11/2025	6/12/2025		134				8											Ø !				136	H	ļ			
7 Ir	nstall Wall Tile	3d	6/11/2025	6/13/2025		134				4															137					1
B Ir	nstall Ceiling Grid + ACT	3d	6/11/2025	6/13/2025		134				Č															138				-1	
9 Ir	nstall Corner Guards	1d	6/13/2025	6/13/2025		140 SS													i L						139	H				Ħ
0 0	Doors and Hardware	2d	6/13/2025	6/16/2025		136				Ĩ															140					H
1 N	MEPF Final Fixture Install	5d	6/13/2025	6/19/2025		138 SS 2d																			141	۱.	1			
2 S	Set Kitchen Equipment	5d	6/13/2025	6/19/2025		136				ł															142					
3 P	Pre-Punch	1d	6/20/2025	6/20/2025		142													i							143			+	
4 N	MEPF Final Trim Install	5d	6/20/2025	6/26/2025		141				Į.									i L							144				Ħ.
5 F	Final Hook-up/Connection for Serving Equipment	5d	6/20/2025	6/26/2025		142													!		2					145				
6 P	Punchlist Corrections	5d	6/23/2025	6/27/2025		143				1																146				
7 A	Ansul Hood Certification for Kitchen Hood	2d	6/27/2025	6/30/2025		145				1																1	47		+	Ħ.
B C	Construction Clean	2d	6/30/2025	7/1/2025		146				4									i L						\perp		148		+	己
9 E	Equipment Start-up/Programming	5d	6/27/2025	7/3/2025		145									_		$\left \right $	_				$\left \right $	_		\downarrow		49			ļļ
	Appearances Start Milestone																													
hor: (Courtney Boyd Start Dat e: 11/1/2024 Finish Da																	mmary T mmock 1		(Task Progress	sed Tas	k				Buffe



			01.1	-	Percent		Ν	Vovembe	r	2024		ecember		1	January	v	1	Februa	v		March			April	2025	1	Мау			Jur	ne			July	_	_	Augu
.ine	Name	Duration	Start	Finish	complete	Predecessors	4 1	1 18	25			23		30 6		20 27	3	10 17	24	3 1	17	24 3	1 7	14	21 28	5	12 1	9 26	2	9 1	16 23	30	7	14 2	21 28	28 4	1
50	Fire Alarm + Sprinkler Test	2d	7/4/2025	7/7/2025		149	-7	-0 -	J	-5	-2 -1		ł		C	<u> </u>	/	0	9 10	11	12 13	19	15 10	1/		5 20	21	<u> </u>) 24	23	20 2		0 1	30	<u>, 11</u>	32	20
51	Install Specialty Finishes (TVs, Signage, Etc)	2d	7/8/2025	7/9/2025		150							4	A											4	i			T	\square		1	151	븝	4	4	
52	Final Clean	2d	7/8/2025	7/9/2025		150							Ĭ	Ø											Ø				T	\square		1	152		T	1	
53	Final + Health Inspections	2d	7/10/2025	7/11/2025		152								4											4	!				\square		1	153	۶.		1	
54	Final Punch	1d	7/14/2025	7/14/2025		153							8	8											Í					\square			154	i III			
55	Punchlist Corrections	10d	7/15/2025	7/28/2025		154								4											4					\square			15	5		H I	
56	Equipment Training	1d	7/29/2025	7/29/2025		155								8											9							Ì			156	hi	
57	Owner Furniture Move-in	1d	7/30/2025	7/30/2025 *	r	156																			4							ļ			157	Í	
58	Phase 3b- Banquette Seating	54d	5/22/2025	8/5/2025																								8								-	l
159	Banquette Seating	54d	5/22/2025	8/5/2025																					4		15	9	+			+		-	-	+	L
160	Demo of Existing Finishes/MEPF	3d	5/22/2025 *	5/26/2025									1														16	0				ĺ					
161	Masonry Infill	4d	5/27/2025	5/30/2025		160																			7			161		\square		\pm	-			i	
62	Install Block Wall	5d	5/27/2025	6/2/2025		161 SS								1														162		\square	-	ݱ	+			!	
163	Install Hollow Metal Frames	2d	6/2/2025	6/3/2025		161																			4			16	,3 1 -	\square	+	╈	\pm	\blacksquare	\pm	-	_
64	Block Fill	2d	6/3/2025	6/4/2025		162							1	1														1	164	\exists	+	╈	\pm	\exists	╪	╈	ł
65	MEP In-Wall Rough-in	5d	5/30/2025	6/5/2025		162 SS 3d							8												4			165			+	╈	\pm		\downarrow	1	_
166	Install Masonry Jambs	3d	6/4/2025	6/6/2025		163								Ø												i L			166	E		茾	\pm	╞	╪	=	1
67	MEP In-Wall Inspection	3d	6/6/2025	6/10/2025		165								Ø											4				167		+	ݱ	+	╘	\downarrow	4	_
68	Frame Bulkheads + Framed Walls	3d	6/11/2025	6/13/2025		167								9											4				16	.68		⋕	\pm	=	╪	⋕	1
169	MEPF Overhead Rough-in	5d	6/11/2025	6/17/2025		167								Ø											7	Ļ			16	.69		╈	+	╞	┥	4	_
70	MEPF Overhead Inspection	3d	6/18/2025	6/20/2025		169																			4				\perp	170	0	╪	+	\square	1	1	_
171	Hang Drywall and Finish Hardlid Ceilings/Bulkeads/Walls	4d	6/23/2025	6/26/2025		170								Ø											4						171	₽	+	+	+	-	
172	Install Screen Walls	3d	6/27/2025	7/1/2025		171								1											4					\square	17	/2	Ŧ	\square	극	<u>_</u>	1
73	Grind/Prep Concrete Slab	2d	6/30/2025	7/1/2025		278 SS																			4						17	173	\pm		=	1	1
174	Polish Concrete Slab	3d	7/3/2025	7/7/2025		279 SS																			4							174			=	- - 	1
75	Seal Concrete Slab	1d	7/9/2025	7/9/2025		280 SS																										Ì	175			1	
176	Paint Hollow Metal Frames	3d	7/10/2025	7/14/2025		177 SS								1																			176				
177	Prime and Paint Walls	4d	7/10/2025	7/15/2025		175																			7								177				
78	Install MEPF Final In-Wall Fixtures	2d	7/16/2025	7/17/2025		177	\square							9											4				\perp	\square		ļ	1	78	\pm	⋕	1
79	Install Plastic Laminate Booths	3d	7/15/2025	7/17/2025		176																\square				i 📙			\perp	\square		ļ	17	79	\square	1	
																									4											!	
	one Appearances Start Milestone																																				
		ate: 11/1																_				nary Ta						Tas				_			,	Buffe	
in D	ate: 11/1/2024 Finish D	Date: 9/3	/2025																			nock Ta nded Ta						_	gressed								
ge:	b Data Da	ate: 10/1	6/2024																		cxba	naeu la	JN.					Criti	ical Tas	ĸ		٠			-	Mile	300



					Percent		New		20		December		1	1			Februa			Marrie				20	25		Mari			har						
Line	Name	Duration	Start	Finish	complete Predece	ssors	4 11	mber 18 25		9 16	December 23	í	80 6	Janua 13	20 27		Februa 10 11	7 24			24		7 1	pril 4 <mark>1</mark> 21		5 12	May 19				23		July 14	21	28 4	
180	Install Ceiling Grid	3d	7/16/2025	7/18/2025		177	-7 -6	-5 -4	-3	-2 -	-1		2 3	4	5	6 7	8	9 10) 11	12	13 14	15	16	17 18	19	20 2	1 12	23	24 2	25 26	6 27	28	29 30 180	31	32	33 1
181	Install Baffle Ceiling	3d	7/16/2025	7/18/2025	1	30 SS							1	+							+						+		+	+	+		181		H	+
182	Install MEPF Final Trims	2d	7/18/2025	7/21/2025		179							Ø	┢					+		+	i i			i		+	\square	+	+		ill	182			1
183	Install Misc. Accesories Corner Guards, Fire Extinguisher Cabinets, TVs/Display Monitors	2d	7/18/2025	7/21/2025		179																			-								183			+
184	Install Rubber Base	3d	7/18/2025	7/22/2025		179																i I			i								184			1
185	Install Acoustical Panels	3d	7/18/2025	7/22/2025		179																İ.											185			1
186	MEPF Install Final Overhead Fixtures	4d	7/18/2025	7/23/2025	181	SS 2d																!			!								186			1
187	Install Doors and Hardware	3d	7/22/2025	7/24/2025		183																											18	7		
188	Pre-Punch	1d	7/25/2025	7/25/2025		187																		1										188		
189	Final Punch	1d	7/28/2025	7/28/2025		188							8									i I			i							i		189		
190	Punchlist Corrections	3d	7/29/2025	7/31/2025		189																		4										190		
191	Final Clean	1d	8/1/2025	8/1/2025		190																		Z	!										191	
192	Health + Final Inspections	2d	8/4/2025	8/5/2025		191																		-											192	
193	Phase 3a- Dining and Guidance	129d	1/31/2025	8/6/2025											19	3						1		Ż	1		-									٩
194	Electrical Closet/Warewashing	97d	1/31/2025	6/23/2025											19	4																	Ħ			1
195	Temp in Electrical Panel for Serving and Prep	5d	1/31/2025	2/6/2025									1		19	5			+								Ŧ			+	-		F			=
196	Install Temp Wall at Warewash	2d	3/28/2025 *	3/31/2025									8								196				!							!			!	Τ
197	Remove all Owner Provided Equipment	2d	3/28/2025 *	3/31/2025		196								Τ							197			Ø			Τ									Τ
198	Demo Existing MEPF/Finishes	3d	4/1/2025	4/3/2025		197							8								19	8					+	+								
199	GPRS Scan	2d	4/4/2025	4/7/2025		198																199	\vdash	-#	÷		+	$\left \cdot \right $				i			i	
200	Sawcut Slab	4d	4/8/2025	4/11/2025		199																200					+		4						ļ	
201	MEP Underground Rough-in	4d	4/14/2025	4/17/2025		200																	201				+		-							
202	MEP Underground Inspection	2d	4/18/2025	4/28/2025		201																	20	02			\pm						E			╡
203	Slab Infill	2d	4/18/2025	4/28/2025		201																	20	3			+			-					i	
204	Lay Block Walls	4d	4/29/2025	5/2/2025		203																		20			\pm		\pm							
205	MEPF Wall Rough-in	3d	5/5/2025	5/7/2025		204																			205		\pm				-	<u> </u>			ļ	
206	Block Fill	3d	5/5/2025	5/7/2025		204																			206		\pm						F			=
207	MEPF Overhead Rough-in	2d	5/8/2025	5/9/2025		205																			2	07	\pm				+					
208	MEP In-Wall Inspection	3d	5/8/2025	5/12/2025		205																		Į		08	\pm						E			=
209	MEPF Overhead Inspection	3d	5/12/2025	5/14/2025		207																		Į		209	⊢								j	
																						!			!											
Milesto	one Appearances Start Milestone	_	_	_					_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
utho	r: Courtney Boyd Start Da	te: 11/1	/2024														_			Su	nmary	Task						Task								
un Da	ate: 11/1/2024 Finish D	ate: 9/3	/2025																		mmock							Progre		ask					_	er Tasl
ige:	7 Data Da	te: 10/1	6/2024																	Exp	banded	Task						Critica	Task		•	•			Mile	stone



ine	Name	Duration	Start	Finish	Percent	Predecessors	lovember		2024	Decem			anuary		bruary	Marc			April	2025	1,	May	, I,		June			July		Au
					complete			25 2 -4		16 2.	<u>3</u> 1	30 6 2	320 45					31 7 15 1		21 28 18			26 2 23 2					14 21 30 31		
10	Paint Exposed Ceiling in Electrical Closet	2d	5/15/2025	5/16/2025		209					1							ΕΓ			2	10				井			Т	
211	Install Resilient Tile Flooring and Rubber Base at Electrical Room	1d	5/19/2025	5/19/2025		210												ļ				211						\pm		E
212	Prime and Paint Walls	3d	5/19/2025	5/21/2025		210																212		-	\square	무	ЪП			Γ
213	MEPF Final Device Install	2d	5/22/2025	5/23/2025		212					1											213		-		구	\square	+	Ŧ	ſ
14	Install Quarry Tile and Base in Warewashing	2d	5/22/2025	5/23/2025		212					2											214		-	\square	+	H			Γ
15	Install Grid/ACT	3d	5/22/2025	5/26/2025		212					4											215	+			₽	冊	干	=	F
16	MEPF Final Trim	3d	5/26/2025	5/28/2025		213					2										!	21	6	_		₽	#	干	干	Ę
17	Install Overhead Coiling Counter Door + Stainless Steel Accessories	3d	5/26/2025	5/28/2025		214					ć											21	7							
18	Install Dishwasher and Equipment	3d	5/29/2025	6/2/2025		217					1							<u>i</u> L					218			\pm		⊣		
19	Install Doors and Hardware	2d	6/3/2025	6/4/2025		218												!					219	⊨		╨		-		
20	Equipment Startup	3d	6/3/2025	6/5/2025		218																	220			∄		\pm	╧	늰
21	Pre-Punch	1d	6/5/2025	6/5/2025		219																	221	╟		<u> </u>		+		
22	Punchlist Corrections	3d	6/6/2025	6/10/2025		221					2							i I		Ø			22	2		\pm		\pm	1	
23	Construction Clean	1d	6/11/2025	6/11/2025		222					Ĩ													223		÷		\pm	-	
24	Final Punch	1d	6/12/2025	6/12/2025		223												1			!			224		╇		\pm	+!	
25	Punchlist Corrections	3d	6/13/2025	6/17/2025		224					Į.													225		╬		\pm	+	
26	Final Clean	1d	6/18/2025	6/18/2025		225																		2	26	╓		+	\pm	
27	Health + Final Inspections	2d	6/19/2025	6/20/2025		226					1							i I		X	i				227	+			+	Η
228	Equipment Training	1d	6/23/2025	6/23/2025		227												li I.							228	∄	₩	\pm	\pm	þ
29	Guidance (Need RM # for Permit)	51d	5/22/2025	7/31/2025																	!	229						-	-	ł
30	Install Temp Barrier at End of Hall	2d	5/22/2025 *	5/23/2025							ł											230								
31	Demo of Existing Finishes	3d	5/26/2025	5/28/2025		230																23	1 1							
32	MEPF Demo	4d	5/26/2025	5/29/2025		231 SS					ł							i I				23	2							
33	Infill Masonry Jambs	3d	5/30/2025	6/3/2025		235 SS																	233			\pm	卅	\pm	\pm	1
34	Frame Stud Walls	3d	5/30/2025	6/3/2025		235 SS					1												234	H						
35	Infill Openings (Masonry)	5d	5/30/2025	6/5/2025		232																	235	H						
36	Install Hollow Metal Frames	5d	5/30/2025	6/5/2025		235 SS																	236			∄	卅	\pm		
37	MEPF Wall Rough-in	3d	6/3/2025	6/5/2025		234 SS 2d												L I					237	ŀ			Ш			
38	MEP In-Wall Inpection	2d	6/6/2025	6/9/2025		237												!					+ +	8 1		i	Ш			
39	MEPF Overhead Rough-in	3d	6/10/2025	6/12/2025		238								_										239			Щ	\perp		
	one Appearances Start Milestone										M									H	:								<u> </u>	
	r: Courtney Boyd Start Dat ate: 11/1/2024 Finish Da B Data Dat	ate: 9/3,	/2025													Ha	mmary mmock panded	Task					Task Progress Critical T		k	•			But	



					Percent		Nor	vember		2024	Decemb	her	1	Januar	v		February		м	arch		April	2025		May			June			July		Δι	gust
Line	Name	Duration	Start	Finish	complete Pre	edecessors	4 11	18	25 2	9 -3 -2	16 23		30 6	13	20 27		10 17	24 3 10	10	17 24		14	21 2	8 5	12 1	26	2 9	16	23 3	10 17	14		3 4	11
240	MEP Overhead Inspection	2d	6/13/2025	6/16/2025		239	-/ -(-4	-5 -2	-1		Í	5 4	3 0	/	0 9	10		15 1	CI †	10 1/		19 20	21	2 25		40 4 1	2/	20 29	00	31 3	2 33	34
241	Hang + Finish Drywall	5d	6/17/2025	6/23/2025		240						1	1										A	11				241	i بھ	itti	\square		1	
242	Prep and Paint	3d	6/23/2025	6/25/2025		241 SS 4d						ĕ												ill				242	2	<u>i</u> tti	\square		T	
243	Install Ceiling Grid	4d	6/26/2025	7/1/2025		242							1											1					243	AT T	\square		1	
244	Install Final MEPF Devices	3d	7/2/2025	7/4/2025		243						1																	244		\square			
245	Seal Concrete at Janitors Closet	2d	7/7/2025	7/8/2025		247 SS						1																		245	#	+	4	
246	MEPF Final Trim	2d	7/7/2025	7/8/2025		244						1												i					2	246	#	+	1	
247	Install ACT Pads	3d	7/7/2025	7/9/2025		244																	Ø	1					2	247	н			
248	Install Carpet	3d	7/7/2025	7/9/2025		247 SS						1												!					2	248	h		1	
249	Install Casework	2d	7/10/2025	7/11/2025		248						1	Ø																	249	í.			
250	Install Corner Guards	2d	7/10/2025	7/11/2025		249 SS		1				1											Ø			1				250	é i	T	1	
251	Install Rubber Base	3d	7/10/2025	7/14/2025		248			\square			1											Í	1						251		+	1	
252	Install Doors and Hardware	3d	7/14/2025	7/16/2025		250						1												1						25	2 1		1	
253	Final Inspections	2d	7/17/2025	7/18/2025		252						8	B											1						1	253	1	1	
254	Pre-Punch	1d	7/21/2025	7/21/2025		253																									254	ĥ		
255	Final Punch	1d	7/22/2025	7/22/2025		254						1																			255	H		
256	Punchlist Corrections	5d	7/23/2025	7/29/2025		255																		i							256	5	н	
257	Owner FF&E/Occupy	1d	7/30/2025	7/30/2025		258 SS						1											Ø	!						III	\square	257	ġ.	
258	Final Clean	2d	7/30/2025	7/31/2025		256						1	Ø											!							\square	258	i I	
259	Dining	55d	5/22/2025	8/6/2025								1													25								4	
260	Remove all Owner Provided Equipment	2d	5/22/2025 *	5/23/2025		196 SS																			26					Ш	\square			
261	Salvage Ceiling Components and Electrical Finishes	3d	5/22/2025	5/26/2025		260 SS															İ				26	1				₩	\square	\mp	- -	
262	Demo of Existing Finishes/MEPF	3d	5/26/2025	5/28/2025		260						1	T 🖌										Ø		2	62					\square			
263	Install Masonry Jambs at Hollow Metal Frames	3d	5/29/2025	6/2/2025		262						8	B													263		-			+	+	4	
264	Install Hollow Metal Frames	3d	5/29/2025	6/2/2025		263 SS						1												i		264	İЦ-	-			\mp		#	
265	MEPF In-Wall Rough-in	3d	5/29/2025	6/2/2025		262						1												1		265	Бd				\square		1	
266	Install Acoustical Ceilling Panels	3d	5/29/2025	6/2/2025		262																	Ø	-		266		-			\pm	+	÷	
267	MEPF In Wall Inspection	2d	6/3/2025	6/4/2025		265						ł														26	7				=	+	-	
268	MEPF Overhead Rough-in	3d	6/5/2025	6/9/2025		265 SS 5d																				2	268			i TIT	\square			\square
269	MEPF Overhead Inspection	2d	6/10/2025	6/11/2025		268						1									į						269				\exists	+	1	
																					-		$\not\models$										1	
Miles	tone Appearances Start Milestone																															_	_]
	r: Courtney Boyd Start Da	te· 11/1	/2024														,		9	umman	/ Task					Task							_	
	ate: 11/1/2024 Finish Da																		()	lammoc	k Task						essed T	āsk					Buffer 1	ask
Page:																			E	xpande	d Task					Critica	al Task		٠			•	Milesto	ne



Line	Name	Duration	Start	Finish	Percent	redecessors	wember		2024	Decem			anuary	1	Fe	bruary	1	Ма		1	Ap	2025 ril	1	Мау]	une			July		_	August
LINC	Naille	Duration	Otan	1 111011	complete	16060633013		25 2			3	30	3 <u>20</u> 4 5				24 3 10 11							12 1									28 4	
270	Paint Exposted Ceiling	3d	6/10/2025	6/12/2025		268																				-	.70		Ī					
271	Block Fill	2d	6/13/2025	6/16/2025		270					1									i			i				271	⊨				\square		╡
272	Frame Bulkheads + Framed Walls	3d	6/13/2025	6/17/2025		273 SS					2									Ī							272		+		+	\square	H	
273	Install Ceiling Clouds	4d	6/13/2025	6/18/2025		270					4									1			1	\square			273		ļ			\square		
274	Hang and Finish Hardlid Ceilings/Bulkeads/Walls	3d	6/18/2025	6/20/2025		272					8													\square			27	74		+		\square		=
275	Install Ceiling Grid	3d	6/19/2025	6/23/2025		273					4													П			2	275				\square		
276	MEPF Install Final Overhead Fixtures	4d	6/24/2025	6/27/2025		275 SS 3d					ł												1	\square				276				\square	i	
277	Install Ceiling ACT Pads	3d	6/30/2025	7/2/2025		276																		П			\square	2	277	₽	<u> </u>	\square		=
278	Grind/Prep Concrete Slab	3d	6/30/2025	7/2/2025		276					1												-					2	278			\square		
279	Stain and Polish Concrete Slab	4d	7/3/2025	7/8/2025		278																					\square		279	9		\square		Τ
280	Seal Concrete Slab	2d	7/9/2025	7/10/2025		279					2																			280	1			
281	Install Rubber Base	2d	7/11/2025	7/14/2025		280														i									j	281				╡
282	Install Glazing	3d	7/11/2025	7/15/2025		280					2									ļ			ļ						ļ	282	2		ļ	
283	Prime and Paint Walls	3d	7/16/2025	7/18/2025		282 SS 3d																									283			
284	Install Casework at North Wall	2d	7/21/2025	7/22/2025		289 SS																									284	F		╡
285	Install Misc. Corner Guards, Fire Extinguisher Cabinets, TVs/Display Monitors	2d	7/21/2025	7/22/2025		290 SS																							ļ		285			
286	Install Doors and Hardware	2d	7/21/2025	7/22/2025		285 SS														!											286			
287	Paint Hollow Metal Frames	3d	7/21/2025	7/23/2025		283																									287			╡
288	Install MEPF Final In-Wall Fixtures	3d	7/21/2025	7/23/2025		283																							ĺ		288		H	
289	Install Plastic Laminate Surrounds	3d	7/21/2025	7/23/2025		283					1									i									ļ		289		Ħ	-
290	Install Acoustical Panels	3d	7/21/2025	7/23/2025		283														!			!						-		290			
291	Pre-Punch	1d	7/23/2025	7/23/2025		286																									29	91		
292	Install MEPF Final Trims	3d	7/24/2025	7/28/2025		288					1																				2	292	Ħ	╡
293	Punchlist Corrections	3d	7/24/2025	7/28/2025		291																	i						l		2	293	1	
294	Final Clean	2d	7/29/2025	7/30/2025		293					1									<u>i</u>			i							\perp		294		
295	Health + Final Inspections	1d	7/31/2025	7/31/2025		294																Ø	!						_!			2	95	
296	Final Punch	1d	8/1/2025	8/1/2025		295					1																						296	
297	Owner Move-In/ FF&E	1d	8/4/2025	8/4/2025		298 SS																						\square		\perp	\perp	\square	297	1
298	Punchlist Corrections	3d	8/4/2025	8/6/2025		296														li			i		\square	\downarrow		\square		\downarrow	\perp	+	298	-
299	Post Construction	24d	8/1/2025	9/3/2025																li			i	\square	\square	\perp		\square	ļ	\perp	\perp	Ŀ	299	-
Miles	tone Appearances Start Milestone																																	
	or: Courtney Boyd Start Dat																		ummary						Tas				_				Buffe	
Run D	Date: 11/1/2024 Finish Da	ate: 9/3,	/2025																ammocl						_		ed Task						_	
Page:	10 Data Dat	te: 10/1	6/2024															E	xpandeo	Task					Crit	tical Ta	.sk		•			•	Mile	stone



,	Name	Duration	Start	Finish	Percent	Predecessors		Novembe	r	2024	Deo	ember	30 6	Janu	Jary	Ļ	Februa	ary	Ļ	March	ļ		April	2025	Ļ	May			June		-	July		
	Rano	Duration	olari		complete		۳	11 18	25 5 -4	29 -3.	16 -2 -1	23	30 6	13 3 4	20 27	7 3 6 7	10 17	7 <u>24</u> 9 10	3 1	0 <u>17</u> 12 13	24 3	1 7 15 16	14 2	1 28 18 1	5 9 20	12 19 21 2	26 2 23	2 9 24 2	16 2	3 30 27 7	7	14 2 30	1 28 31 3	4 32
	Test and Balance	5d	8/1/2025 *	8/7/2025																				4									30	ю
	Closeout Documents Provided to Owner		9/1/2025 *	9/1/2025																				7	i					i				i
	O&M Trainings	3d	9/1/2025 *	9/3/2025		301							l								Ti			2						T				ī
									+											+	Τİ	+								Ť			+	t
									+					-	+	+		+		+		+				-	\top	+			-	\square	+	1
								\vdash	+-					+	++	+				+		+				+	+	+		+	+	$\left \right $	+	+
_									+						++	-				+		+		9	:					╬		$\left \right $	-	+
_							-	\vdash	+-		-			+	+	-				+	+	+					+-	-		+	-	$\left \right $	+	÷
_									-		_			_	+	_		_		_		_				_		_		+	_	$\left \right $	_	÷
							-	$\left \right $	+	\vdash	_			_	+	+-	$\left \cdot \right $		\vdash	_	+	_		7			+	_	+	╬		$\left \cdot \right $	+	÷
									_		_			_	+	_				_	<u> </u>	_				_	+	_		-	_		_	4
_									_											_										ļ	_			-
_									_		_					_					!				!					_ <u> </u> !				-
																								2						_!				_
																								7										
																								9	:					i				l
																								4						i				Ţ
																								7						Ì				1
																									!									1
									+																									1
									1				11											A									+	1
_									+					-	+			+		+		+				-		+		Ť	-	\square	+	t
								\vdash	+-					+	+	+		+	\vdash	+	+	+				+	+	+	+	-	+	$\left \right $	+	Ť
								\vdash	+-						+	+				+	+ ¦i	+			i –		+		+	+		$\left \right $	+	÷
								\square	+-		-			-	+	-			\square	-	+	-					+	-		+	_	$\left \right $	+	÷
							-	\vdash	+-	\vdash	_			_	++	+			\vdash		+	+			<u> </u>	_	+			÷	_	$\left \cdot \right $	_	+
							-	\square	+		_			_	++	_		_		_		_		4	!	_	+	_		<u> </u>	_	$\left \cdot \right $	+	+
								\square	+-		_			_	++	_		_		_	+	_				_	_	_		-	_	$\left \cdot \right $	_	4
_									_		_			_	$\left \right $	_		_		_		_				_	_	_	$ \rightarrow $	_ <u> </u> ;	_			4
									_		_													4						_	_			-
																					<u> i</u>									_ <u> </u> i				1
																														_ <u> </u>				ļ
;	tone Appearances		-											1						1				-		1		1						
	Start Milestone	+0. 11/1	/2024																	Sum	mary Tas	sk					Task							_
	br: Courtney Boyd Start Da Date: 11/1/2024 Finish D	ne: 11/1 ate: 9/3	./2024 /2025																		mock Ta						Progre	ssed Ta	ik					Buf
	11 Data Da		,																		nded Ta						Critica						٠	

OFFICIAL BULLETIN #16



TO: All Unit Heads

FROM: Curriculum, Assessment and Instruction

SUBJECT: Testing and Assessment Dates 2024-25

DATE: August 13, 2024

ACT

ACT Test Date	<u>Registration Deadline</u>	Late Registration Deadline
September 14, 2024	August 9, 2024	August 25, 2024
October 26, 2024	September 20, 2024	October 7, 2024
December 14, 2024	November 8, 2024	November 22, 2024
February 8, 2025	January 3, 2024	January 20, 2024
April 5, 2025	February 28, 2024	March 16, 2024
June 14, 2025	May 9, 2024	May 26, 2024
July 12, 2025	June 6, 2024	June 20, 2024

<u>AP (Advanced Placement)</u>			
Subject Grades Dates			
AP Courses	9-12	May 9-May 16, 2025	

Armed Services Vocational Aptitude Battery (ASVAB)

Testing scheduled by each High School

CogAT (Selected Students)

Level	Grades	Dates
Elementary	K Screener	January 21-February 21, 2025
Elementary	K Full Battery	March 18-April 11, 2025
Elementary	2 Screener	September 24-October 25, 2024
Elementary	2 Full Battery	November 18-December 20, 2024
Elementary	5 Full Battery	October 7-December 20, 2024
Middle	8 Screener	September 24-October 25, 2024
Middle	8 Full Battery	November 18-December 20, 2024

<u>Subject</u>	<u>Grades</u>	Dates
BoY	K-2 ELA	August 12-August 30, 2024
MoY	K-2 ELA	December 9-December 20, 2024
EoY	K-2 ELA	May 5-May 16, 2025

HMH Literacy Growth Measure

<u>Subject</u>	Grades	<u>Dates</u>
BoY	9-12 ELA HMH	August 12-August 23, 2024
MoY	9-12 ELA HMH	December 9-December 20, 2024
EoY	9-12 ELA HMH	April 28-May 9, 2025

i-Ready Math Diagnostic Numeracy

<u>Subject</u>	Grades	Dates
BoY	K-5 Math	August 12-August 30, 2024
MoY	K-5 Math	December 9-December 20, 2024
EoY	K-5 Math	May 5-May 16, 2025

IAM Dates			
<u>Subject</u>	Grades	Dates	
ELA, Math, Social Studies,	3-8 and 10	March 31-May 9, 2025	
Science	(per case conference decision		
	only)		
	<u>IB Exams (South Side)</u>		
Level	<u>Grades</u>	Dates	
Southside High School	IB Students	April 23-May 16, 2025	
	ILEARN		
<u>Subject</u>	Grades	Dates	
ELA, Math, Social Studies,	3-8	April 14-May 9, 2025	
Science, Biology	Biology ECA	April 14-May 16, 2025	
	IREAD-3		
Subject	Grades	Dates	
IREAD-3 Spring	2-3 (4-5 re-testers)	March 3-March 14, 2025	
IREAD-3 Summer	3, 4, 5 re-testers	May 12-June 27, 2025	
	ISPROUT		
Subject	Grades	Dates	
BoY	PreK	October 7-January 5, 2025	
MoY	PreK	January 6-March 30, 2025	
EoY	PreK	March 31-June 15, 2025	
Multilingual Proficiency Testing			
<u>Subject</u>	Grades	Dates	
Multilingual Proficiency for	8-12	March 3-March 28, 2025	
Native Language Speakers			
and WL/ELL students			
PSAT (Preliminary SAT) 8/9 and PSAT/NMSQT			
<u>Subject</u>	Grades	Dates	
PSAT 8/9	9	October 1-October 31, 2024	
PSAT/NMSQT	10-11	October 1-October 31, 2024	

<u>McGraw Hill Reveal Math Diagnostic</u>		
<u>Subject</u>	Subject Grades Dates	
BoY	6-8 Math	August 12-August 30, 2024
MoY	6-8 Math	December 9-December 20, 2024
EoY	6-8 Math	May 5-May 16, 2025

<u>SAT (Scholastic Aptitude Test)</u>		
SAT Test Date	Registration Deadline	Late Registration Deadline
August 24, 2024	August 9, 2024	August 13, 2024
October 5, 2024	September 20, 2024	September 24, 2024
November 2, 2024	October 18, 2024	October 22, 2024
December 7, 2024	November 22, 2024	November 26, 2024
March 8, 2025	February 21, 2025	February 25, 2025
May 3, 2025	April 18, 2025	April 22, 2025
June 7, 2025	May 22, 2025	May 27, 2025

SAT (IDOE Required)

Subject	Grades	Dates
Primary Days	11	March 3-March 14, 2025 (FWCS
		date 3/4/25; snow date 3/11/25)

US Government Naturalization		
Subject	Grades	Dates
Semester 1	Government students only	November 1-December 20, 2024
Semester 2	Government students only	April 7-May 22, 2025

<u>WIDA ACCESS</u>		
Level	Grades	<u>Dates</u>
ELL Students English	K-12	January 13-February 28, 2025
Proficiency Levels: 1.0-4.9		
and Alternate Levels: A1, A2,		
A3, P1, P2 and P3		

WIDA ACCESS





Responsibilities for Establishing and Managing an Effective Hot Work Permit Program (Adapted from the National Fire Protection Association Standard 51B, 1999 Edition)

1. Management:

- **D** Establish permissible areas for hot work. Designate areas where hot work is prohibited.
- Designate one individual in the organization as the Permit Authorizing Individual (PAI).
- □ Ensure that only approved apparatus including torches, manifolds, regulators and related equipment is used.
- □ Ensure that anyone involved in hot work operations, including contractors, are familiar with, and follow the provisions of the Hot Work Permit Program.
- Specify that any contractor bidding on work include a copy of *their* Fire Safety Program and Hot Work Permit Program, as required by OSHA standards, along with their quote.

2. <u>Permit Authorizing Individual (PAI)</u>:

- □ Determine site-specific flammable materials, hazardous processes, or other potential fire hazards present or likely to be present in the work location.
- **D** Ensure the protection of combustibles from ignition by the following means:
- ✓ Move work to a location that is free from combustibles.
- ✓ If the work cannot be moved, ensure the combustibles are moved to a safe distance of have the combustibles properly shielded against ignition.
- ✓ Ensure that the hot work is scheduled such that operations where combustible materials may be exposed to the hot work are delayed until the area is safe.
- Determine that fire protection and extinguishing equipment are properly located at the site.
- Make a final checkup 30 and 60 minutes after the completion of the hot work operations to detect and extinguish possible smoldering fires.
- 3. Fire Watch:
 - □ Maintain an awareness of the inherent hazards of the work site and of the hot work.
 - □ Ensure that safe conditions are maintained during hot work operations.
 - □ Have the authority to stop the hot work operations if unsafe conditions develop.
 - Be familiar with the facilities and procedures for sounding an alarm in the event of a fire.
 - □ Watch for fires in all exposed areas and try to extinguisher them only when the fires are obviously within the capacity of the equipment available.
 - Where fires are not within the capacity of extinguishing equipment sound the alarm without delay and notify the fire department.





Hot Work Permits

- 1. Before hot work operations begin a written **Hot Work Permit** issued and signed by the Permit Authorizing Person (PAI) is required. Before issuing a permit the following conditions must be verified by the PAI:
 - □ Hot work equipment to be used is approved, in satisfactory condition and in good repair. Where combustible materials are on the floor, the floor is swept clean for a radius of 35 feet.
 - □ Combustible floors and floor covering are kept wet, covered with damp sand or protected by noncombustible or fire-retardant shields.
 - Openings or cracks in walls, floors, or ducts within 35 feet of the site are tightly covered with fireretardant or noncombustible materials to prevent the passage of sparks to adjacent areas.
 - Conveyor systems that might carry sparks to distant combustibles are shielded.
 - □ Where hot work is done near walls, partitions, ceilings or roofs of combustible construction, fireretardant shields or guards are placed to prevent ignition.
 - Hot work shall not be attempted on a partition; wall, ceiling or roof that has a combustible covering or insulation, or on walls or partitions of combustible sandwich-type panel construction.
 - Hot work that is performed on pipes or other metal that is in contact with combustible walls, partitions, ceilings, roof, or other combustibles shall not be undertaken if the work is close enough to cause ignition by conduction. This includes pipe-thawing operations. Fully charged and operable fire extinguishers that are appropriate for the type of possible fire must be available immediately at the work area. Extinguishers should have a current inspection & service tag.
 - □ If hot work is done in close proximity to a fire sprinkler head, a wet rag shall be laid over the head and then removed at the conclusion of the welding or cutting operation.
 - Persons working in the area must be protected against heat, sparks, slag and so on.
 - **D** The PAI shall determine the length of the period for which the Hot Work Permit is valid.
 - □ The PAI shall inspect the work area at least once per day while the hot work permit is in effect to ensure that it is a fire-safe area.
- 2. A Fire Watch is required whenever hot work is performed in a location where other than a minor fire might develop, or where the following conditions exist:
 - Combustible materials in building construction or contents are closer than 35 feet to the point of the operation.
 - Combustible materials are more than 35 feet away but are easily ignited by sparks.
 - □ Wall or floor openings within a 35-foot radius expose combustible materials in adjacent areas, including concealed spaces in walls or floors.
 - Combustible materials are adjacent to the opposite side of partitions, walls, ceilings, or roofs and are likely to be ignited.
- 3. If required, the Fire Watch shall be maintained for at least ½ hour after completion of hot work operations in order to detect and extinguish smoldering fires.





4. More than one fire watch shall be required if the initial fire watch cannot directly observe combustible materials that could be ignited.

ATTENTION!

Before approving any hot work permit, the PAI shall inspect the work area and confirm that precautions have been taken to prevent fire in accordance with NFPA 51 B and OSHA Standards 29CFR1910.252 and/or 29CFR1926.352.

NOTE: This checklist is not all-inclusive. The Permit Authorizing Individual (PAI) has the responsibility to review all fire exposures and safety measures and to require or take appropriate action to prevent fires. The PAI also has the responsibility and authority to stop any hot work where he/she feels that precautions are not adequate.

PRECAUTIONS

- **G** Fire sprinkler systems are in good service.
- Hot work equipment is in good repair.

WITHIN 35 FEET OF WORK

- Floors are swept clean of combustibles.
- Combustible floors are wet down, covered with damp sand, metal or other fire resistive shields.
- All wall and floor openings are covered.
- Covers are suspended beneath work to collect sparks.

WORK ON WALLS OR CEILINGS

- Construction is noncombustible and without combustible coverings.
- Combustibles are moved away from the opposite side of the wall.

WORK ON ENCLOSED EQUIPMENT

- (Tanks, containers, ducts, dust collectors, etc.)
- **Equipment is cleaned of all combustibles.**
- Containers are purged of flammable vapors.

FIRE WATCH

- To be provided during and 30 minutes after operation.
- Supplied with a fully charged and operable fire extinguisher.
- Trained in use of equipment and in sounding fire alarm.

FINAL CHECK

D To be made 30 minutes and 60 minutes after the completion of any operation.

Signed:

Permit Authorizing Individual (PAI)





HOT WORK PERMIT

NOTICE! A Hot Work Permit is required for any operation involving open flames or which produces heat and/or sparks. This includes Brazing, Cutting, Grinding, Welding, Soldering, Thawing Pipe, Torch-Applied Roofing and Cadwelding.

This permit MUST be signed & posted in the work area!

Date:	Time issued:	oAM oPM		
Building / Location:				
Department:		Floor:		
Special Precautions Required:				
Fire Watch Required: oYES oNO				
The Location where this work is to be done has been examined, necessary precautions taken, and permission granted for this work. (See other side)				
Permit expires on (date) at	(time) oAM	оРМ		
Signed:				
Permit Authorizing Individual (PAI)				
Final Check				
Work was completed on (date) at (time) oAM oPM I hereby certify that the work area and all adjacent areas to which sparks and heat might have spread, including floors above and below and on opposite side of wall(s), were inspected 30 minutes and 60 minutes after the work was completed and were found to be firesafe.				
Signed:				
Permit Authorizing Individual (PAI)				

ADDENDUM 01- 10/17/2024

Renovation of Wayne HS Kitchen & Cafeteria Fort Wayne, Indiana				
Bid Item #1-	Masonry			
Bid Item #2-				
Bid Item #3-	General Trades			
Bid Item #4- Glazing Bid Item #5- Framing				
			Bid Item #6-	Painting
Bid Item #7-	Flooring and Wall Tile			
Bid Item #8-	Polished Concrete			
Bid Item #9- Fire Protection Bid Item #10- Mechanical Bid Item #11- Electrical/Fire Alarm/Low Voltage Bid Item #12- Kitchen Equipment				
			Bid Item #13	3- Doors, Frames, and Hardware
			Bid Date:	November 7, 2024
			Bid Time:	2:00 p.m. EST
of Bidder:				
Item No.:				
escription:				
	Fort Wayne, Bid Item #1- Bid Item #2- Bid Item #3- Bid Item #4- Bid Item #5- Bid Item #6- Bid Item #7- Bid Item #7- Bid Item #8- Bid Item #9- Bid Item #11 Bid Item #11 Bid Item #13 Bid Item #13			

Bidders are to complete and submit the following forms:

- 1. Bid Form
- 2. Bid Bond
- 3. Resumes for Proposed Project Staff
- 4. Subcontractor/Sub-subcontractor/Supplier List
- 5. Labor Rate Table

Bid Submitted to:	Fort Wayne Community Schools	
(hand deliver or mail)	Attn: Jacob Buckland	
	1517 Catalpa St.	
	Fort Wayne, IN 46802	

The undersigned Bidder, having visited the site of the work and having familiarized himself/herself with local conditions affecting the cost of this Work, hereby proposes to perform the following listed Work, in accordance with the Project Specifications and Drawings dated August 13, 2021, and all Addenda and Revisions/Clarifications Letters issued prior to the due date of bids, for the **Lump Sum Amount** stated below.

RENOVATION OF WAYNE HS KITCHEN & CAFETERIA

ADDENDUM 01- 10/17/2024

Addenda Received & Included:	No	Dated
Addenda Received & Included:	No	Dated
Addenda Received & Included:	No	Dated

ADDENDUM 01- 10/17/2024

\$

BASE BID(S)

Bid Item # -

TOTAL BASE BID:

(amount in words)

Bid Item # _ PAYMENT AND PERFORMANCE (P&P) BONDS: Please list the amount DEDUCTED from Base Bid Total if P&P Bonds are not required: \$______. (DEDUCT)

BREAKOUT PRICING (FOR ACCOUNTING PURPOSES ONLY):

State the costs of each work area (three (3) total) as outlined in the Work Area Breakdown Plan on the following page.

1.) Kitchen/Serving/Test Kitchen-Café


2.) Dining/Banquette Area \$_____

3.) Guidance


\$_____


Work Area Breakout Document

Please breakout the costs on the Bid Form according to the shaded areas below.









ADDENDUM 01- 10/17/2024

VOLUNTARY ALTERNATE(S): Describe here or attach to Bid Form.

NOTE: Bidders are to circle "Add" or "Deduct" as appropriate.

1.	Description:
	<u>\$</u> (Add/Deduct)
2.	Description:
	<u>\$</u> (Add/Deduct)
3.	Description:
	\$(Add/Deduct)

LABOR RATE TABLE:

All bidders shall provide a breakdown of cost/hour rates for their labor to be used on future Change Order Time and Material work. These rates will not be subject to change for the duration of the project.

LEGA	AL NAME OF BIDDER: _		ADDENDUM 01- 10/17/2024
d/b/a	NAME (if different):		
PHO	NE:		
BY:			
	NOWLEDGEMENT – Nota		
STAT	TE OF		
COU	NTY OF	SS:	(seal)
		being duly sv	vorn, deposes and says that
he/sho	e is	of the above	and that the
staten	(Title) nents contained in the foreg	N) oing Supplements to Bid Form a	ame of Organization) are true and correct.
Subsc	cribed and sworn to before I	me this day of	
		_	
My C	commission Expires:		Notary Public
Coun	ty of Residence:		
	Subcontractor is also reque ct as well as a resume for ea		proposed staff that would be assigned to this
A.	Site Foreman/Superinter	ndent:	
B.	Project Manager:		
		END OF SECTION	N

RENOVATION OF WAYNE HS KITCHEN & CAFETERIA