

ADDENDUM NO. 2

Pike High School – Baseball and Softball Turf

Project No. 224064.00

MSD of Pike Township
Indianapolis, Indiana

Index of Contents

Addendum No. 2, 5 Items, 2 pages
Revised Drawing Sheets: G4.0, G4.1, G4.2, G4.3, G4.4, SU5.0, SU5.1, SU5.2, SU5.3, SU6.0, SU6.1, and
SU6.2

Date: October 24, 2024

FANNING/HOWEY ASSOCIATES, INC.
ARCHITECTS/ENGINEERS/CONSULTANTS

TO: ALL BIDDERS OF RECORD

ADDENDUM NO. 2 to Drawings and Project Manual, dated October 4, 2024, for MSD of Pike Township, 3950 W. 56th Street, Indianapolis, Indiana 46278; as prepared by Fanning/Howey Associates, Inc., Indianapolis, Indiana. This Addendum shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes, and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified in this Addendum.

Each bidder shall acknowledge receipt of this Addendum in his proposal or bid.

NOTE: Bidders are responsible for becoming familiar with every item of this Addendum. (This includes miscellaneous items at the very end of this Addendum.)

RE: ALL BIDDERS

ITEM NO. 1. ADDENDUM NO. 1

A. Revised Project Manual Section 13 34 17 – Angle Frame Bleachers: Make the following modifications:

“Add 2.6, A., 4., as follows:

“4. Fully enclosed adjoining horizontal deck planks and vertical riser planks.”

ITEM NO. 2. PROJECT MANUAL, SECTION 01 50 00 – TEMPORARY FACILITIES AND CONTROLS

A. Add 3.4, C., 3., a., 2) as follows:

“2) Erect barricades as required by applicable laws at open excavations and other hazardous locations created by earthwork and site preparation.”

B. Add 3.4, H., 5., as follows:

“5. Site Security Fencing: Plastic construction fencing, 4 feet high, with posts spaced 10 feet on center and driven 3 feet into ground. Fasten fence to each post with 5 fasteners. Site security fencing must be maintained and in upright configuration at all times. This site security fencing is in addition to compliance with safety requirements for barricades at hazardous locations and open excavations, etc.

Location:

- a. Provide plastic construction fencing along north side of varsity softball field from east property line to the existing creek to west and around the softball field perimeter beyond outfield fencing, bleachers, dugouts and other areas where work will be occurring.
- b. Provide plastic construction fencing along north side of varsity baseball field from east property line to the existing creek to west. Full perimeter of varsity baseball field does not need to be enclosed.

ITEM NO. 3. PROJECT MANUAL, SECTION 07 01 50.91 – ROOFING RESTORATION

A. Replace 2.1, B., as follows:

“B. Installers licensed and approved by the coating manufacturer including completion of training by the coating manufacturer are also approved Installers for the Work of this Section.”

B. Add 2.3, A., 1., as follows:

- “1. Approved Manufacturers:
 - a. Tremco
 - b. Sika Sarnafil
 - c. GAF Materials Corporation
 - d. NeoGard Construction Coatings

ITEM NO. 4. ACCEPTABLE MANUFACTURERS

The following manufacturers are to be considered acceptable manufacturers (suppliers and fabricators) for the Sections of the Specifications listed. Listed manufacturers are required to bid on products equal in type and design, size, function, and quality to that originally specified. Final decision as to equality of products specified versus those proposed shall be made by the Architect.

Section 13 34 17 – Angle Frame Bleachers
- National Recreation Systems, Inc., Fort Wayne, Indiana

ITEM NO. 5. REVISED DRAWING SHEETS

- A. Drawing Sheets: G4.0, G4.1, G4.2, G4.3, G4.4, SU5.0, SU5.1, SU5.2, SU5.3, SU6.0, SU6.1, and SU6.2 have been revised, dated 10/24/24, and is included with and hereby made a part of this Addendum. These Drawings supersede the original documents.

END OF ADDENDUM