




Primary Engineering, Inc.
2828 Lake Ave.
Fort Wayne, Indiana 46805
260-424-0444 ph
www.primary-eng.com



Addendum: **3**
Date: **11/1/2024**
Project: **Purdue Fort Wayne
Ginsberg Hall Chiller & Control Air Replacement**
Comm #: **24635**

The following items shall be incorporated into the specifications and drawings and are considered to be integral to the bid documents for the project. Acknowledgement of receipt of this addendum is required on the bid form.

Item #1: Drawing Sheet M501.

- A.** Add the attached glycol fill station schedule to sheet M501. Coordinate with electrical power and move new 120v outlet closer to glycol feed unit on East wall.

GLYCOL FILL STATION SCHEDULE								
TAG	MFR.	MODEL	CAPACITY (GAL)	MAX. PRESSURE (PSI)	FLOW RATE (GPM)	MOTOR SIZE (HP)	ELEC (V/PH)	REMARKS
GFS-1	CALIFACTIO	GMP18	18	60	1.6	-	120/1	1
REMARKS: 1. PROVIDE AND INSTALL WITH FULLY PIPED PRESSURE SWITCH, PRESSURE GAUGE, AND LOW LEVEL ALARM SYSTEM.								