


# ADAMS COUNTY ENGINEER

201 N POLK ST., MONROE, IN 46772

Office: 260-692-6551 email: nrumschlag@adamscounty.in.gov



## ADAMS COUNTY

### County Road 700 South Reconstruction

### Project No. 2024-11


### ADDENDUM #3

Date: November 20, 2024

The attention of all prospective Bidders on the subject project is directed to the following change in project specifications:

#### Contractor Questions / Answers


1. For the removal of all the existing pipe- do we need to figure additional backfill material such as granular and or native backfill or is that already in a line item such as 48, 49 and potentially 12?
  - a. See Technical Specification Section 2.13 for backfilling instructions for all trenches and excavations.
  - b. The cost of backfill related to storm pipe removal shall be included for each "storm pipe removal" line item. Backfill for pipe removals is not included in line items #48, #49, or #12.
2. Is full depth removal of asphalt, stone, and concrete figured in line item 12?
  - a. Yes
3. For line item 8 and 9- does the contractor have to cover the cost for relocation or is the local provider already aware of what will be taking place, and contractor must coordinate it with provider when it needs to happen?
  - a. The contractor is not responsible for utility relocation cost or fees from the Utility Companies as described in items #8, #9, and #10.
  - b. Item #7 – We assume the regional waste district will allow the project contractor to lower the 1.5" force main service lines. Please provide cost to perform this work.
    - i. Please notify, coordinate, and comply with required regional waste district inspections/inspectors as necessary prior to construction.
    - ii. Any unknown inspection cost or fees from the regional waste district will be paid by Adams County Board of Commissioners.
    - iii. If an as-built utility survey is required, please notify Adams County Engineer and/or project surveyor when the utility work is completed so the survey may be scheduled.
  - c. Items #8, #9, and #10 – Utility Coordination includes notification, scheduling, coordination, rules & standards compliance with each Utility Company performing the utility work, and combined effort to complete the work necessary to complete the project.



# ADAMS COUNTY ENGINEER

201 N POLK ST., MONROE, IN 46772

Office: 260-692-6551 email: nrumschlag@adamscounty.in.gov



- i. Adams County Board of Commissioners will be responsible for all costs and fees of utility work performed by the Utility Company.
4. Are the aggregate quantities, for example 4" of compacted aggregate under driveway concrete figured in line item 42 or do we need to figure the tonnage amount in each individual line item for concrete? Examples such as 3.5" of 53 beneath curb & gutter, 3.5" beneath depressed curb etc. are they all in 42 or need tonnage figured in with each line item?
  - a. Item #42 is the compacted aggregate needed for Add Alternate No. 1, which also includes Item #41 – Concrete Sidewalk, 4" (Add Alternate No. 1 for South Adams Schools). This alternative is for the school to decide if they want to help pay for the sidewalk or not.
  - b. Item #34 is the tons of compacted aggregate for the curbs, driveways, and road improvements.
  - c. The asphalt and concrete pavements are calculated as separate items from the compacted aggregate that is beneath them.
5. Does the contractor need to figure any lime or cement stabilization, if so what is sy amount?
  - a. If lime or cement stabilization is needed during construction, additional project cost will be handled by change order.
6. Does this job require any certain wage requirements (prevailing wage etc)?
  - a. No.
7. Do you have a geotechnical report for the project?
  - a. No.

Please acknowledge receipt of this Addendum in final proposal.

Sincerely,

Nate Rumschlag, PE, MCM  
County Engineer