

Addendum C-1 December 16, 2024 Cedarville Elementary School Parking Lot Improvements

This Addendum forms a part of the Contract Documents for the above-referenced project and is issued in accordance with the Instructions to Bidders. Acknowledge receipt of this addendum by inserting its number in the space provided in the bid form.

Item C1.1: General Description: Add

A. The Pre-Bid Meeting Agenda that was shared during the meeting.

Item C1.2: General Description: Add

- A. The Pre-Bid Meeting Sign-in Sheet
- Item C1.3: General Description: Clarification
 - A. There will be summer school at Cedarville Elementary. Contractors will need to phase the construction to allow for one parking lot to remain open at all times.

Item C1.4: General Description: Clarification

B. The last day for questions will be January 3rd. If any questions come in after the 3rd they may not be answered. Please email questions to Dan Brincefield (<u>dbrincefield@eri.consulting</u>). His phone number is (260) 451-9741.

Item C1.5: General

Description: Clarification

A. The 6' Wood Privacy fence shall be comprised of 4" wood posts spaced a maximum of 8'-0" on center, 2" x 4" wood rails (3 per section), and 1" x 6" x 6' Dog-eared Pickets. All wood to be pressure treated and not stained. All posts to be placed in a concrete foundation that is 18" diameter wide by 4' deep.

Item C1.6: General Description: Clarification

A. The Contractor is responsible for watering the newly planted lawn as needed to ensure a satisfactory lawn is established. See Lawns and Grasses Specification #32 92 00 for additional information.



Item C1.7:C0.0 Title Sheet (Reissued Sheet)Description:Add

A. Added C7.0 Maintenance of Traffic Plan to the Sheet Index.

Item C1.8:C1.0 Site Demolition Plan (Reissued Sheet)Description:Add

A. Added an additional area of asphalt pavement removal to the project.

Item C1.9: C2.0 Site Layout Plan (Reissued Sheet)

Description: Add

A. Added an additional area of Type "A" and Type "B" pavement to the project.

- Item C1.10:C3.0 Site Grading Plan (Reissued Sheet)Description:Clarification
 - A. Added spot elevations to the new pavement removal / replacement areas.
 - B. Modified the rim elevations on the proposed storm structure #4 and the existing storm structure #4.
 - C. Reprinted the Grading Plan due to issues with the old PDF. If a Contractor still has issues seeing the spot elevations on this PDF, please contact Engineering Resources.

Item C1.11: C4.0 Site Utility Plan (Reissued Sheet)

- Description: Clarification
 - A. Modified the rim elevations on the proposed storm structure #4 and the existing storm structure #4.

Item C1.12:C5.0 Site Construction Erosion Control Plan (Reissued Sheet)Description:Clarification / Added

- A. Updated plans to switch a couple "T9" tags to be "T8" Tags.
- B. Updated Note #2 under "Post Construction Activity" notes to read that the Contractor to contact the Allen County Surveyor's Office for Final Site Inspection and Verification of Site Stabilization.
- C. Added a Public Notice Board requirement to the project.

Item C1.13:C7.0 Maintenance of Traffic Plan (Reissued Sheet)Description:Add

A. Added the Maintenance of Traffic Plan to the project. This plan will be submitted to INDOT with the driveway permit for their review.



December 12, 2024

Pre-Bid Meeting

Centerville Elementary School Parking Lot Improvements

Introduction

- 1. Owner & Design Team
- 2. Project Overview

Bidding

- 1. Bids due at 2:00 pm on January 9, 2025, at the East Allen County Schools Administration Offices (1240 State Road 930 East, New Haven, Indiana)
- 2. Forthcoming Addendum
- 3. \$25,000 Allowance to be included in the bid.
- 4. Unit Costs Summary
- 5. Submit all forms including the Indiana Form 96, E-Verify, Bid Bond and Certified Check and No Iran Investment.

Construction Phase

- 1. Project Schedule:
 - a. Start of Construction = May 27, 2025.
 - b. Substantial Completion Date = July 25, 2025.
 - c. Final Completion For all Areas minus Seeding = August 1, 2025.
 - d. Final Completion Date for Lawn Seeding = October 3, 2025.
- 2. Coordination:
 - a. Owner
- 3. Permits:
 - a. A SWPPP permit is required for this project.
 - b. A Site Review Permit through Allen County Planning Department is required for this project.
 - c. INDOT permit for construction in S.R.1 right-of-way.
- 4. Provide a certified record drawing of all improvements and any existing utilities discovered during construction to Owner and Engineer.
- 5. Issues with Grading Plan PDF from Eastern.



December 12, 2024


Pre-Bid Meeting

East Allen County School District Cedarville Elementary School Parking Lot Improvements

Sign In Sheet

Name		Company	Phone	E-mail
Haron	Lybarger	API	260-397-2743	3 a. lybarger capiland i net
Dan	Brincefield	ERI	260 - 45(-974)	dbrincefield e eri. consutting
Diane	Reynolds	ERI	260-451-9742	diance eri. consalting
Chris	Baker	EACS	260-446-0119	<u>cbakera</u> eacs, KI2, In. US
			<u>u</u>	

CEDARVILLE ELEMENTARY SCHOOL PARKING LOT RENOVATIONS








EAST ALLEN COUNTY SCHOOLS

12225 Hardisty Road Fort Wayne, IN, 46845





PROJECT INFORMATION:

OWNER:



EAST ALLEN COUNTY SCHOOLS 1240 STATE ROAD 930 EAST NEW HAVEN, IN 46774

PH.: (260) 446-0100 www.eacs.k12.in.us

4175 New Vision Drive

Fort Wayne, IN 46845

260-490-1025

SHEET INDEX

	SHEET NO.	TITLE					
	C0.1	TOPOGRAPHIC SURVEY					
	C1.0	SITE DEMOLITION PLAN					
	C2.0	SITE LAYOUT PLAN					
	C3.0	SITE GRADING PLAN					
	C4.0	SITE UTILITY PLAN					
	C5.0	SITE CONSTRUCTION EROSION CONTROL PLAN					
	C5.1	SITE EROSION CONTROL DETAILS					
Λ	C6.0	SITE DETAIL SHEET					
<u>`````{</u>	C7.0	MAINTENANCE OF TRAFFIC PLAN					
	L1.0	SITE LANDSCAPE PLAN					


ENGINEER:





4175 NEW VISION DRIVE FORT WAYNE INDIANA 46845 260-490-1025 wwww.eri.consulting


www.eri.consulting

















THE FOLLOWING SEQUENCING IS SCHEMATIC IN NATURE. CONTRACTOR SHALL DETERMINE INSTALLATION SCHEDULE TO

1. CONTACT THE INDIANA UNDERGROUND PLANT PROTECTION SERVICE "INDIANA 811" TO LOCATE UNDERGROUND UTILITIES AT LEAST TWO (2) WORKING DAYS PRIOR TO EARTH DISTURBING ACTIVITIES. MARK UTILITIES ON THE PROJECT

NOTIFY IDEM RULE 5 COORDINATOR, ERIC ROBERTS, AT eroberts@idem.IN.gov OR 1-800-451-6027 AND THE REVIEWING AGENCY(S), MATT JARRETT OF THE ALLEN COUNTY SURVEYORS OFFICE (260) 449-7625, AT LEAST TWO (2) WORKING DAYS PRIOR TO EARTH DISTURBING ACTIVITIES OF THE <u>ACTUAL</u> START DATE FOR EARTH DISTURBING ACTIVITIES. 3. PROTECT EXISTING WATERWAYS, STREAMS, RIVERS, LAKES, WETLANDS, ETC. FROM SEDIMENT AND POLLUTANTS

ESTABLISH STABLE CONSTRUCTION ENTRANCE, EQUIPMENT AND EMPLOYEE PARKING AND STAGING AREAS. ADJACENT

6. INSTALL PERIMETER PROTECTION DEVICES AND MEASURES SUCH AS SILT FENCE, TEMPORARY DIVERSION SWALES AND

PROTECT EXISTING STORM WATER SEWER SYSTEM INLETS WITH INLET PROTECTION DEVICES.

DE-WATER THE CONSTRUCTION SITE WHEN NEEDED. THE WATER MUST FLOW THROUGH A TREATMENT SYSTEM OR

PREPARE ON OR OFF-SITE SOIL STOCKPILE AREAS WITH EROSION CONTROL DEVICES AND MEASURES. BEGIN INITIAL LAND CLEARING AND GRADING BY GRUBBING AND CLEARING VEGETATION THEN STRIP AND STOCKPILE TOPSOIL. WHEN POSSIBLE, PHASE LAND CLEARING AS TO NOT LEAVE LARGE AREAS OF SOIL EXPOSED AND LEFT INACTIVE FOR SEVEN (7) DAYS OR MORE. IF DISTURBED AREAS ARE EXPECTED TO BE LEFT INACTIVE FOR SEVEN (7) DAYS OR MORE, THE DISTURBED ARE IS TO BE STABILIZED BY PERMANENT OR TEMPORARY SEEDING, MULCHED AND MECHANICALLY CRIMPED INTO THE SOIL, OR BY OTHER SURFACE STABILIZING METHODS TO BE COMPLETED WITHIN

PERMANENTLY SEED, OR MULCH, DISTURBED AREAS AS SOON AS POSSIBLE TO PREVENT SEDIMENT LOSS. INSTALL EROSION CONTROL BLANKET OR TURF REINFORCEMENT MAT (TRM) AS INDICATED ON THE PLANS. IF EROSION CONTROL BLANKETS OR TRM'S ARE NOT SPECIFIED THE CONTRACTOR MAY INSTALL ADDITIONAL EROSION CONTROL

INSTALL CONCRETE WASHOUT AREA TO BE USED DURING CONSTRUCTION OF UTILITIES, DRIVES, PARKING LOTS,

9. CONSTRUCT STORM WATER CONVEYANCE SYSTEMS SUCH AS SWALES, CHANNELS AND STORM WATER SEWERS. 11. FINE GRADE SITE, PERMANENTLY SEED AND LANDSCAPE. THE CONTRACTOR SHALL NOTIFY THE CITY OF FORT WAYNE

12. REMOVE TEMPORARY EROSION CONTROL DEVICES AND MEASURES, ONCE THE CONTRIBUTING DRAINAGE AREA IS STABILIZED AND 70% UNIFORM DENSITY OF VEGETATIVE COVER HAS BEEN ACHIEVED. STABILIZE SOIL ANY DISTURBED

1. REMOVE CONSTRUCTION SEDIMENT AND DEBRIS FROM PERMANENT EROSION CONTROL DEVICES AND MEASURES.

NOTICE OF TERMINATION (NOT) TO IDEM ONLINE. A COPY OF THE NOT SUFFICIENCY LETTER WILL THEN BE SENT TO THE ALLEN COUNTY SURVEYOR'S OFFICE, AND THE OWNER AS REQUIRED BY THE EROSION CONTROL PERMIT.

PUBLIC INFORMATION NOTE:

THE PROJECT OWNER/CONTRACTOR MUST POST NEAR THE ENTRANCE OR NEAR THE PROJECT FIELD OFFICE AND BE ACCESSIBLE TO THE PUBLIC SUCH THAT IT DOES NOT CREATE TRESPASS CONCERNS:

- . A COPY OF THE COMPLETED NOTICE OF INTENT (NOI) LETTER WITH PERMIT NUMBER. CONTACT INFORMATION (ADDRESS, PHONE, AND
- EMAIL) OF THE PROJECT SITE OWNER OR DESIGNATED CONTACT PERSON. THE NOI CONTAINS THIS INFORMATION.
- LOCATION OF THE CONSTRUCTION PLAN, IF ONE IS NOT STORED ON-SITE.

PERMANENT EROSION CONTROL DEVICES AND **MEASURES NOTE:**

THE CONTRACTOR SHALL CLEAN THE EROSION CONTROL DEVICES AND MEASURES OF, BUT NOT LIMITED TO, SEDIMENT, DEBRIS, AND ANY HYDROCARBONS WHEN CONSTRUCTION IS COMPLETE. WATER AND SEDIMENT FROM CLEANING PROCEDURES SHALL BE DISPOSED OF PROPERLY AND MUST NOT BE DEPOSITED INTO ANY SANITARY

SEWER SYSTEM. DISPOSAL OF ALL SEDIMENT, DEBRIS AND HYDROCARBONS MUST BE IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL REQUIREMENTS.

!! IMPORTANT !!

CONTRACTOR MUST MAINTAIN AND REPLACE ALL EXISTING DRAINAGE PATHS THROUGH THIS SITE, REGARDLESS OF GRAPHIC REPRESENTATION ON THE PLANS UNTIL PROPOSED IMPROVEMENTS ARE INSTALLED. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL EROSION CONTROL MEASURES AND DEVICES UNTIL ADEQUATE RE-VEGETATION AND STABILIZATION IS ACHIEVED.

NOTE:

STORM WATER SEWER LINES SHOWN ARE FOR REFERENCE ONLY. SEE SHEET C4.0 SITE UTILITY PLAN FOR STORM WATER SEWER LINE SIZE, INVERT, ETC.

PERMANENT OFF-SITE EXCESS SOIL AREA AND WETLAND NOTE:

EXCESS SOIL IS TO BE REMOVED FROM PROJECT SITE TO A PERMANENT SITE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIND A SITE TO PERMANENTLY PLACE THE EXCESS SOIL, EXECUTE ANY CONTRACTS NEEDED WITH THE PROPERTY OWNER, AND RESEARCH FOR THE POSSIBILITY OF WETLANDS ON THE EXCESS SOIL SITE. IF WETLANDS ARE FOUND, ANOTHER SITE SHOULD BE CHOSEN. IF THE CONTRACTOR WISHES TO USE A SITE THAT CONTAINS WETLANDS IT IS THE CONTRACTORS FINANCIAL RESPONSIBILITY TO HAVE THE WETLANDS ASSESSED AND DELINEATED BY A CERTIFIED ENVIRONMENTAL CONSULTING FIRM. IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE EROSION CONTROL DRAWINGS OF THE EXCESS SOIL SITE TO THE ALLEN COUNTY MS4 COORDINATOR FOR INSPECTION AND APPROVAL, TO ASSURE APPROPRIATE MEASURES WILL BE TAKEN TO PROTECT THE WETLANDS AND THAT THE WETLANDS WILL NOT BE DISTURBED. THE EXCESS SOIL PROPERTY SHALL HAVE EROSION CONTROL MEASURES AND DEVICES IN PLACE IN ACCORDANCE WITH THE LATEST INDIANA STORM WATER QUALITY MANUAL AND ANY LOCAL ORDINANCE. CONTRACTOR SHALL MAINTAIN THE EROSION CONTROL MEASURES AND DEVICES USED, IN ACCORDANCE WITH THE LATEST INDIANA STORM WATER QUALITY MANUAL AND LOCAL ORDINANCES. THE SITE SHALL BE FINE GRADED, SOIL STABILIZED, AND

TEMPORARY EROSION CONTROL DEVICES AND MEASURES REMOVED AT THE COMPLETION OF SOIL PLACEMENT.

SPILLS; REPORTING, CONTAINMENT, AND RESPONSE NOTE:

CONTRACTOR SHALL REPORT TO THE DEPARTMENT OF ENVIRONMENTAL MANAGEMENT, OFFICE OF LAND QUALITY, EMERGENCY RESPONSE SECTION AT:

(317) 233-7745 FOR IN-STATE CALLS 1-888-233-7745 (TOLL FREE) FOR OUT-OF-STATE CALLS

AND THE LOCAL SPILL HAZARDOUS MATERIALS TEAM

- SPILLS THAT DAMAGE THE WATERS OF THE STATE SO AS TO CAUSE DEATH OR ACUTE INJURY OR ILLNESS TO HUMANS OR ANIMALS.

- SPILLS FROM A FACILITY THAT HAD BEEN NOTIFIED IN WRITING BY A WATER UTILITY THAT IT IS LOCATED IN A DELINEATED PUBLIC WATER SUPPLY WELLHEAD PROTECTION AREA.

SPILLS THAT DAMAGE WATERS OF THE STATE AND THAT ARE LOCATED: WITHIN FIFTY (50) FEET OF A KNOWN PRIVATE DRINKING WATER WELL LOCATED BEYOND THE FACILITY PROPERTY BOUNDARY OR WITHIN ONE HUNDRED (100) YARDS OF ANY HIGH QUALITY WATER CLASSIFIED AS AN OUTSTANDING STATE RESOURCE WATER, ANY WATER DESIGNATED AS CAPABLE OF SUPPORTING A SALMONID FISHERY, OR ANY WATER THAT IS A FISH HATCHERY, FISH AND WILDLIFE AREA, NATURE PRESERVE, OR RECREATIONAL WATER OWNED BY THE DNR OR THE FEDERAL GOVERNMENT.

- SPILLS TO SURFACE WATER.

SPILLS TO SOIL BEYOND THE FACILITY BOUNDARY.

SPILLS TO SOIL WITHIN THE FACILITY BOUNDARY THAT ARE HAZARDOUS SUBSTANCES OR EXTREMELY HAZARDOUS SUBSTANCES OF ONE HUNDRED (100) POUNDS OR PETROLEUM THAT THE AMOUNT EXCEEDS FIFTY-FIVE (55) GALLONS.

- ANY SPILL FOR WHICH A SPILL RESPONSE HAS NOT BEEN DONE.

A SPILL OF ANY SIZE SHALL BE CONTAINED AND CLEANED UP IMMEDIATELY USING ACCEPTABLE METHODS ACCORDING TO THE TYPE OF MATERIAL SPILLED AND THE SURFACE THE SPILL OCCURRED ON

EROSION CONTROL KEY:

	TEMPORARY EROSION CONTROL DEVICES AND MEASURES		INSTALL SILT FENCE PER DETAIL #1/C5.1.		
			CONSTRUCTION ENTRANCE PER DETAIL #10/C5.1.		
		T 3	INSTALL YARD INLET PROTECTION DEVICE PER DETAIL #2/C5.1.		
			INSTALL PAVEMENT INLET PROTECTION DEVICE PER DETAIL #3/C5.1.		
		T5	INSTALL CONCRETE WASHOUT STRUCTURE PER DETAIL #6/C5.1.		
		T6	INSTALL CONCRETE WASHOUT AREA SIGN PER DETAIL #7/C5.1.		
			INSTALL TEMPORARY TOPSOIL STOCKPILE AREA SIGN PER DETAIL #5/C5.1.		
			INSTALL EROSION CONTROL BLANKET PER DETAIL #4/C5.1.		
>	~ ~ ~	T 9			
	PERMANENT EROSION CONTROL DEVICES AND MEASURES	P1	INSTALL VEGETATED SWALE PER DETAIL #8/C5.1.		
		P2>	EXISTING DETENTION POND.		
	ERO:				


FUELING AREA AND VEHICLE AND EQUIPMENT MAINTENANCE / MATERIAL STORAGE NOTE:


FUELING AREA:


- 1. ON-SITE VEHICLE AND EQUIPMENT FUELING SHALL ONLY BE USED WHERE IT IS IMPRACTICAL TO SEND VEHICLES AND EQUIPMENT OFF-SITE FOR FUELING. 2. IF ON-SITE FUELING IS NECESSARY, CONTRACTOR SHALL DESIGNATE A DEDICATED AN AREA
- TO BE USED. 3. CONTRACTOR SHALL SUPPLY, CLEARLY MARK, AND KEEP CLEAN-UP MATERIALS AND SPILL
- KITS AVAILABLE IN FUELING AREAS. 4. CONTRACTOR SHALL USE DRIP PANS OR ABSORBENT PADS DURING VEHICLE AND EQUIPMENT FUELING UNLESS FUELING IS CONDUCTED IN A DESIGNATED AREA, OVER AN
- IMPERMEABLE CONTAINMENT AREA. 5. FUELING AREAS SHALL BE ON LEVEL GRADE AND PROTECTED FROM STORM WATER RUN-ON AND RUN-OFF AND BE AT LEAST 100 FT FROM DOWNSTREAM DRAINAGE FACILITIES AND
- WATERCOURSES. 6. CONTRACTOR SHALL USE FUELING NOZZLES WITH AUTOMATIC SHUT-OFFS. FUELING OPERATIONS SHALL NOT BE LEFT UNATTENDED.
- 7. CONTRACTOR SHALL PROTECT FUELING AREAS WITH IMPERMEABLE BERMS AND OR DIKES TO PREVENT STORM WATER RUN-ON, RUN-OFF AND TO CONTAIN SPILLS.
- 8. CONTRACTOR SHALL NOT "TOP-OFF" FUEL TANKS. 9. CONTRACTOR SHALL INSPECT VEHICLES AND EQUIPMENT EACH DAY FOR LEAKS. IF LEAKS
- ARE FOUND, THEY MUST BE REPAIRED AND CLEANED-UP IMMEDIATELY AND/OR THE LEAKING VEHICLES OR EQUIPMENT REMOVED FROM THE PROJECT SITE. 10. CONTRACTOR SHALL DISPOSE OF ANY USED ABSORBENT SPILL KIT MATERIALS AND ANY CONTAMINATED SOILS ACCORDING TO FEDERAL, STATE AND LOCAL REGULATIONS.

VEHICLE AND EQUIPMENT MAINTENANCE / MATERIAL STORAGE AREA:


- 1. CONTRACTOR SHALL DESIGNATE A DEDICATED AREA TO BE USED IF STORING MATERIALS, MAINTAINING OR STORING VEHICLES AND EQUIPMENT ON-SITE.
- 2. STORAGE / MAINTENANCE AREAS SHALL BE ON LEVEL GRADE AND PROTECTED FROM STORM WATER RUN-ON AND RUN-OFF AND BE AT LEAST 100 FT FROM DOWNSTREAM DRAINAGE FACILITIES AND WATERCOURSES. 3. CONTRACTOR SHALL USE DRIP PANS OR ABSORBENT PADS DURING VEHICLE AND
- EQUIPMENT MAINTENANCE UNLESS MAINTENANCE IS CONDUCTED IN A DESIGNATED AREA, OVER AN IMPERMEABLE CONTAINMENT AREA.
- 4. CONTRACTOR SHALL SUPPLY, CLEARLY MARK, AND KEEP CLEAN-UP MATERIALS AND SPILL KITS AVAILABLE IN STORAGE / MAINTENANCE AREAS. 5. CONTRACTOR SHALL PROTECT STORAGE / MAINTENANCE AREAS WITH IMPERMEABLE
- BERMS AND OR DIKES TO PREVENT STORM WATER RUN-ON, RUN-OFF AND TO CONTAIN SPILLS.
- 6. CONTRACTOR SHALL PROVIDE IMPERMEABLE SPILL CONTAINMENT DIKES OR SECONDARY CONTAINMENT AROUND STORED OIL AND CHEMICAL DRUMS.
- 7. CONTRACTOR SHALL DISPOSE OF ANY USED ABSORBENT SPILL KIT MATERIALS AND ANY CONTAMINATED SOILS ACCORDING TO FEDERAL, STATE AND LOCAL REGULATIONS.












1 \ C7.0 NOT TO SCALE

PRESENT.

OVERNIGHT BARREL PLACEMENT

TYPE "C" LIGHT SHALL BE PROVIDED ON DRUMS WHEN USED OVERNIGHT.



TRAFFIC CONTROL NOTES:

- 1. PLANS ARE SHOWN FOR CONSTRUCTION WITHIN THE RIGHT-OF-WAY. 2. ALL TRAFFIC CONTROL "TRAFFIC CONTROL - FLAGGER" PLAN MUST FOLLOW INDOT MUTCD MOT STANDARDS FOR TEMPORARY LANE CLOSURES DURING DAYLIGHT HOURS.
- 3. CONSTRUCTION SHALL BE PHASED TO ALLOW THE REOPENING OF BOTH THE EASTBOUND AND WESTBOUND LANES AT THE END OF THE WORK DAY. INSTALL DRUM WITH TYPE C CONSTRUCTION WARNING LIGHT IF THE DROP-OFF IS MORE THAN 1 $\frac{1}{2}$ ". PLACE BARRELS AT EDGE OF DRIVE LANE DURING OVERNIGHT HOURS AS SHOWN ON DETAIL #1/C7.0..
- 4. A FLAGGER SHALL BE USED DURING ANY CONSTRUCTION THAT REDUCES THE LANE WIDTH FOR EITHER NORTHBOUND OR SOUTHBOUND TRAFFIC TO LESS THAN 10'
- 5. IMPLEMENT FLAGMEN AT EACH END OF THE CONSTRUCTION SITE. TRAFFIC CONTROL PERSONS SHALL BE CERTIFIED AND BE ABLE TO PROVIDE PROOF OF CERTIFICATION TO INDOT PERSONNEL. THE USE OF PORTABLE SIGNAL DEVICES ARE NOT ALLOWED.
- 6. THE CONTRACTOR SHALL LEAVE ONE LANE OF TRAFFIC OPEN AT ALL TIMES WITH FLAGMEN.
- 7. OVERNIGHT LANE CLOSURES ARE NOT PERMITTED.
- 8. INSTALL CONSTRUCTION SIGNS PER INDOT STANDARDS AND SPECIFICATION.
- 9. REMOVE SIGNS 2 AND 3 WHEN WORK IS NOT OCCURRING.

