

ADDENDUM NO. 2

Guion Creek Middle School – 224067.00  
Lincoln Middle School – 224068.00  
New Augusta Public Academy North – 224069.00

Interior Refresh

MSD of Pike Township  
Indianapolis, Indiana

Index of Contents

Addendum No. 2, 6 Items, 2 pages

New Project Manual Section: 10 14 23.16 – Interior Panel Signage

Guion Creek Middle School Revised Drawing Sheets: AD10A, AD10B, AD10C, AD10D, AF10A, AF10B,  
AF10C, AF10D, AF10E, AF10F, AF10G, AF10H, AF10J, and AF10K

Lincoln Middle School Revised Drawing Sheets: AD10A, AD10B, AD10C, AD10D, AD10E, AD10F, AD10G,  
AD10J, AF10A, AF10B, AF10C, AF10D, AF10E, AF10F, AF10G, AF10H, AF10J, AF201, AF601, AC10A,  
AC10B, AC10C, AC10D, AC10E, AC10F, AC10G, AC10H, AC10J and E-001

New Augusta Public Academy North Revised Drawing Sheets: AD10A, AD10B, AD10C, AD10D, AD10E,  
AD10F, AF10A, AF10B, AF10C, AF10D, AF10E, AF10F, AF10G, AF10H, AF201, AF601, AC10A, AC10B,  
AC10C, AC10D, AC10E, AC10F AC10G, AC10H and E-001

Pre-Bid Sign-in sheet.

Date: February 13, 2025

FANNING/HOWEY ASSOCIATES, INC.  
ARCHITECTS/ENGINEERS/CONSULTANTS

TO: ALL BIDDERS OF RECORD

ADDENDUM NO. 2 to Drawings and Project Manual, dated January 24, 2025, for MSD of Pike Township, 3950 W. 56<sup>th</sup> Street, Indianapolis, Indiana 46278; as prepared by Fanning/Howey Associates, Inc., Indianapolis, Indiana.

This Addendum shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes, and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified in this Addendum.

Each bidder shall acknowledge receipt of this Addendum in his proposal or bid.

NOTE: Bidders are responsible for becoming familiar with every item of this Addendum. (This includes miscellaneous items at the very end of this Addendum.)

RE: ALL BIDDERS

ITEM NO. 1. NEW PROJECT MANUAL SECTIONS

- A. New Project Manual Section 10 14 23.16 – Interior Panel Signage is included with and hereby made a part of this Addendum.

ITEM NO. 2. PROJECT MANUAL, SECTION 01 10 00 - SUMMARY

- A. Replace Article 2.8., C., as follows:

“C. All work at each location shall achieve final completion by July 17, 2026”.

1. Contractor’s construction phasing and scheduling should focus on the academic/classroom pod corridors scope of work completion during the summer of 2025 in all buildings.
2. Demolition work within academic/classroom pods shall not commence without assurance of new work completion in the available school calendar period. Differing levels of construction and completion between academic/classroom pods within a building is unacceptable.”

ITEM NO. 3. PROJECT MANUAL, SECTION 09 84 33 – SOUND-ABSORBING WALL UNITS

- A. Delete this Section in its entirety.

**GUION CREEK MIDDLE SCHOOL – 224067.00**

ITEM NO. 4. REVISED DRAWING SHEET

- A. Drawing Sheets AD10A, AD10B, AD10C, AD10D, AF10A, AF10B, AF10C, AF10D, AF10E, AF10F, AF10G, AF10H, AF10J, and AF10K have been revised, dated 2/13/25, and is included with and hereby made a part of this Addendum. These Drawings supersede the original documents.

**LINCOLN MIDDLE SCHOOL – 224068.00**

ITEM NO. 5. REVISED DRAWING SHEET

- A. Drawing Sheets AD10A, AD10B, AD10C, AD10D, AD10E, AD10F, AD10G, AD10J, AF10A, AF10B, AF10C, AF10D, AF10E, AF10F, AF10G, AF10H, AF10J, AF201, AF601, AC10A, AC10B, AC10C, AC10D, AC10E, AC10F, AC10G, AC10H, AC10J and E-001 have been revised, dated 2/13/25, and is included with and hereby made a part of this Addendum. These Drawings supersede the original documents.

**NEW AUGUSTA PUBLIC ACADEMY NORTH – 224069.00**

ITEM NO. 6. REVISED DRAWING SHEET

- A. Drawing Sheets AD10A, AD10B, AD10C, AD10D, AD10E, AD10F, AF10A, AF10B, AF10C, AF10D, AF10E, AF10F, AF10G, AF10H, AF201, AF601, AC10A, AC10B, AC10C, AC10D, AC10E, AC10F, AC10G, AC10H and E-001 have been revised, dated 2/13/25, and is included with and hereby made a part of this Addendum. These Drawings supersede the original documents.

END OF ADDENDUM

## SECTION 10 14 23.16 – INTERIOR PANEL SIGNAGE

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes the following:
  - 1. Custom vinyl wall decal/graphics

#### 1.2 DEFINITIONS

- A. Accessibility Standard: U.S. Department of Justice's "2010 ADA Standards for Accessible Design."

#### 1.3 COORDINATION

- A. Coordinate placement of anchorage devices with templates for installing signs.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Show fabrication and installation details for signs.
  - 1. Show sign mounting heights, locations of supplementary supports to be provided by others, and accessories.
  - 2. Provide message list, typestyles, graphic elements, including tactile characters and Braille, and layout for each sign.

#### 1.5 CLOSEOUT SUBMITTALS:

- A. General: Closeout Submittals are to be submitted with O and M Manuals only. Do not submit with other ACTION and INFORMATIONAL Submittals:
  - 1. Maintenance Data: For signs to include in maintenance manuals.
  - 2. Warranty: Special warranty specified in this Section.

#### 1.6 FIELD CONDITIONS

- A. Field Measurements: Verify locations of anchorage devices embedded in permanent construction by field measurements before fabrication and indicate measurements on Shop Drawings.

#### 1.7 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of signs that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Deterioration of finishes beyond normal weathering.
    - b. Deterioration of embedded graphic image, colors, and sign lamination.
  - 2. Warranty Period: Five years from date of Substantial Completion.

### PART 2 - PRODUCTS

#### 2.1 PERFORMANCE REQUIREMENTS

- A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design," ICC A117.1, and requirements of authorities with jurisdiction for signs.

## 2.2 MATERIALS

- A. Vinyl Film: UV-resistant vinyl film of nominal thickness indicated, with pressure-sensitive, permanent adhesive on back; die cut to form characters or images as indicated and suitable for exterior applications.

## 2.3 VINYL WALL GRAPHICS

- A. Applied Vinyl Wall Graphics (Custom vinyl wall decal/graphic): Vinyl film of nominal thickness of between 3 and 3.5 mil, adhesive; aggressive and removable, unprinted outdoor durability; 5 years, indoor durability; 5 years and ASTM E 84, Class A surface burning resistance.
  - 1. Manufacturers: Subject to compliance with requirements provide one of the following:
    - a. Avery Dennison
    - b. Orafol
    - c. MACtac
  - 2. Size: As indicated on Drawings.
  - 3. Substrate: As indicated on Drawings.
  - 4. Graphics: As indicated on Drawings.

## 2.4 ACCESSORIES

- A. Adhesive: As recommended by sign manufacturer.

## 2.5 FABRICATION

- A. Shop and Subsurface-Applied Vinyl: Align vinyl film in final position and apply to surface. Firmly press film from the middle outward to obtain good bond without blisters or fish mouths.

## 2.6 FINISHES, GENERAL

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of work.
- B. Verify that sign-support surfaces are within tolerances to accommodate signs without gaps or irregularities between backs of signs and support surfaces, unless otherwise indicated.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. General: Install signs and accessories, using mounting methods of types described and complying with manufacturer's written instructions.
  - 1. Install signs level, plumb, and at heights indicated, with sign surfaces free of distortion and other defects in appearance.
  - 2. Install signs on walls adjacent to latch side of door where applicable. Where not indicated or possible, such as double doors, install signs on nearest adjacent walls. Locate to allow approach within 3 inches of sign without encountering protruding objects or standing within swing of door.
  - 3. Before installation, verify that sign surfaces are clean and free of materials or debris that would impair installation.
  - 4. Install signs so they do not protrude or obstruct according to the accessibility standard.
- B. Field-Applied, Vinyl Signs: Clean and dry substrate. Align sign characters in final position before removing release liner. Remove release liner in stages, and apply and firmly press characters into final position. Press from the middle outward to obtain good bond without blisters or fish mouths. Remove carrier film without disturbing applied vinyl film.

### 3.3 ADJUSTING AND CLEANING

- A. Remove and replace damaged or deformed signs and signs that do not comply with specified requirements. Replace signs with damaged or deteriorated finishes or components that cannot be successfully repaired by finish touchup or similar minor repair procedures.
- B. Remove temporary protective coverings and strippable films as signs are installed.
- C. On completion of installation, clean exposed surfaces of signs according to manufacturer's written instructions, and touch up minor nicks and abrasions in finish. Maintain signs in a clean condition during construction and protect from damage until acceptance by Owner.

END OF SECTION 10 14 23.16

Project Name MSD OF PIKE TOWNSHIP  
 PIKE MIDDLE SCHOOL CORRIDOR REFRESH PROJECTS  
 Project No. GUION CREEK MIDDLE SCHOOL - 224067.00  
 LINCOLN MIDDLE SCHOOL - 224068.00  
 Meeting Date NEW AUGUSTA PUBLIC ACADEMY NORTH - 224069.00  
 FEBRUARY 6, 2025

PLEASE PRINT CLEARLY. YOUR NAME AND  
 TITLE WILL BE INCLUDED IN THE MEETING  
 REPORT.

THANK YOU!

**SIGN-IN SHEET**

NAME (Please print)	TITLE	COMPANY	PHONE/ FAX	E-MAIL
Clayton Gruber	Director of Facilities & Security	MSD of Pike Township		cgruber@pike.k12.in.us
Peter Winters	Project Manager	Fanning Howey	317.410.1289	pwinters@fhai.com
Dan Hammond	Construction Administrator	Fanning Howey	317.965.3568	dhammond@fhai.com
Hannah Stineburg	Interior Designer	Fanning Howey		hstineburg@fhai.com
Justin Caffey	PM	HP Legacy	317 522 3425	jcaffey@hplegacyinc.com
Lance Dischler	super	HP Legacy	317-837-0225	ldischler@hplegacyinc.com
Jacob Henderson	PM	Blankleys	317-800-1244	jacobhenderson@blankleys.com
HVE N. Bouris	Project Manager	Bousk	317 627-8425	HABouris@Bousk.com
Craig Applegate	Sales Executive	FSG Electric	317-570-4917	Craig.Applegate@fsg.com
Shawn Annandale	Sales Engineer	C-CAT	317-902-7184	Sannandale@ccat.com
Chris Kerns	Est.	Powers & Sons	317-551-746	ckerns@powersandsons.com
Brooke Gallant	Person Eng.	POWERS & SONS	8643827105	bgallant@powersandsons.com

