

**WHITLEY COUNTY CONSOLIDATED SCHOOLS  
WCCS Northern Heights Elementary Mechanical Renovation-2025 ; DC's #20240001  
3/4/2025**

**ADDENDUM NO. 2**

This addendum is issued as a supplement to the plans and specifications and shall be considered an integral part of the same.

- Item: 2.01**  
Location: M4.2 - Mechanical Schedules  
Description: Note 18 in Boiler schedule notes to be revised. Boiler pump to be sized for flow and delta t for Boiler system, not 350gpm.
- Item: 2.02**  
Location: Sheets M4.1, M4.2  
Description: Condensing Unit Schedule and Hot Water Coils Schedule are FOR REFERNECE ONLY, and will be owner furnished.
- Item: 2.03**  
Location: Sheet M2.1  
Description: Note existing VFD's for AHUs are unitstrut mounted adjacent to each AHU. Note M25 should read: "EXISTING VFDS TO REPLACED WITH NEW PROVIDED BY OWNER AND INSTALLED BY ELECTRICAL CONTRACTOR"
- Item: 2.04**  
Location: Sheet E1.2, Power Plan - Second Level - Unit  
Description: Note existing VFD's for AHUs are unitstrut mounted adjacent to each AHU. Key Note EP08 shoud read "REMOVE EXISTING VFD AND INSTALL NEW VFD PROVIDED BY OWNER, REINSTALL ON EXISTING UNI-STRUT MOUNT"
- Item: 2.05**  
Location: Sheet E4.6 - Electrical Schedules and Details  
Description: Fixture, F02 shall be as follows; 2x4 LOW-PROFILE "VOLUMETRIC" STYLE LAY-IN FIXUTRE PART NO: CBT24-A-LSCS-EDD, 5800 LUMENS, RECESSED, WHITE, WITH 0-10V 1% DIMMING DRIVER BY COLUMBIA.

*\*No revised or updated sheets are issued with this addendum.*

Each contractor is responsible for incorporating all changes into their bid.

Respectfully submitted,



Craig Scully, PE, Project Manager  
Design Collaborative, Inc.  
CSS/KLB