



Addendum #1
Frontier School Corporation

Frontier Elementary Boiler Replacement & Mech. Upgrades

Date: July 15, 2025
Project: Frontier Elementary Boiler Replacement & Mechanical Upgrades
Project #: 25032
Pages: 1 of 2 pages
Bid Dates: **TUESDAY, July 22nd, 2025 at 2:00 pm (prevailing local time)**

General Note:

The original Specifications and Drawings dated June 27th, 2025 for the project referenced above are amended as noted in this Addendum No. 1. Receipt of this Addendum and any subsequent Addenda must be acknowledged on the Bid Form. Items changed or added by this addendum are to take precedence over the items or descriptions of the work in the project manual and the drawings. Items not mentioned in this addendum are to remain as described in the original plans and specifications.

General Items:

1. See sign-in sheet attached to end of Addendum #1.
2. Question received via email to krM.
 - a. **Q:** AHU Schedule Note #2 states that the chilled water system utilizes glycol but doesn't say what type of glycol (propylene or ethylene) or %. Can you please ask the question as that will significantly impact the coil selection.
 - b. **A:** The chilled water system utilizes propylene glycol.
3. Question received via email to KBSO.
 - a. **Q:** Lochinvar allows for PVC/CPVC air and vent piping for the boiler model that is listed on the schedule. The specifications seem to only allow for stainless steel boiler vent piping. Would PVC/CPVC be acceptable for boiler air and vent piping?
 - b. **A:** PCV/CPVC is acceptable for boiler venting material.

Specifications Items:

Section 23 09 23 – Direct Digital Control (DDC) System for HVAC

1. The following statement has been removed from the specification section: "TCC to expand existing Niagara Framework (Tridium) automation system to new equipment."
2. Specification Acceptable Control Installation and Service Contractor revised to state only Grantham Company.



Addendum #1
Frontier School Corporation
Frontier Elementary Boiler Replacement & Mech. Upgrades

Section 23 52 16 – Condensing Boilers

1. Laars added to list of approved manufacturers.
2. Boiler protocol adjusted to be BACnet IP.
3. Delegated Design Submittal section has been removed from the specifications.
4. Boilers to utilize room air for combustion intake.
5. PVC / CPVC is an allowable material for boiler venting. Refer to manufacturers requirements.

Drawing Set Items:

Sheet M102 – Roof Mechanical Plan

1. Plan Note #2 added. All roof work to be completed by Danco Roofing Services.

Sheet M401 – Mechanical Enlarged Plans

1. Boiler's will now utilize room air for combustion intake.
2. Plan Note #5 adjusted to describe scope of work.

Sheet E401 – Enlarged Electrical Plans

1. Duct mounted smoke detector relocated to be shown on the return air duct.

Attachments:

1. Specification Section 23 09 23 – Direct Digital Controls (DDC) System for HVAC
2. Specification Section 23 52 16 – Condensing Boilers
3. Sheet M102 – Roof Mechanical Plan
4. Sheet M401 – Mechanical Enlarged Plans
5. Sheet E401 – Enlarged Electrical Plans
6. Pre-Bid Walk-Thru Sign-In Sheet

END

SECTION 23 09 23
DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

PART 1 GENERAL

1.01 SUMMARY

- A. Scope:
 - 1. The Temperature Control Contractor (TCC) shall install, furnish, program, and turn over to client a complete operating DDC system for monitoring and controlling of MEP systems as shown in the Contract Documents.
- B. Section Includes:
 - 1. DDC system for monitoring and controlling of MEP systems.
 - 2. Delivery of selected control devices to equipment and systems manufacturers for factory installation and to HVAC systems installers for field installation.
- C. Scope not included in 230923:
 - 1. Electrical Contractor (EC) to provide all wiring to all motor starters, variable frequency drives, and motor control centers.
 - 2. EC to provide 120 V/60 Hz power to all direct digital controllers (DDC) that require 120 V power.
 - 3. Sheet Metal Contractor shall install all motorized dampers, duct mounted airflow measuring stations, thermowells (for temperature & pressure sensors), flow meters, control valves, and other accessories that are furnished by the TCC.
 - 4. Mechanical Contractor shall install all temperature and pressure sensing wells and control valves furnished by the Temperature Control Contractor.

1.02 DEFINITIONS

- A. Algorithm: A logical procedure for solving a recurrent mathematical problem. A prescribed set of well-defined rules or processes for solving a problem in a finite number of steps.
- B. Analog: A continuously varying signal value, such as current, flow, pressure, or temperature.
- C. BACnet Specific Definitions:
 - 1. BACnet: Building Automation Control Network Protocol, ASHRAE 135. A communications protocol allowing devices to communicate data over and services over a network.
 - 2. BACnet Interoperability Building Blocks (BIBBs): BIBB defines a small portion of BACnet functionality that is needed to perform a particular task. BIBBs are combined to build the BACnet functional requirements for a device.
 - 3. BACnet/IP: Defines and allows using a reserved UDP socket to transmit BACnet messages over IP networks. A BACnet/IP network is a collection of one or more IP subnetworks that share the same BACnet network number.
 - 4. BACnet Testing Laboratories (BTL): Organization responsible for testing products for compliance with ASHRAE 135, operated under direction of BACnet International.
 - 5. PICS (Protocol Implementation Conformance Statement): Written document that identifies the particular options specified by BACnet that are implemented in a device.
- D. Binary: Two-state signal where a high signal level represents "ON" or "OPEN" condition and a low signal level represents "OFF" or "CLOSED" condition. "Digital" is sometimes used interchangeably with "Binary" to indicate a two-state signal.
- E. Controller: Generic term for any standalone, microprocessor-based, digital controller residing on a network, used for local or global control. Three types of controllers are indicated: Network Controller, Programmable Application Controller, and Application-Specific Controller.

- F. Control System Integrator: An entity that assists in expansion of existing enterprise system and support of additional operator interfaces to I/O being added to existing enterprise system.
- G. COV: Changes of value.
- H. DDC System Provider: Authorized representative of, and trained by, DDC system manufacturer and responsible for execution of DDC system Work indicated.
- I. Distributed Control: Processing of system data is decentralized and control decisions are made at subsystem level. System operational programs and information are provided to remote subsystems and status is reported back. On loss of communication, subsystems shall be capable of operating in a standalone mode using the last best available data.
- J. DOCSIS: Data-Over Cable Service Interface Specifications.
- K. Gateway: Bidirectional protocol translator that connects control systems that use different communication protocols.
- L. HLC: Heavy load conditions.
- M. I/O: System through which information is received and transmitted. I/O refers to analog input (AI), binary input (BI), analog output (AO) and binary output (BO). Analog signals are continuous and represent control influences such as flow, level, moisture, pressure, and temperature. Binary signals convert electronic signals to digital pulses (values) and generally represent two-position operating and alarm status. "Digital," (DI and (DO), is sometimes used interchangeably with "Binary," (BI) and (BO), respectively.
- N. LAN: Local area network.
- O. LNS: LonWorks Network Services.
- P. LON Specific Definitions:
 - 1. FTT-10: Echelon Transmitter-Free Topology Transceiver.
 - 2. LonMark: Association comprising suppliers and installers of LonTalk products. Association provides guidelines for implementing LonTalk protocol to ensure interoperability through a standard or consistent implementation.
 - 3. LonTalk: An open standard protocol developed by the Echelon Corporation that uses a "Neuron Chip" for communication. LonTalk is a register trademark of Echelon.
 - 4. LonWorks: Network technology developed by Echelon.
 - 5. Node: Device that communicates using CEA-709.1-C protocol and that is connected to a CEA-709.1-C network.
 - 6. Node Address: The logical address of a node on the network, consisting of a Domain number, Subnet number, and Node number. "Node number" portion of an address is a number assigned to device during installation, is unique within a subnet, and is not a factory-set unique Node ID.
 - 7. Node ID: A unique 48-bit identifier assigned at factory to each CEA-709.1-C device. Sometimes called a "Neuron ID."
 - 8. Program ID: An identifier (number) stored in a device (usually EEPROM) that identifies node manufacturer, functionality of device (application and sequence), transceiver used, and intended device usage.
 - 9. Standard Configuration Property Type (SCPT): Pronounced "skip-it." A standard format type maintained by LonMark International for configuration properties.
 - 10. Standard Network Variable Type (SNVT): Pronounced "snivet." A standard format type maintained by LonMark used to define data information transmitted and received by individual nodes. "SNVT" is used in two ways. It is an acronym for "Standard Network Variable Type" and is often used to indicate a network variable itself (i.e., it can mean "a network variable of a standard network variable type").

11. Subnet: Consists of a logical grouping of up to 127 nodes, where logical grouping is defined by node addressing. Each subnet is assigned a number, which is unique within a Domain. See "Node Address."
 12. TP/FT-10: Free Topology Twisted Pair network defined by CEA-709.3 and is most common media type for a CEA-709.1-C control network.
 13. TP/XF-1250: High-speed, 1.25-Mbps, twisted-pair, doubly terminated bus network defined by "LonMark Interoperability Guidelines" typically used only to connect multiple TP/FT-10 networks.
 14. User-Defined Configuration Property Type (UCPT): Pronounced "U-Keep-It." A Configuration Property format type that is defined by device manufacturer.
 15. User-Defined Network Variable Type (UNVT): Network variable format defined by device manufacturer. UNVTs create non-standard communications that other vendors' devices may not correctly interpret and may negatively impact system operation. UNVTs are not allowed.
- Q. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control, signaling power-limited circuits.
- R. Modbus TCP/IP: An open protocol for exchange of process data.
- S. MS/TP: Master-slave/token-passing, IEE 8802-3. Datalink protocol LAN option that uses twisted-pair wire for low-speed communication.
- T. Network Controller: Digital controller, which supports a family of programmable application controllers and application-specific controllers, that communicates on peer-to-peer network for transmission of global data.
- U. Network Repeater: Device that receives data packet from one network and rebroadcasts it to another network. No routing information is added to protocol.
- V. PDA: Personal digital assistant.
- W. Peer to Peer: Networking architecture that treats all network stations as equal partners.
- X. RAM: Random access memory.
- Y. RF: Radio frequency.
- Z. Router: Device connecting two or more networks at network layer.
- AA. TCP/IP: Transport control protocol/Internet protocol incorporated into Microsoft Windows.
- BB. UPS: Uninterruptible power supply.
- CC. USB: Universal Serial Bus.
- DD. User Datagram Protocol (UDP): This protocol assumes that the IP is used as the underlying protocol.
- EE. VAV: Variable air volume.
- FF. WLED: White light emitting diode.

1.03 ACTION SUBMITTALS

- A. Product Data: For each type of product include the following:
1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
 2. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
 3. Product description with complete technical data, performance curves, and product specification sheets.

4. Installation, operation and maintenance instructions including factors effecting performance.
 5. Bill of materials of indicating quantity, manufacturer, and extended model number for each unique product.
 6. When manufacturer's product datasheets apply to a product series rather than a specific product model, clearly indicate and highlight only applicable information.
 7. Each submitted piece of product literature shall clearly cross reference specification and drawings that submittal is to cover.
- B. Shop Drawings:
1. Include plans, elevations, sections, and mounting details where applicable.
 2. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 3. Detail means of vibration isolation and show attachments to rotating equipment.
 4. Plan Drawings indicating the following:
 - a. Screened backgrounds of walls, structural grid lines, HVAC equipment, ductwork and piping.
 - b. Room names and numbers with coordinated placement to avoid interference with control products indicated.
 - c. Each desktop operator workstation, server, gateway, router, DDC controller, control panel instrument connecting to DDC controller, and damper and valve connecting to DDC controller, if included in Project.
 - d. Exact placement of products in rooms, ducts, and piping to reflect proposed installed condition.
 - e. Network communication cable and raceway routing.
 - f. Proposed routing of wiring, cabling, conduit, and tubing, coordinated with building services for review before installation.
 5. Schematic drawings for each controlled HVAC system indicating the following:
 - a. I/O points labeled with point names shown. Indicate instrument range, normal operating set points, and alarm set points. Indicate fail position of each damper and valve, if included in Project.
 - b. I/O listed in table format showing point name, type of device, manufacturer, model number, and cross-reference to product data sheet number.
 - c. A graphic showing location of control I/O in proper relationship to HVAC system.
 - d. Wiring diagram with each I/O point having a unique identification and indicating labels for all wiring terminals.
 - e. Unique identification of each I/O that shall be consistently used between different drawings showing same point.
 - f. Elementary wiring diagrams of controls for HVAC equipment motor circuits including interlocks, switches, relays and interface to DDC controllers.
 - g. Narrative sequence of operation.
 - h. Graphic sequence of operation, showing all inputs and output logical blocks.
 6. Control panel drawings indicating the following:
 - a. Panel dimensions, materials, size, and location of field cable, raceways, and tubing connections.
 - b. Interior subpanel layout, drawn to scale and showing all internal components, cabling and wiring raceways, nameplates and allocated spare space.

- c. Front, rear, and side elevations and nameplate legend.
 - d. Unique drawing for each panel.
- 7. DDC system network riser diagram indicating the following:
 - a. Each device connected to network with unique identification for each.
 - b. Interconnection of each different network in DDC system.
 - c. For each network, indicate communication protocol, speed and physical means of interconnecting network devices, such as copper cable type, or fiber-optic cable type. Indicate raceway type and size for each.
 - d. Each network port for connection of an operator workstation or other type of operator interface with unique identification for each.
- 8. DDC system electrical power riser diagram indicating the following:
 - a. Each point of connection to field power with requirements (volts/phase/hertz/amperes/connection type) listed for each.
 - b. Each control power supply including, as applicable, transformers, power-line conditioners, transient voltage suppression and high filter noise units, DC power supplies, and UPS units with unique identification for each.
 - c. Each product requiring power with requirements (volts/phase/hertz/amperes/connection type) listed for each.
 - d. Power wiring type and size, race type, and size for each.
- 9. Monitoring and control signal diagrams indicating the following:
 - a. Control signal cable and wiring between controllers and I/O.
 - b. Point-to-point schematic wiring diagrams for each product.
 - c. Control signal tubing to sensors, switches and transmitters.
 - d. Process signal tubing to sensors, switches and transmitters.
- C. System Description:
 - 1. Full description of DDC system architecture, network configuration, operator interfaces and peripherals, servers, controller types and applications, gateways, routers and other network devices, and power supplies.
 - 2. Complete listing and description of each report, log and trend for format and timing and events which initiate generation.
 - 3. System and product operation under each potential failure condition including, but not limited to, the following:
 - a. Loss of power.
 - b. Loss of network communication signal.
 - c. Loss of controller signals to inputs and outputs.
 - d. Operator workstation failure.
 - e. Gateway failure.
 - f. Network failure
 - g. Controller failure.
 - h. Instrument failure.
 - i. Control damper and valve actuator failure.
 - 4. Complete bibliography of documentation and media to be delivered to Owner.
 - 5. Description of testing plans and procedures.
 - 6. Description of Owner training.

D. Samples:

1. For each exposed product, installed in finished space for approval of selection of aesthetic characteristics.

1.04 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Plan drawings, reflected ceiling plan(s), and other details, drawn to scale and coordinated with each other, using input from installers of the items involved.
- B. Qualification Data:
 1. Systems Provider Qualification Data:
 - a. Resume of project manager assigned to Project.
 - b. Resumes of application engineering staff assigned to Project.
 - c. Resumes of installation and programming technicians assigned to Project.
 - d. Resumes of service technicians assigned to Project.
 - e. Brief description of past project including physical address, floor area, number of floors, building system cooling and heating capacity and building's primary function.
 - f. Description of past project DDC system, noting similarities to Project scope and complexity indicated.
 - g. Names of staff assigned to past project that will also be assigned to execute work of this Project.
 - h. Owner contact information for past project including name, phone number, and e-mail address.
 - i. Contractor contact information for past project including name, phone number, and e-mail address.
 - j. Architect and Engineer contact information for past project including name, phone number, and e-mail address.
 2. Manufacturer's qualification data.
 3. Testing agency's qualifications data.
- C. Welding certificates.
- D. Product Certificates:
 1. Data Communications Protocol Certificates: Certifying that each proposed DDC system component complies with ASHRAE 135.
- E. Product Test Reports: For each product that requires testing to be performed by manufacturer.
- F. Preconstruction Test Reports: For each separate test performed.
- G. Source quality-control reports.
- H. Field quality-control reports.
- I. Sample Warranty: For manufacturer's warranty.

1.05 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For DDC system to include in emergency, operation and maintenance manuals.
 1. In addition include the following:
 - a. Project Record Drawings of as-built versions of submittal Shop Drawings provided in electronic PDF format.
 - b. Testing and commissioning reports and checklists of completed final versions of reports, checklists, and trend logs.
 - c. As-built versions of submittal Product Data.

- d. Names, addresses, e-mail addresses and 24-hour telephone numbers of Installer and service representatives for DDC system and products.
- e. Operator's manual with procedures for operating control systems including logging on and off, handling alarms, producing point reports, trending data, overriding computer control and changing set points and variables.
- f. Programming manuals with description of programming language and syntax, of statements for algorithms and calculations used, of point database creation and modification, of program creation and modification, and of editor use.
- g. Engineering, installation, and maintenance manuals that explain how to:
 - 1) Design and install new points, panels, and other hardware.
 - 2) Perform preventive maintenance and calibration.
 - 3) Debug hardware problems.
 - 4) Repair or replace hardware.
- h. Documentation of all programs created using custom programming language including set points, tuning parameters, and object database.
- i. Backup copy of graphic files, programs, and database.
- j. List of recommended spare parts with part numbers and suppliers.
- k. Complete original-issue documentation, installation, and maintenance information for furnished third-party hardware including computer equipment and sensors.
- l. Complete original-issue copies of furnished software, including operating systems, custom programming language, operator workstation software, and graphics software.
- m. Licenses, guarantees, and warranty documents.
- n. Recommended preventive maintenance procedures for system components, including schedule of tasks such as inspection, cleaning, and calibration; time between tasks; and task descriptions.
- o. Owner training materials.

1.06 QUALITY ASSURANCE

- A. DDC System Manufacturer Qualifications:
 - 1. Nationally recognized manufacturer of DDC systems and products.
 - 2. DDC systems with similar requirements to those indicated for a continuous period of 5 years within time of bid.
 - 3. DDC systems and products that have been successfully tested and in use on at least 3 past projects.
 - 4. Having complete published catalog literature, installation, operation and maintenance manuals for all products intended for use.
 - 5. Having full-time in-house employees for the following:
 - a. Product research and development.
 - b. Product and application engineering.
 - c. Product manufacturing, testing and quality control.
 - d. Technical support for DDC system installation training, commissioning and troubleshooting of installations.
 - e. Owner operator training.
 - 6. Acceptable Control Supplier:
 - a. Delta.
 - 7. Acceptable Control Installation and Service Contractor:

a. Grantham Company

- B. DDC System Provider Qualifications:
1. Authorized representative of, and trained by, DDC system manufacturer.
 2. In-place facility located within 150 miles of Project and be capable of to respond on-site within 4 hours of notice.
 3. Staffing resources of competent and experienced full-time employees that are assigned to execute work according to schedule.
 4. Service and maintenance staff assigned to support Project during warranty period.
 5. Product parts inventory to support on-going DDC system operation for a period of not less than 5 years after Substantial Completion.
 6. DDC system manufacturer's backing to take over execution of Work if necessary to comply with requirements indicated. Include Project-specific written letter, signed by manufacturer's corporate officer, if requested.
- C. Testing Agency Qualifications: Member company of NETA or an NRTL.
1. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.
- D. Welding Qualifications: Qualify procedures and personnel according to the following:
1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."
 2. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum."
 3. AWS D1.3/D1.3M, "Structural Welding Code - Sheet Steel."
 4. AWS D1.4/D1.4M, "Structural Welding Code - Reinforcing Steel."
- E. Pipe and Pressure-Vessel Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

1.07 WARRANTY

- A. Manufacturer's Warranty: Manufacturer and Installer agree to repair or replace products that fail in materials or workmanship within specified warranty period at no cost to client.
1. Failures shall be adjusted, repaired, or replaced at no additional cost or reduction in service to Owner.
 2. Include updates or upgrades to software and firmware if necessary to resolve deficiencies.
 - a. Install updates only after receiving Owner's written authorization.
 3. Warranty service shall occur during normal business hours and commence within 24 hours of Owner's warranty service request.
 4. Warranty Period: 3 years from date of Substantial Completion. Warranty shall cover labor, material, replacement, and repairs for work performed during warranty period.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Delta.

2.02 DESCRIPTION

- A. Microprocessor-based monitoring and control including analog/digital conversion and program logic. A control loop or subsystem in which digital and analog information is received and processed by a microprocessor, and digital control signals are generated based on control algorithms and transmitted to field devices to achieve a set of predefined conditions.
1. DDC system shall consist of a high-speed, peer-to-peer network of distributed DDC controllers, other network devices, operator interfaces, and software.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.03 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional to design DDC system to satisfy requirements indicated.
 - 1. System Performance Objectives:
 - a. DDC system shall manage HVAC systems.
 - b. DDC system control shall operate HVAC systems to achieve optimum operating costs while using least possible energy and maintaining specified performance.
 - c. DDC system shall respond to power failures, HVAC equipment failures, and adverse and emergency conditions encountered through connected I/O points.
 - d. DDC system shall operate while unattended by an operator and through operator interaction.
 - e. DDC system shall record & store trends and transaction of events and produce report information such as performance, energy, occupancies, and equipment operation.
- B. Surface-Burning Characteristics: Products installed in ducts, equipment, and return-air paths shall comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 25 or less.
 - 2. Smoke-Developed Index: 50 or less.
- C. DDC System Data Storage:
 - 1. Include server(s) with disk drive data storage to archive not less than 24 consecutive months of historical data for all I/O points connected to system, including alarms, event histories, transaction logs, trends and other information indicated.
 - 2. When logged onto a server, operator shall be able to also interact with any DDC controller connected to DDC system as required for functional operation of DDC system.
 - 3. Server(s) shall be used for application configuration; for archiving, reporting and trending of data; for operator transaction archiving and reporting; for network information management; for alarm annunciation; and for operator interface tasks and controls application management.
 - 4. Server(s) shall use IT industry-standard database platforms such as Microsoft SQL Server and Microsoft Data Engine (MSDE).
- D. Future Expandability:
 - 1. DDC system size shall be expandable to an ultimate capacity of at least 125% times total I/O points indicated.
 - 2. Additional DDC controllers, I/O and associated wiring shall be all that is needed to achieve ultimate capacity. Initial network infrastructure shall be designed and installed to support ultimate capacity.
 - 3. Operator interfaces installed initially shall not require hardware and software additions and revisions for ultimate capacity.
- E. Environmental Conditions for Controllers, Gateways, and Routers:
 - 1. Products shall operate without performance degradation under ambient environmental temperature, pressure and humidity conditions encountered for installed location.
 - a. If product alone cannot comply with requirement, install product in a protective enclosure that is isolated and protected from conditions impacting performance. Enclosure shall be internally insulated, electrically heated, cooled and ventilated as required by product and application.
 - 2. Products shall be protected with enclosures satisfying the following minimum requirements unless more stringent requirements are indicated. Products not available with integral enclosures complying with requirements indicated shall be housed in protective secondary

enclosures. Installed location shall dictate the following NEMA 250 enclosure requirements:

- a. Outdoors, Protected: Type 4.
- b. Outdoors, Unprotected: Type 4.
- c. Indoors, Heated with Filtered Ventilation: Type 2.
- d. Indoors, Heated with Non-Filtered Ventilation: Type 2.
- e. Indoors, Heated and Air Conditioned: Type 2.
- f. Mechanical Equipment Rooms:
 - 1) Chiller and Boiler Rooms: Type 4.
 - 2) Air-Moving Equipment Rooms: Type 4.
- g. Localized Areas Exposed to Washdown: Type 4.
- h. Within Duct Systems and Air-Moving Equipment Not Exposed to Possible Condensation: Type 3.
- i. Within Duct Systems and Air-Moving Equipment Exposed to Possible Condensation: Type 4.

F. Environmental Conditions for Instruments and Actuators:

- 1. Instruments and actuators shall operate without performance degradation under the ambient environmental temperature, pressure, humidity, and vibration conditions specified and encountered for installed location.
 - a. If instruments and actuators alone cannot comply with requirement, install instruments and actuators in protective enclosures that are isolated and protected from conditions impacting performance. Enclosure shall be internally insulated, electrically heated and ventilated as required by instrument and application.
- 2. Instruments, actuators and accessories shall be protected with enclosures satisfying the following minimum requirements unless more stringent requirements are indicated. Instruments and actuators not available with integral enclosures complying with requirements indicated shall be housed in protective secondary enclosures. Installed location shall dictate the following NEMA 250 enclosure requirements:
 - a. Outdoors, Protected: Type 4.
 - b. Outdoors, Unprotected: Type 4.
 - c. Indoors, Heated with Filtered Ventilation: Type 2.
 - d. Indoors, Heated with Non-Filtered Ventilation: Type 2.
 - e. Indoors, Heated and Air Conditioned: Type 2.
 - f. Mechanical Equipment Rooms:
 - 1) Chiller and Boiler Rooms: Type 4.
 - 2) Air-Moving Equipment Rooms: Type 4.
 - g. Localized Areas Exposed to Washdown: Type 4.
 - h. Within Duct Systems and Air-Moving Equipment Not Exposed to Possible Condensation: Type 3.
 - i. Within Duct Systems and Air-Moving Equipment Exposed to Possible Condensation: Type 4.

G. Backup Power Source:

- 1. HVAC systems and equipment served by a backup power source shall have associated DDC system products that control such systems and equipment also served from a backup power source.

H. UPS:

1. DDC system products powered by UPS units shall include the following:
 - a. DDC controllers.
2. DDC system instruments and actuators powered by UPS units shall be defined in the documents.
- I. Continuity of Operation after Electric Power Interruption:
 1. Equipment and associated factory-installed controls, field-installed controls, electrical equipment, and power supply connected to building normal and backup power systems shall automatically return equipment and associated controls to operating state occurring immediately before loss of normal power, without need for manual intervention by operator when power is restored either through backup power source or through normal power if restored before backup power is brought online.

2.04 DDC SYSTEM OPERATOR INTERFACES

- A. Operator Means of System Access: Operator shall be able to access entire DDC system through any of multiple means, including, but not limited to, the following:
 1. Desktop and portable operator workstation with hardwired connection through LAN port.
 2. Portable operator terminal with hardwired connection through LAN port.
 3. Portable operator workstation with wireless connection through LAN router.
 4. Remote connection using outside of system personal computer or through Web access.
 5. Remote connection using portable operator workstation and internet connection.
 6. Mobile device.
- B. Access to system, regardless of operator means used, shall be transparent to operator.
- C. Desktop Workstations:
 1. Connect to DDC system Level one LAN through a communications port directly on LAN or through a communications port on a DDC controller.
 2. Able to communicate with any device located on any DDC system LAN.
 3. Able to communicate, with modems, remotely with any device connected to any DDC system LAN.
 4. Communication via a modem shall not interfere with LAN activity and LAN activity shall not prevent workstation from handling incoming calls.
- D. Critical Alarm Reporting:
 1. Operator-selected critical alarms shall be sent by DDC system to notify operator of critical alarms that require immediate attention.
 2. DDC system shall send alarm notification to multiple recipients that are assigned for each alarm.
 3. DDC system shall notify recipients by any or all means, including e-mail, text message, and prerecorded phone message to mobile and landline phone numbers.
- E. Simultaneous Operator Use: Capable of accommodating up to 10 simultaneous operators that are accessing DDC system through any one of operator interfaces indicated.

2.05 NETWORK COMMUNICATION PROTOCOL

- A. Network communication protocol(s) used throughout entire DDC system shall be open to public and available to other companies for use in making future modifications to DDC system.
- B. ASHRAE 135 Protocol:
 1. ASHRAE 135 communication protocol shall be sole and native protocol used throughout entire DDC system.

2. DDC system shall not require use of gateways except to integrate HVAC equipment and other building systems and equipment, not required to use ASHRAE 135 communication protocol.
3. If used, gateways shall connect to DDC system using ASHRAE 135 communication protocol and Project object properties and read/write services indicated by interoperability schedule.
4. Operator workstations, controllers and other network devices shall be tested and listed by BACnet Testing Laboratories.

2.06 ASHRAE 135 GATEWAYS

- A. Include BACnet communication ports, whenever available as an equipment OEM standard option, for integration via a single communication cable. BACnet-controlled plant equipment includes, but is not limited to, boilers, chillers, and variable-speed drives.
- B. Include gateways to connect BACnet to legacy systems, existing non-BACnet devices, and existing non-BACnet DDC-controlled equipment, only when specifically requested and approved by Owner.
- C. Include with each gateway an interoperability schedule showing each point or event on legacy side that BACnet "client" will read, and each parameter that BACnet network will write to. Describe this interoperability of BACnet services, or BIBBs, defined in ASHRAE 135, Annex K.
- D. Gateway Minimum Requirements:
 1. Read and view all readable object properties on non-BACnet network to BACnet network and vice versa where applicable.
 2. Write to all writeable object properties on non-BACnet network from BACnet network and vice versa where applicable.
 3. Include single-pass (only one protocol to BACnet without intermediary protocols) translation from non-BACnet protocol to BACnet and vice versa.
 4. Comply with requirements of Data Sharing Read Property, Data Sharing Write Property, Device Management Dynamic Device Binding-B, and Device Management Communication Control BIBBs according to ASHRAE 135.
 5. Hardware, software, software licenses, and configuration tools for operator-to-gateway communications.
 6. Backup programming and parameters on CD media and the ability to modify, download, backup, and restore gateway configuration.

2.07 DDC CONTROLLERS

- A. DDC system shall consist of a combination of network controllers, programmable application controllers and application-specific controllers to satisfy performance requirements indicated.
- B. DDC controllers shall perform monitoring, control, energy optimization and other requirements indicated.
- C. DDC controllers shall use a multitasking, multiuser, real-time digital control microprocessor with a distributed network database and intelligence.
- D. Each DDC controller shall be capable of full and complete operation as a completely independent unit and as a part of a DDC system wide distributed network.
- E. Environment Requirements:
 1. Controller hardware shall be suitable for the anticipated ambient conditions.
 2. Controllers located in conditioned space shall be rated for operation at 32 to 120 deg F.
 3. Controllers located outdoors shall be rated for operation at 40 to 150 deg F.
- F. Power and Noise Immunity:

1. Controller shall operate at 90 to 110 percent of nominal voltage rating and shall perform an orderly shutdown below 80 percent of nominal voltage.
 2. Operation shall be protected against electrical noise of 5 to 120 Hz and from keyed radios with up to 5 W of power located within 36 inches of enclosure.
- G. DDC Controller Spare Processing Capacity:
1. Include spare processing memory for each controller. RAM, PROM, or EEPROM will implement requirements indicated with the following spare memory:
 - a. Network Controllers: 50 percent.
 - b. Programmable Application Controllers: Not less than 60 percent.
 - c. Application-Specific Controllers: Not less than 70 percent.
 2. Memory shall support DDC controller's operating system and database and shall include the following:
 - a. Monitoring and control.
 - b. Energy management, operation and optimization applications.
 - c. Alarm management.
 - d. Historical trend data of all connected I/O points.
 - e. Maintenance applications.
 - f. Operator interfaces.
 - g. Monitoring of manual overrides.
- H. Maintenance and Support: Include the following features to facilitate maintenance and support:
1. Mount microprocessor components on circuit cards for ease of removal and replacement.
 2. Means to quickly and easily disconnect controller from network.
 3. Means to quickly and easily access connect to field test equipment.
 4. Visual indication that controller electric power is on, of communication fault or trouble, and that controller is receiving and sending signals to network.
- I. Input and Output Point Interface:
1. Hardwired input and output points shall connect to network, programmable application and application-specific controllers.
 2. Input and output points shall be protected so shorting of point to itself, to another point, or to ground will not damage controller.
 3. Input and output points shall be protected from voltage up to 24 V of any duration so that contact will not damage controller.
 4. AIs:
 - a. AIs shall include monitoring of low-voltage (zero- to 10-V dc), current (4 to 20 mA) and resistance signals from thermistor and RTD sensors.
 - b. AIs shall be compatible with, and field configurable to, sensor and transmitters installed.
 - c. Controller AIs shall perform analog-to-digital (A-to-D) conversion with a minimum resolution of 12 bits or better to comply with accuracy requirements indicated.
 - d. Signal conditioning including transient rejection shall be provided for each AI.
 - e. Capable of being individually calibrated for zero and span.
 - f. Incorporate common-mode noise rejection of at least 50 dB from zero to 100 Hz for differential inputs, and normal-mode noise rejection of at least 20 dB at 60 Hz from a source impedance of 10000 ohms.
 5. AOs:

- a. Controller AOs shall perform analog-to-digital (A-to-D) conversion with a minimum resolution of 12 bits or better to comply with accuracy requirements indicated.
 - b. Output signals shall have a range of 4 to 20 mA dc or zero- to 10-V dc as required to include proper control of output device.
 - c. Capable of being individually calibrated for zero and span.
 - d. AOs shall not exhibit a drift of greater than 0.4 percent of range per year.
6. BIs:
- a. Controller BIs shall accept contact closures and shall ignore transients of less than 5-ms duration.
 - b. Isolation and protection against an applied steady-state voltage of up to 180-V ac peak.
 - c. BIs shall include a wetting current of at least 12 mA to be compatible with commonly available control devices and shall be protected against effects of contact bounce and noise.
 - d. BIs shall sense "dry contact" closure without external power (other than that provided by the controller) being applied.
 - e. Pulse accumulation input points shall comply with all requirements of BIs and accept up to 10 pulses per second for pulse accumulation. Buffer shall be provided to totalize pulses. Pulse accumulator shall accept rates of at least 20 pulses per second. The totalized value shall be reset to zero on operator's command.
7. BOs:
- a. Controller BOs shall include relay contact closures or triac outputs for momentary and maintained operation of output devices.
 - 1) Relay contact closures shall have a minimum duration of 0.1 second. Relays shall include at least 180 V of isolation. Electromagnetic interference suppression shall be provided on all output lines to limit transients to non-damaging levels. Minimum contact rating shall be 1 A at 24-V ac.
 - 2) Triac outputs shall include at least 180 V of isolation. Minimum contact rating shall be 1 A at 24-V ac.
 - b. BOs shall include for two-state operation or a pulsed low-voltage signal for pulse-width modulation control.
 - c. BOs shall be selectable for either normally open or normally closed operation.
 - d. Include tristate outputs (two coordinated BOs) for control of three-point floating-type electronic actuators without feedback.
 - e. Limit use of three-point floating devices to VAV terminal unit control applications, and other applications indicated on Drawings, Control algorithms shall operate actuator to one end of its stroke once every 24 hours for verification of operator tracking.

2.08 NETWORK CONTROLLERS

A. General Network Controller Requirements:

- 1. Include adequate number of controllers to achieve performance indicated.
- 2. System shall consist of one or more independent, standalone, microprocessor-based network controllers to manage global strategies indicated.
- 3. Controller shall have enough memory to support its operating system, database, and programming requirements.
- 4. Data shall be shared between networked controllers and other network devices.

5. Operating system of controller shall manage input and output communication signals to allow distributed controllers to share real and virtual object information and allow for central monitoring and alarms.
 6. Controllers that perform scheduling shall have a real-time clock.
 7. Controller shall continually check status of its processor and memory circuits. If an abnormal operation is detected, controller shall assume a predetermined failure mode and generate an alarm notification.
 8. Controllers shall be fully programmable.
- B. Communication:
1. Network controllers shall communicate with other devices on DDC system network.
 2. Network controller also shall perform routing if connected to a network of programmable application and application-specific controllers.
- C. Operator Interface:
1. Controller shall be equipped with a service communications port for connection to a portable operator's workstation.
 2. Local Keypad and Display:
 - a. Equip controller with local keypad and digital display for interrogating and editing data.
 - b. Use of keypad and display shall require security password.
- D. Serviceability:
1. Controller shall be equipped with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
 2. Wiring and cable connections shall be made to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
 3. Controller shall maintain BIOS and programming information in event of a power loss for at least 72 hours.

2.09 PROGRAMMABLE APPLICATION CONTROLLERS

- A. General Programmable Application Controller Requirements:
1. Include adequate number of controllers to achieve performance indicated.
 2. Controller shall have enough memory to support its operating system, database, and programming requirements.
 3. Data shall be shared between networked controllers and other network devices.
 4. Operating system of controller shall manage input and output communication signals to allow distributed controllers to share real and virtual object information and allow for central monitoring and alarms.
 5. Controllers that perform scheduling shall have a real-time clock.
 6. Controller shall continually check status of its processor and memory circuits. If an abnormal operation is detected, controller shall assume a predetermined failure mode and generate an alarm notification.
 7. Controllers shall be fully programmable.
- B. Communication:
1. Programmable application controllers shall communicate with other devices on network.
- C. Operator Interface:
1. Controller shall be equipped with a service communications port for connection to a portable operator's workstation.
 2. Local Keypad and Display:

- a. Equip controller with local keypad and digital display for interrogating and editing data.
- b. Use of keypad and display shall require security password.
- D. Serviceability:
 - 1. Controller shall be equipped with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
 - 2. Wiring and cable connections shall be made to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
 - 3. Controller shall maintain BIOS and programming information in event of a power loss for at least 72 hours.

2.10 APPLICATION-SPECIFIC CONTROLLERS

- A. Description: Microprocessor-based controllers, which through hardware or firmware design are dedicated to control a specific piece of equipment. Controllers are not fully user-programmable but are configurable and customizable for operation of equipment they are designed to control.
 - 1. Capable of standalone operation and shall continue to include control functions without being connected to network.
 - 2. Data shall be shared between networked controllers and other network devices.
- B. Communication: Application-specific controllers shall communicate with other application-specific controller and devices on network, and to programmable application and network controllers.
- C. Operator Interface: Controller shall be equipped with a service communications port for connection to a portable operator's workstation. Connection shall extend to port on space temperature sensor that is connected to controller.
- D. Serviceability:
 - 1. Controller shall be equipped with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
 - 2. Wiring and cable connections shall be made to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
 - 3. Controller shall use nonvolatile memory and maintain all BIOS and programming information in event of power loss.

2.11 ENCLOSURES

- A. General Enclosure Requirements:
 - 1. House each controller and associated control accessories in a enclosure. Enclosure shall serve as central tie-in point for control devices such as switches, transmitters, transducers, power supplies and transformers.
 - 2. Do not house more than one controller in a single enclosure.
 - 3. Include enclosure door with key locking mechanism. Key locks alike for all enclosures and include one pair of keys per enclosure.
 - 4. Equip doors of enclosures housing controllers and components with analog or digital displays with windows to allow visual observation of displays without opening enclosure door.
 - 5. Individual wall-mounted single-door enclosures shall not exceed 36 inches wide and 48 inches high.
 - 6. Individual wall-mounted double-door enclosures shall not exceed 60 inches wide and 36 inches high.
 - 7. Include wall-mounted enclosures with brackets suitable for mounting enclosures to wall or freestanding support stand as indicated.

8. Supply each enclosure with a complete set of as-built schematics, tubing, and wiring diagrams and product literature located in a pocket on inside of door.
- B. Internal Arrangement:
1. Internal layout of enclosure shall group and protect pneumatic, electric, and electronic components associated with a controller, but not an integral part of controller.
 2. Arrange layout to group similar products together.
 3. Include a barrier between line-voltage and low-voltage electrical and electronic products.
 4. Factory or shop install products, tubing, cabling and wiring complying with requirements and standards indicated.
 5. Terminate field cable and wire using heavy-duty terminal blocks.
 6. Include spare terminals, equal to not less than 25 percent of used terminals.
 7. Include spade lugs for stranded cable and wire.
 8. Install a maximum of two wires on each side of a terminal.
 9. Include enclosure field power supply with a toggle-type switch located at entrance inside enclosure to disconnect power.
 10. Include enclosure with a line-voltage nominal 20-A GFCI duplex receptacle for service and testing tools. Wire receptacle on hot side of enclosure disconnect switch and include with a 5-A circuit breaker.
 11. Mount products within enclosure on removable internal panel(s).
 12. Include products mounted in enclosures with engraved, laminated phenolic nameplates (black letters on a white background). The nameplates shall have at least 1/4-inch-high lettering.
 13. Route tubing cable and wire located inside enclosure within a raceway with a continuous removable cover.
 14. Label each end of cable, wire and tubing in enclosure following an approved identification system that extends from field I/O connection and all intermediate connections throughout length to controller connection.
 15. Size enclosure internal panel to include at least 25 percent spare area on face of panel.
- C. Environmental Requirements:
1. Evaluate temperature and humidity requirements of each product to be installed within each enclosure.
 2. Calculate enclosure internal operating temperature considering heat dissipation of all products installed within enclosure and ambient effects (solar, conduction and wind) on enclosure.
 3. Where required by application, include temperature-controlled electrical heat to maintain inside of enclosure above minimum operating temperature of product with most stringent requirement.
 4. Where required by application, include temperature-controlled ventilation fans with filtered louver(s) to maintain inside of enclosure below maximum operating temperature of product with most stringent requirement.
- D. Wall-Mounted, NEMA 250, Type 1:
1. Enclosure shall be NRTL listed according to UL 50 or UL 50E.
 2. Construct enclosure of steel.
 3. Finish enclosure inside and out with polyester powder coating that is electrostatically applied and then baked to bond to substrate.
 - a. Exterior color shall be NSF/ANSI 61 gray or manufacturer's standard.

- b. Interior color shall be NSF/ANSI 61 gray or manufacturer's standard.
- 4. Hinged door full size of front face of enclosure and supported using:
 - a. Enclosures sizes less than 36 in. tall: Multiple butt hinges.
 - b. Enclosures sizes 36 in. tall and larger: Continuous piano hinges.
- 5. Removable internal panel with a white polyester powder coating that is electrostatically applied and then baked to bond to substrate.
- 6. Internal panel mounting hardware, grounding hardware and sealing washers.
- 7. Grounding stud on enclosure body.
- 8. Thermoplastic pocket on inside of door for record Drawings and Product Data.
- E. Wall Mounted NEMA 250, Types 4 and 12:
 - 1. Enclosure shall be NRTL listed according to UL 508A.
 - 2. Seam and joints are continuously welded and ground smooth.
 - 3. Where recessed enclosures are indicated, include enclosures with face flange for flush mounting.
 - 4. Externally formed body flange around perimeter of enclosure face for continuous perimeter seamless gasket door seal.
 - 5. Single-door enclosure sizes up to 60 inches tall by 36 inches wide.
 - 6. Double-door enclosure sizes up to 36 inches tall by 60 inches wide.
 - 7. Construct enclosure of steel.
 - 8. Finish enclosure with polyester powder coating that is electrostatically applied and then baked to bond to substrate.
 - a. Exterior color shall be NSF/ANSI 61 gray or manufacturer's standard.
 - b. Interior color shall be NSF/ANSI 61 gray or manufacturer's standard.
 - 9. Corner-formed door, full size of enclosure face, supported using multiple concealed hinges with easily removable hinge pins.
 - a. Sizes through 24 Inches Tall: Two hinges.
 - b. Sizes between 24 Inches through 48 Inches Tall: Three hinges.
 - c. Sizes Larger 48 Inches Tall: Four hinges.
 - 10. Double-door enclosures with overlapping door design to include unobstructed full-width access.
 - a. Single-door enclosures 48 inches and taller, and all double-door enclosures, with three-point (top, middle and bottom) latch system.
 - 11. Removable internal panel with a white polyester powder coating that is electrostatically applied and then baked to bond to substrate.
 - 12. Internal panel mounting studs with hardware, grounding hardware, and sealing washers.
 - 13. Grounding stud on enclosure body.
 - 14. Thermoplastic pocket on inside of door for record Drawings and Product Data.

2.12 RELAYS

- A. General-Purpose Relays:
 - 1. Relays shall be heavy duty and rated for at least 10 A at 250-V ac and 60 Hz.
 - 2. Relays shall be either double pole double throw (DPDT) or three-pole double throw, depending on the control application.
 - 3. Use a plug-in-style relay with an eight-pin octal plug for DPDT relays and an 11-pin octal plug for three-pole double-throw relays.

4. Construct the contacts of either silver cadmium oxide or gold.
 5. Enclose the relay in a clear transparent polycarbonate dust-tight cover.
 6. Relays shall have LED indication and a manual reset and push-to-test button.
 7. Equip relays with coil transient suppression to limit transients to non-damaging levels.
 8. Plug each relay into an industry-standard, 35-mm DIN rail socket. Plug all relays located in control panels into sockets that are mounted on a DIN rail.
 9. Relay socket shall have screw terminals. Mold into the socket the coincident screw terminal numbers and associated octal pin numbers.
- B. Multifunction Time-Delay Relays:
1. Relays shall be continuous duty and rated for at least 10 A at 240-V ac and 60 Hz.
 2. Relays shall be DPDT relay with up to eight programmable functions to provide on/off delay, interval and recycle timing functions.
 3. Use a plug-in-style relay with either an 8- or 11-pin octal plug.
 4. Construct the contacts of either silver cadmium oxide or gold.
 5. Enclose the relay in a dust-tight cover.
 6. Include knob and dial scale for setting delay time.
 7. Equip relays with coil transient suppression to limit transients to non-damaging levels.
 8. Plug each relay into an industry-standard, 35-mm DIN rail socket. Plug all relays located in control panels into sockets that are mounted on a DIN rail.
 9. Relay socket shall have screw terminals. Mold into the socket the coincident screw terminal numbers and associated octal pin numbers.
- C. Latching Relays:
1. Relays shall be continuous duty and rated for at least 10 A at 250-V ac and 60 Hz.
 2. Relays shall be either DPDT or three-pole double throw, depending on the control application.
 3. Use a plug-in-style relay with a multibladed plug.
 4. Construct the contacts of either silver cadmium oxide or gold.
 5. Enclose the relay in a clear transparent polycarbonate dust-tight cover.
 6. Equip relays with coil transient suppression to limit transients to non-damaging levels.
 7. Plug each relay into an industry-standard, 35-mm DIN rail socket. Plug all relays located in control panels into sockets that are mounted on a DIN rail.
 8. Relay socket shall have screw terminals. Mold into the socket the coincident screw terminal numbers and associated octal pin numbers.
- D. Current Sensing Relay:
1. Monitors ac current.
 2. Independent adjustable controls for pickup and dropout current.
 3. Energized when supply voltage is present and current is above pickup setting.
 4. De-energizes when monitored current is below dropout current.
 5. Dropout current is adjustable from 50 to 95 percent of pickup current.
 6. Include a current transformer, if required for application.
 7. House current sensing relay and current transformer in its own enclosure. Use NEMA 250, Type 12 enclosure for indoors and NEMA 250, Type 4 for outdoors.
- E. Combination On-Off Status Sensor and On-Off Relay:
1. Description:

- a. On-off control and status indication in a single device.
 - b. LED status indication of activated relay and current trigger.
 - c. Closed-Open-Auto override switch located on the load side of the relay.
2. Performance:
 - a. Ambient Temperature: Minus 30 to 140 deg F.
 - b. Voltage Rating: Single-phase loads rated for 300-V ac. Three-phase loads rated for 600-V ac.
3. Status Indication:
 - a. Current Sensor: Integral sensing for single-phase loads up to 20 A and external solid or split sensing ring for three-phase loads up to 150 A.
 - b. Current Sensor Range: As required by application.
 - c. Current Set Point: Fixed or adjustable as required by application.
 - d. Current Sensor Output:
 - 1) Solid-state, single-pole double-throw contact rated for 30-V ac and dc and for 0.4 A.
 - 2) Solid-state, single-pole double-throw contact rated for 120-V ac and 1.0 A.
 - 3) Analog, zero- to 5- or 10-V dc.
 - 4) Analog, 4 to 20 mA, loop powered.
4. Relay: Single-pole double-throw, continuous-duty coil; rated for 10-million mechanical cycles.
5. Enclosure: NEMA 250, Type 1 enclosure.

2.13 ELECTRICAL POWER DEVICES

- A. Transformers:
 1. Transformer shall be sized for the total connected load, plus an additional 25 percent of connected load.
 2. Transformer shall be at least 100 VA.
 3. Transformer shall have both primary and secondary fuses.
- B. DC Power Supply:
 1. Plug-in style suitable for mating with a standard eight-pin octal socket. Include the power supply with a mating mounting socket.
 2. Enclose circuitry in a housing.
 3. Include both line and load regulation to ensure a stable output. To protect both the power supply and the load, power supply shall have an automatic current limiting circuit.
 4. Performance:
 - a. Output voltage nominally 25-V dc within 5 percent.
 - b. Output current up to 100 mA.
 - c. Input voltage nominally 120-V ac, 60 Hz.
 - d. Load regulation within 0.5 percent from zero- to 100-mA load.
 - e. Line regulation within 0.5 percent at a 100-mA load for a 10 percent line change.
 - f. Stability within 0.1 percent of rated volts for 24 hours after a 20-minute warmup.

2.14 UNINTERRUPTABLE POWER SUPPLY (UPS) UNITS

- A. 250 through 1000 VA:
 1. UPS units shall provide continuous, regulated output power without using their batteries during brown-out, surge, and spike conditions.

2. Load served shall not exceed 75 percent of UPS rated capacity, including power factor of connected loads.
 - a. Larger-capacity units shall be provided for systems with larger connected loads.
 - b. UPS shall provide 5 minutes of battery power.
 3. Performance:
 - a. Input Voltage: Single phase, 120- or 230-V ac, compatible with field power source.
 - b. Load Power Factor Range (Crest Factor): 0.65 to 1.0.
 - c. Output Voltage: 101- to 132-V ac, while input voltage varies between 89 and 152-V ac.
 - d. On Battery Output Voltage: Sine wave.
 - e. Inverter overload capacity shall be minimum 150 percent for 30 seconds.
 - f. Recharge time shall be a maximum of six hours to 90 percent capacity after full discharge to cutoff.
 - g. Transfer Time: 6 ms.
 - h. Surge Voltage Withstand Capacity: IEEE C62.41, Categories A and B; 6 kV/200 and 500 A; 100-kHz ringwave.
 4. UPS shall be automatic during fault or overload conditions.
 5. Unit with integral line-interactive, power condition topology to eliminate all power contaminants.
 6. Include front panel with power switch and visual indication of power, battery, fault and temperature.
 7. Unit shall include an audible alarm of faults and front panel silence feature.
 8. Unit with four NEMA WD 1, NEMA WD 6 Configuration 5-15R receptacles.
 9. UPS shall include dry contacts (digital output points) for low battery condition and battery-on (primary utility power failure) and connect the points to the DDC system.
 10. Batteries shall be sealed lead-acid type and be maintenance free. Battery replacement shall be front accessible by user without dropping load.
 11. Include tower models installed in ventilated cabinets to the particular installation location.
- B. 1000 through 3000 VA:
1. UPS units shall provide continuous, regulated output power without using their batteries during brown-out, surge, and spike conditions.
 2. Load served shall not exceed 75 percent of UPS rated capacity, including power factor of connected loads.
 - a. Larger-capacity units, or multiple units, shall be provided for systems with larger connected loads.
 - b. UPS shall provide 5 minutes of battery power.
 3. Performance:
 - a. Input Voltage: Single phase, 120-V ac, plus 20 to minus 30 percent.
 - b. Power Factor: Minimum 0.97 at full load.
 - c. Output Voltage: Single phase, 120-V ac, within 3 percent, steady state with rated output current of 10.0 A, 30.0-A peak.
 - d. Inverter overload capacity shall be minimum 150 percent for 30 seconds.
 - e. Recharge time shall be a maximum of eight hours to 90 percent capacity.
 4. UPS bypass shall be automatic during fault or overload conditions.

5. UPS shall include dry contacts (digital output points) for low battery condition and battery-on (primary utility power failure) and connect the points to the DDC system.
6. Batteries shall be sealed lead-acid type and be maintenance free.
7. Include tower models installed in ventilated cabinets or rack models installed on matching racks, as applicable to the particular installation location and space availability/configuration.

2.15 CONTROL WIRE AND CABLE

- A. Wire: Single conductor control wiring above 24 V.
 1. Wire size shall be at least No. 14 AWG or sized per length of run.
 2. Conductor shall be 7/24 soft annealed copper strand with 2- to 2.5-inch lay.
 3. Conductor insulation shall be 600 V, Type THWN or Type THHN, and 90 deg C according to UL 83.
 4. Conductor colors shall be black (hot), white (neutral), and green (ground).
 5. Furnish wire on spools.
- B. Single Twisted Shielded Instrumentation Cable above 24 V:
 1. Wire size shall be a minimum No. 18 AWG or sized per length of run.
 2. Conductors shall be a twisted, 7/24 soft annealed copper strand with a 2- to 2.5-inch lay.
 3. Conductor insulation shall have a Type THHN/THWN or Type TFN rating.
 4. Shielding shall be 100 percent type, 0.35/0.5-mil aluminum/Mylar tape, helically applied with 25 percent overlap, and aluminum side in with tinned copper drain wire.
 5. Outer jacket insulation shall have a 600-V, 90-deg C rating and shall be Type TC cable.
 6. For twisted pair, conductor colors shall be black and white. For twisted triad, conductor colors shall be black, red and white.
 7. Furnish wire on spools.
- C. Single Twisted Shielded Instrumentation Cable 24 V and Less:
 1. Wire size shall be a minimum No. 18 AWG or sized per length of run.
 2. Conductors shall be a twisted, 7/24 soft annealed copper stranding with a 2- to 2.5-inch lay.
 3. Conductor insulation shall have a nominal 15-mil thickness, constructed from flame-retardant PVC.
 4. Shielding shall be 100 percent type, 1.35-mil aluminum/polymer tape, helically applied with 25 percent overlap, and aluminum side in with tinned copper drain wire.
 5. Outer jacket insulation shall have a 300-V, 105-deg C rating and shall be Type PLTC cable.
 6. For twisted pair, conductor colors shall be black and white. For twisted triad, conductor colors shall be black, red and white.
 7. Furnish wire on spools.
- D. LAN and Communication Cable: Comply with DDC system manufacturer requirements for network being installed.
 1. Cable shall be plenum rated.
 2. Cable shall comply with NFPA 70.
 3. Cable shall have a unique color that is different from other cables used on Project.
 4. Copper Cable for Ethernet Network:
 - a. 100BASE-TX, 1000BASE-T, or 1000BASE-TX.
 - b. TIA/EIA 586, Category 6.

- c. Minimum No. 22 AWG solid or sized per length of run.
- d. Shielded Twisted Pair (STP).
- e. Thermoplastic insulated conductors, enclosed in a thermoplastic outer jacket, Class CMP as plenum rated.

2.16 RACEWAYS FOR CONTROL WIRING, CABLING, AND TUBING

A. Metal Conduits, Tubing, and Fittings:

- 1. Listing and Labeling: Metal conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- 2. EMT: Comply with NEMA ANSI C80.3 and UL 797.
- 3. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

2.17 CONTROL POWER WIRING AND RACEWAYS

A. Installation minimum requirements:

- 1. Mechanical spaces, services spaces, and areas without ceiling: All wiring including cables in EMT.
- 2. Space sensors and alarms: All wiring cables in EMT within wall construction.
- 3. Ducted ceiling return: Approved non-plenum cable.
- 4. Non-ducted return ceiling plenum: Approved plenum rated cable.
- 5. Non-accessible ceilings: EMT or code compliant equal solid conduit.
- 6. Inside air handling units: All wiring including cables in EMT or code compliant solid conduit.
- 7. Note the use of cable is limited to low voltage service with less than 24 volt only.
- 8. Do not lay cables on ceiling grids.
- 9. Conduit junctions and terminations shall utilize compression fittings.

B. All control wiring that is stated to be routed in EMT shall be separate from any power wiring.

2.18 FIELD EQUIPMENT

A. Space Sensors:

- 1. All space sensors to have digital display of setpoint and actual space temperature.
- 2. Set-point adjustment to be a maximum plus and minus 5 degrees from the null setpoint programmed through the DDC system.
- 3. Space sensors may be (RTD) 1,000 Ohm platinum with an accuracy of ± 0.5 deg F or 10,000 OHM thermistor with accuracy of ± 0.5 deg. F for all spaces.
- 4. Space sensor shall be manufacture's standard color.
- 5. Provide insulating bases for all sensors located on exterior walls and on exterior column wraps. Foam seal cavity and junction box prior to installing insulating base.
- 6. Space sensors with occupant set-point adjustment shall be adjustable from the operator's workstation as to the deadband of adjustability allowed to the occupants.

B. Temperature Sensors:

- 1. Duct sensors for critical spaces shall utilize averaging elements, 1000 OHM platinum Resistance Temperature Detectors (RTD) having an accuracy of ± 0.5 deg F.
- 2. Duct sensors for non-critical spaces may utilize 10,000 OHM or 20,000 OHM thermistor having an accuracy of ± 1.0 deg F. 1000 OHM RTDs are also acceptable for non-critical applications.

3. Immersion sensors to be furnished with companion wells separable stainless steel. Well pressure rating shall be consistent with and extend the system pressure it will be immersed in. Wells shall withstand pipe design flow velocities.
- C. Low limit thermostats:
1. Low limit safety thermostats shall be manually reset, line voltage with maximum 23'-0" flexible sensing elements responsible to lowest temperature along entire length. Furnish minimum two (2) wired in series on the discharge side of the first hydronic coils (i.e., a 4-section coil requires eight low limit thermostats wired in series). Contractor to note that the operating head of such instruments shall be shielded from conditions whereby it could be activated by low temperature.
 2. All flexible averaging sensors shall be attached by wire ties to a suspended wire or insulated cable to prevent sensor contact with metal or other unit components.
 3. Install flexible sensors across all coils at a maximum of 6" from the bottom of the bottom coil and a minimum of 7" diameter to turn the sensor. Install the detector with a maximum free distance of 12" between each pass.
 4. Staggered coils (if applicable) shall utilize multiple sensors. Each sensor shall cover one section of the staggered coil. Sensing elements shall be a minimum of 17' long.
 5. All flexible sensors shall be protected at point of penetration of unit via a section of poly tubing to prevent contact of the sensor and the unit.
 6. Mount detector within 6" of the face of the coil unless noted otherwise. For staggered coil banks, this requirement applies for each half of the bank
 7. TCC to note that when any low limit controls are above an elevation 7'-0" above floor level or otherwise inaccessible, they shall employ automatic reset and shall be wired to an auxiliary control panel of a 5'-0" elevation. The control panel with piano hinged door shall utilize a latching reset relay for each individual low limit control which ensures that the fan is de-energized even as the low limit resets automatically. The panel face shall utilize a red alarm pilot light that remains lit until the 10 second time delay reset relay momentary contact switch is activated. An LED inside the panel shall indicate which of low limits has signaled the alarm.
- D. Electronic Actuators:
1. Manufactured, brand labeled or distributed by Belimo or Johnson Controls, Inc. or Siemens.
 2. Size for torque required for damper seal at load conditions.
 3. Coupling: V-bolt dual nut clamp with a V-shaped, toothed cradle.
 4. Mounting: Actuators shall be direct shaft mount type. Actuators shall be capable of being mechanically and electrically paralleled to increase torque if required.
 5. Overload protected electronically throughout rotation.
 6. Fail safe operation: Mechanical, spring return mechanism.
 7. Power requirements (spring return): 24 VAC.
 8. Proportional actuators shall be fully programmable through an EEPROM without the use of actuator mounted switches.
 9. Temperature rating: -22 deg. F to +122 deg. F.
 10. Housing: Minimum requirement NEMA Type 2/IP54 mounted in any orientation. NEMA 4/4X (IP67) required for outdoor applications.
 11. Agency listings: ISO 9001 or UL.
 12. The manufacturer shall warrant all components for a period of 5 years from the date of production with the first two years unconditional.

13. All damper actuators used on equipment introducing outdoor air shall be furnished with mechanical spring return mechanism as indicated in "fail safe operation" above.
14. All actuators shall have external adjustable stops to limit the travel in either direction and a gear release to allow manual positioning.
15. Actuators shall be provided with position feedback signal (2-10 VDC or 4-20 mA) where indicated on control drawings. Feedback signal shall be independent of the input signal and shall provide true position indication.

E. Dampers:

1. All automatic dampers furnished by this Contractor for modulating control shall be of the proportioning type with opposed or parallel blades depending on the application or as shown on the drawings. Dampers for two position action shall be of the opposed blade type for all applications except those located immediately at the inlet of fans and as noted otherwise on the drawings. Dampers for generator radiator fan exhaust shall be opposed blade type.
2. All dampers for outdoor air service and exhaust air service to be equivalent to TAMCO Series 9000 aluminum and have the following features:
 - a. Frames shall be 4" deep X 1" and no less than .080" in thickness, mill finish extruded aluminum 6063-T5 with mounting flanges on both sides of the frame. Frame to be assembled using plated steel mounting fasteners.
 - b. Entire frame shall be thermally broken by means of two polyurethane resin pockets complete with thermal cuts.
 - c. Blades shall be extruded aluminum 6063-T5, mill finish air foil profiles, internally insulated with expanded polyurethane foam and shall be thermally broken.
 - d. Blade and frame seals shall be of extruded silicone and shall be secured in an integral slot within the aluminum extrusions. Blade and frame seals are to be mechanically fastened to eliminate shrinkage and movement over the life of the damper. Adhesive or clip on type blade seals shall not be approved. Jamb seals shall be silicone.
 - e. Maintenance free bearings are to be composed of an inner bearing fixed to a 7/16" aluminum hexagon blade pivot pin, rotating within a polycarbonate outer bearing inserted into the frame. There shall be no metal-to-metal or metal-to-plastic contact.
 - f. Adjustable 7/16" hexagonal drive rod, U-bolt fastener and hexagonal retaining nuts shall be corrosion resistant, zinc plated steel to provide positive connection to blades and linkage.
 - g. Linkage hardware shall be installed in the frame side. All linkage crank arm and rod hardware parts shall be constructed of mill finished aluminum, complete with corrosion resistant, zinc plated trunnions and cup point trunnion screws for a slip-proof grip.
 - h. Dampers are to be designed for operation in temperatures ranging between -40 deg. F (-40 deg. C) and 212 deg. F (100 deg. C).
 - i. Dampers shall be rated Leakage Class 1A at 1 in. w.g. (0.25 kPa) static pressure differential. Standard air leakage data shall be certified under the AMCA Certified Ratings Program.
 - j. Dampers shall be made to size required without blanking off free area.
 - k. Dampers shall be available as "flanged to duct" mounting type.
 - l. Installation of dampers must be in accordance with manufacturer's installation guidelines provided with each damper shipment.
 - m. Intermediate or tubular steel structural support is required to resist applied pressure loads for dampers that consist of two or more sections in both height and width. (See manufacturer's installation guidelines).

3. Dampers for all other applications to be equal to TAMCO Series 1500 Ultra Low Leakage Air Foil Aluminum and have the following features:
 - a. Frames shall be 4" deep X 1" and no less than .080" in thickness, mill finish extruded aluminum 6063-T5 with mounting flanges on both sides of the frame. Frame to be assembled using plated steel mounting fasteners.
 - b. Entire frame shall be thermally broken by means of two polyurethane resin pockets complete with thermal cuts.
 - c. Blades shall be extruded aluminum 6063-T5, mill finish air foil profiles, internally insulated with expanded polyurethane foam and shall be thermally broken.
 - d. Blade and frame seals shall be of extruded silicone and shall be secured in an integral slot within the aluminum extrusions. Blade and frame seals are to be mechanically fastened to eliminate shrinkage and movement over the life of the damper. Adhesive or clip on type blade seals shall not be approved.
 - e. Maintenance free bearings are to be composed of an inner bearing fixed to a 7/16" aluminum hexagon blade pivot pin, rotating within a polycarbonate outer bearing inserted into the frame. There shall be no metal-to-metal or metal-to-plastic contact.
 - f. Adjustable 7/16" hexagonal drive rod, U-bolt fastener and hexagonal retaining nuts shall be corrosion resistant, zinc plated steel to provide positive connection to blades and linkage.
 - g. Linkage hardware shall be installed in the frame side. All linkage crank arm and rod hardware parts shall be constructed of mill finished aluminum, complete with corrosion resistant, zinc plated trunnions and cup point trunnion screws for a slip-proof grip.
 - h. Dampers are to be designed for operation in temperatures ranging between -40 deg. F (-40 deg. C) and 212 deg. F (100 deg. C).
 - i. Dampers shall be rated Leakage Class 1A at 1 in. w.g. (0.25 kPa) static pressure differential. Standard air leakage data shall be certified under the AMCA Certified Ratings Program.
 - j. Dampers shall be made to size required without blanking off free area.
 - k. Dampers shall be available with either opposed blade action or parallel blade action.
 - l. Dampers shall be available as "flanged to duct" mounting type.
 - m. Installation of dampers must be in accordance with manufacturer's installation guidelines provided with each damper shipment.
 - n. Intermediate or tubular steel structural support is required to resist applied pressure loads for dampers that consist of two or more sections in both height and width. (See manufacturer's installation guidelines).
4. Automatic dampers (modulating) shall be designed for face velocity that varies from 1,200 fpm to 2,000 fpm in most cases as approved by the design engineer. Dampers to be selected by the supplier with blade shaft lengths that prevent torsion that will create a leakage of more than 2 percent of the rated leakage capacity. Beyond that point, the dampers shall be broken into multiple sections. Field supplied mullions are required on large dampers exceeding 200 square feet.
5. Individual damper section actuators are preferred unless access to actuators is difficult and then jack shafting is acceptable. TCC to note that drive shafts between dampers of different air paths (i.e., outdoor air and return air or return air and exhaust air) is not acceptable. Jack shafting between sections is permitted when such shafting is designed to accommodate and eliminate the effects of torsion.
6. TCC to note that free access to all actuators is the responsibility of the TCC.
7. Each damper shall be equipped with an individual damper operator of the size and style required for the service intended.

8. Actuators to be designed for modulating control with spring return to the fail "safe" position. Actuators to be low voltage with 100% surplus torque (submittals to incorporate calculations to prove 100 percent closure under 4.0" wg status pressure differential for modulating service and 2.0" wg for two position application).
 9. Terminal box/AFCV damper actuators to be low voltage, non-spring return and incremental control with 200 percent torque. All control actuators to utilize auto zero program to insure total accuracy of damper actuator. The feature to be activated during periods of low or no occupancy.
- F. Differential Pressure Transmitter:
1. Liquid: Furnish field mounted differential pressure transmitters as indicated on plans for measuring differential pressure and transmitting an isolated 4 to 20 mA DC output linear differential pressure signal.
 - a. The unit shall be accurate to $\pm 0.20\%$ of calibrated span. It shall withstand static pressures of 1000 psig with negligible change in output. The flanges shall be made of stainless steel with stainless steel wetted sensing components, wetted parts all stainless steel and a silicone fill fluid. A brass or stainless 3 valve bypass manifold and bracket mounting kit shall be utilized for easier on-site equalization and calibration. Unit shall be protected against radio frequency interference and shall have a water-tight (NEMA Type 4) electrical enclosure with 1/2" NPT conduit connection. An LCD display is not required.
 - 1) The Type A transmitter shall be a standard process grade loop powered transmitter as manufactured by:
 - a) Rosemount Model 3051C.
 - b) Foxboro Model IDP10.
 - c) Yokogawa Model EJA110A.
 2. Air: Furnish field mounted differential pressure transmitters using a 4-20 mA (or 0-10 VDC) output linear with measured differential pressure. Accuracy shall be $\pm 0.8\%$ of calibrated span. Response time shall be 250 milliseconds. Transmitter shall be in a standard grade transmitter manufactured by Ashcroft or Setra.
- G. Airflow Measuring Stations:
1. All air flow measuring stations to be furnished under this contract as shown on control schematics and as scheduled.
 - a. Approved manufacturers are Tek-Air Systems, Air Monitor, Paragon, Ebtron, Farr, and Airflow Wing.
 2. Duct-mounted stations shall be installed by the Sheet Metal Contractor while fan inlet station installation responsibility shall be by this Contractor.
 3. Sizing and physical location of stations shall be the responsibility of this Contractor. TCC to ensure that sufficient distance is available both upstream and downstream such that turbulence is not a factor in the velocity pressure measurement. Sizing shall insure that the minimum velocity across the station affords accuracy of measurement and the design engineer shall be notified within 30 days of contract award if any modifications are required to the field ductwork.
 4. TCC to ensure that a proper access door upstream of the station is provided in the ductwork such that the inlet face of the unit may be cleaned as necessary.
 5. Duct-mounted air flow measuring stations:
 - a. Furnish and install air flow measuring stations constructed of 16 gage sheet metal casing and a copper velocity pressure traverse section.
 - b. The velocity pressure traverse section shall consist of air straightening tubes, total pressure sensors and static pressure sensors, all interconnected to form a traverse by copper manifolds which shall equalize and integrate each type sensor measurement

into one (1) total pressure and one (1) static pressure metering port. There shall be one static pressure sensor for each total pressure sensor.

- c. A minimum of one static and one total pressure sensor shall be used for every 16 square feet in cross section. For larger ducts, a minimum of one static and one total pressure sensor shall be used for every 36" of duct cross sectional area up to a maximum as recommended by ASHRAE guide for traverse measurement.
 - d. Identification: Each air flow measuring station shall have a nameplate with the following information:
 - 1) Unit size.
 - 2) Unit designation.
 - 3) Design air quantity.
 - 4) Direction of air flow.
 - 5) Design air velocity.
6. Fan inlet air flow sensing (non-intrusive piezometer type):
- a. Accuracy: Within 2% throughout the velocity range of 600 fpm and over, when installed in accordance with published recommendations
 - b. Temperature: 350 deg F continuous operation; 400 deg F intermittent operation
 - c. Humidity: 0-100% continuous operation
 - d. Corrosion resistance: Good salt air and mild acid resistance, excellent solvent and aromatic hydrocarbon resistance
 - e. Material: 6063-T5 anodized aluminum, galvanized mounting brackets
- H. Thermal Dispersion Air Flow Measurement:
1. Air volume measurement system to consist of multiple sensors designed to average velocity using thermal dispersion principles. System to be designed to be totally independent of temperature, density, and humidity. Tek-Air or Ebtron.
 2. The quantity of sensing tubes shall conform to manufacturer's requirements for spacing based on the specified accuracy and the actual inlet and outlet conditions.
 3. Unit to be accurate to 1.5% between 50 fpm and 6000 fpm. Output to be 4-20 mA.
- I. VAV Terminal Unit Control Components (DDC Control):
- | Component | Furnished By | Installed By | Wired By |
|-------------------|--------------|--------------|--------------|
| Disconnect Switch | Manufacturer | Manufacturer | Manufacturer |
| Transformer | TCC | Manufacturer | Manufacturer |
| Damper Actuator | TCC | Manufacturer | Manufacturer |
| Flow Controller | TCC | Manufacturer | Manufacturer |
| Flow Sensing | Manufacturer | Manufacturer | Manufacturer |
| Misc Accessories | TCC | TCC | TCC |
- J. Gas Instruments:
1. Carbon Monoxide (CO) Sensor and Controller.
 - a. Comply with UL 61010-1.
 - b. Wall mounted.
 - c. 24 VAC power.
 - d. BACnet IP protocol.
 - e. Programmable fan and alarm relays.

- f. Integrated display with LED indicators for status and adjustable parameters for warning and alarm setpoints.
 - g. Audible alarm.
 - h. 2 analog outputs.
 - i. Field replaceable sensing elements with a 7-year minimum life expectancy on each element.
 - j. Standard water/dust tight, corrosion resistant drip proof enclosure, NEMA 3R minimum rating enclosure.
 - k. Carbon Monoxide accuracy to be plus or minus 5% between 0-100 ppm and cover up to 7500 SF.
 - l. Include standard 7-year warranty on sensor electronics and 2-year warranty on replaceable elements.
 - m. Similar or equivalent to Senva TG Series or Brasch GSE.
 - n. Application
 - 1) Locate in any mechanical room with condensing boilers.
- K. Control Valves:
- 1. Source Limitations: Obtain valves from single manufacturer.
 - 2. Selection Criteria:
 - a. Control valves shall be suitable for operation at following conditions:
 - 1) Refer to specification section 232113 – Hydronic Piping for system pressures.
 - b. Fail positions unless otherwise indicated:
 - 1) Condenser Water: Open.
 - c. In water systems, select modulating control valves for a design Cv based on a pressure drop of:
 - 1) 1 psig for two-position unless otherwise indicated.
 - 2) 5 psig for two way modulating unless otherwise indicated.
 - 3) 5 psig for three way modulating unless otherwise indicated.
 - d. Actuators:
 - 1) Actuators for Steam Control Valves: Shutoff against 1.5 times design pressure.

2.19 BALL-STYLE CONTROL VALVES

- A. Ball Valves with Single Port and Characterized Disk:
- 1. Pressure Rating for NPS 1 and Smaller: Nominal 600 WOG.
 - 2. Pressure Rating for NPS 1-1/2 through NPS 2: Nominal 400 WOG.
 - 3. Close-off Pressure: 200 psig.
 - 4. Process Temperature Range: Zero to 212 deg F.
 - 5. Body and Tail Piece: Cast bronze ASTM B 61, ASTM B 62, ASTM B 584, or forged brass with nickel plating.
 - 6. End Connections: Threaded (NPT) ends.
 - 7. Ball: 300 series stainless steel.
 - 8. Stem and Stem Extension:
 - a. Material to match ball.
 - b. Blowout-proof design.
 - c. Sleeve or other approved means to allow valve to be opened and closed without damaging the insulation or the vapor barrier seal.

9. Ball Seats: Reinforced PTFE.
 10. Stem Seal: Reinforced PTFE packing ring with a threaded packing ring follower to retain the packing ring under design pressure with the linkage removed. Alternative means, such as EPDM O-rings, are acceptable if an equivalent cycle endurance can be demonstrated by testing.
 11. Flow Characteristic: Equal percentage.
- B. Ball Valves with Two Ports and Characterized Disk:
1. Pressure Rating for NPS 1 and Smaller: Nominal 600 WOG.
 2. Pressure Rating for NPS 1-1/2 through NPS 2: Nominal 400 WOG.
 3. Close-off Pressure: 200 psig.
 4. Process Temperature Range: Zero to 212 deg F.
 5. Body and Tail Piece: Cast bronze ASTM B 61, ASTM B 62, ASTM B 584, or forged brass with nickel plating.
 6. End Connections: Threaded (NPT) ends.
 7. Ball: 300 series stainless steel.
 8. Stem and Stem Extension:
 - a. Material to match ball.
 - b. Blowout-proof design.
 - c. Sleeve or other approved means to allow valve to be opened and closed without damaging the insulation or the vapor barrier seal.
 9. Ball Seats: Reinforced PTFE.
 10. Stem Seal: Reinforced PTFE packing ring with a threaded packing ring follower to retain the packing ring under design pressure with the linkage removed. Alternative means, such as EPDM O-rings, are acceptable if an equivalent cycle endurance can be demonstrated by testing.
 11. Flow Characteristics for A-Port: Equal percentage.
 12. Flow Characteristics for B-Port: Modified for constant common port flow.

2.20 ACCESSORIES

- A. Damper Blade Limit Switches:
1. Sense positive open and/or closed position of the damper blades.
 2. NEMA 250, Type 13, oil-tight construction.
 3. Arrange for the mounting application.
 4. Additional waterproof enclosure when required by its environment.
 5. Arrange to prevent "over-center" operation.

2.21 IDENTIFICATION

- A. Control Equipment, Instruments, and Control Devices:
1. Engraved tag bearing unique identification.
 - a. Include instruments with unique identification identified by equipment being controlled or monitored, followed by point identification.
 2. Letter size shall be as follows:
 - a. DDC Controllers: Minimum of 0.5 inch high.
 - b. Enclosures: Minimum of 0.5 inch high.
 - c. Electrical Power Devices: Minimum of 0.25 inch high.
 - d. UPS units: Minimum of 0.5 inch high.

- e. Instruments: Minimum of 0.25 inch high.
- f. Control Damper and Valve Actuators: Minimum of 0.25 inch high.
- 3. Tag shall consist of white lettering on black background.
- 4. Tag shall be engraved phenolic consisting of three layers of rigid laminate. Top and bottom layers are color-coded black with contrasting white center exposed by engraving through outer layer.
- 5. Tag shall be fastened with drive pins.
- 6. Instruments, control devices and actuators with Project-specific identification tags having unique identification numbers following requirements indicated and provided by original manufacturer do not require an additional tag.
- B. Valve Tags:
 - 1. Brass tags and brass chains attached to valve.
 - 2. Tags shall be at least 1.5 inches in diameter.
 - 3. Include tag with unique valve identification indicating control influence such as flow, level, pressure, or temperature; followed by location of valve, and followed by three-digit sequential number. For example: TV-1.001.
 - 4. Valves with Project-specific identification tags having unique identification numbers following requirements indicated and provided by original manufacturer do not require an additional tag.
- C. Raceway and Boxes:
 - 1. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
 - 2. Paint cover plates on junction boxes and conduit same color as the tape banding for conduits. After painting, label cover plate "HVAC Controls," using an engraved phenolic tag.
 - 3. For raceways housing pneumatic tubing, add a phenolic tag labeled "HVAC Instrument Air Tubing."
 - 4. For raceways housing air signal tubing, add a phenolic tag labeled "HVAC Air Signal Tubing."
- D. Equipment Warning Labels:
 - 1. Acrylic label with pressure-sensitive adhesive back and peel-off protective jacket.
 - 2. Lettering size shall be at least 14-point type with white lettering on red background.
 - 3. Warning label shall read "CAUTION-Equipment operated under remote automatic control and may start or stop at any time without warning. Switch electric power disconnecting means to OFF position before servicing."
 - 4. Lettering shall be enclosed in a white line border. Edge of label shall extend at least 0.25 inch beyond white border.

2.22 SOURCE QUALITY CONTROL

- A. Product(s) will be considered defective if it does not pass tests and inspections.
- B. Prepare test and inspection reports.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
 - 1. Verify compatibility with and suitability of substrates.
- B. Examine roughing-in for products to verify actual locations of connections before installation.

1. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.
2. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.
- C. Examine walls, floors, roofs, and ceilings for suitable conditions where product will be installed.
- D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 DDC SYSTEM INTERFACE WITH OTHER SYSTEMS AND EQUIPMENT

- A. Communication Interface to Equipment with Integral Controls:
 1. DDC system shall have communication interface with equipment having integral controls and having a communication interface for remote monitoring or control.
 2. Equipment to Be Connected:
 - a. Air-terminal units specified in Section 233600 "Air Terminal Units."
 - b. Boilers specified in Section 235216 "Condensing Boilers."
 - c. Air-handling units specified in Section 237313 "Modular Indoor Central-Station Air-Handling Units."
 - d. Variable-frequency controllers specified in Section 262923 "Variable-Frequency Motor Controllers."
 - e. Generator sets specified in Section 263213 "Engine Generators."
 - f. UPS specified in Section 263353 "Static Uninterruptible Power Supply."
- B. Communication Interface to Other Building Systems:
 1. DDC system shall have a communication interface with systems having a communication interface.
 2. Systems to Be Connected:
 - a. Fire-alarm system specified in "Digital, Addressable Fire Alarm System."
 - b. Fire-alarm system specified in Fire-Alarm System.

3.03 CONTROL DEVICES FOR INSTALLATION BY INSTALLERS

- A. Deliver selected control devices, specified in indicated HVAC instrumentation and control device Sections, to identified equipment and systems manufacturers for factory installation and to identified installers for field installation.
- B. Deliver the following to duct fabricator and Installer for installation in ductwork. Include installation instructions to Installer and supervise installation for compliance with requirements.
 1. DDC control dampers, which are specified in Section 230923.12 "DDC Control Dampers."
 2. Airflow sensors and switches, which are specified in Section 230923.14 "Flow Instruments."
 3. Pressure sensors, which are specified in Section 230923.23 "Pressure Instruments."
- C. Deliver the following to plumbing and HVAC piping installers for installation in piping. Include installation instructions to Installer and supervise installation for compliance with requirements.
 1. DDC control valves, which are specified in Section 230923.11 "Control Valves."
 2. Pipe-mounted flow meters, which are specified in Section 230923.14 "Flow Instruments."
 3. Pipe-mounted sensors, switches and transmitters. Flow meters are specified in Section 230923.14 "Flow Instruments." Liquid temperature sensors, switches, and transmitters are specified in Section 230923.27 "Temperature Instruments."

4. Tank-mounted sensors, switches and transmitters. Pressure sensors, switches, and transmitters are specified in Section 230923.23 "Pressure Instruments." Liquid temperature sensors, switches, and transmitters are specified in Section 230923.27 "Temperature Instruments."
5. Pipe- and tank-mounted thermowells. Liquid thermowells are specified in Section 230923.27 "Temperature Instruments."

3.04 CONTROL DEVICES FOR EQUIPMENT MANUFACTURER FACTORY INSTALLATION

- A. Deliver the following to air-handling unit manufacturer for factory installation. Include installation instructions to air-handling unit manufacturer.
 1. Programmable application controller.
 2. Unit-mounted Devices
 - a. DDC control dampers and actuators, which are specified in Section 230923.12 "Control Dampers."
 - b. Airflow Sensors, switched and transmitters.
 - c. Pressure Sensors, switches, and transmitters.
 - d. Temperature Sensors, switches, and transmitters.
 - e. Relays.
- B. Deliver the following to terminal unit manufacturer for factory installation. Include installation instructions to terminal unit manufacturer.
 1. Programmable application controller.
 2. Electric damper actuator. Dampers actuators.
 3. Unit-mounted flow and pressure sensors, transmitters and transducers. Flow sensors, transmitters, and transducers.
 4. Pressure sensors, switches, and transmitters.
 5. Unit-mounted temperature sensors. Air-temperature sensors, switches, and transmitters.
 6. Relays.

3.05 GENERAL INSTALLATION REQUIREMENTS

- A. Install products to satisfy more stringent of all requirements indicated.
- B. Install products level, plumb, parallel, and perpendicular with building construction.
- C. Support products, tubing, piping wiring and raceways. Brace products to prevent lateral movement.
- D. If codes and referenced standards are more stringent than requirements indicated, comply with requirements in codes and referenced standards.
- E. Fabricate openings and install sleeves in ceilings, floors, roof, and walls required by installation of products. Before proceeding with drilling, punching, and cutting, check for concealed work to avoid damage. Patch, flash, grout, seal, and refinish openings to match adjacent condition.
- F. Firestop penetrations made in fire-rated assemblies.
- G. Seal penetrations made in acoustically rated assemblies.
- H. Welding Requirements:
 1. Restrict welding and burning to supports and bracing.
 2. No equipment shall be cut or welded without approval. Welding or cutting will not be approved if there is risk of damage to adjacent Work.
 3. Welding, where approved, shall be by inert-gas electric arc process and shall be performed by qualified welders according to applicable welding codes.

4. If requested on-site, show satisfactory evidence of welder certificates indicating ability to perform welding work intended.
- I. Fastening Hardware:
 1. Stillson wrenches, pliers, and other tools that damage surfaces of rods, nuts, and other parts are prohibited for work of assembling and tightening fasteners.
 2. Tighten bolts and nuts firmly and uniformly. Do not overstress threads by excessive force or by oversized wrenches.
 3. Lubricate threads of bolts, nuts and screws with graphite and oil before assembly.
- J. If product locations are not indicated, install products in locations that are accessible and that will permit service and maintenance from floor, equipment platforms, or catwalks without removal of permanently installed furniture and equipment.
- K. Corrosive Environments:
 1. When conduit is in contact with a corrosive airstream and environment, use Type 316 stainless-steel conduit and fittings or conduit and fittings that are coated with a corrosive-resistant coating that is suitable for environment. Comply with requirements for installation of raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
 2. Where instruments are located in a corrosive airstream and are not corrosive resistant from manufacturer, field install products in NEMA 250, Type 4X enclosure constructed of Type 316L stainless steel.

3.06 CONTROLLER INSTALLATION

- A. Install controllers in enclosures to comply with indicated requirements.
- B. Connect controllers to field power supply and to UPS units.
- C. Install controller with latest version of applicable software and configure to execute requirements indicated.
- D. Test and adjust controllers to verify operation of connected I/O to achieve performance indicated requirements while executing sequences of operation.
- E. Installation of Network Controllers:
 1. Quantity and location of network controllers shall be determined by DDC system manufacturer to satisfy requirements indicated.
 2. Install controllers in a protected location that is easily accessible by operators.
 3. Top of controller shall be within 72 inches of finished floor.
- F. Installation of Programmable Application Controllers:
 1. Quantity and location of programmable application controllers shall be determined by DDC system manufacturer to satisfy requirements indicated.
 2. Install controllers in a protected location that is easily accessible by operators.
 3. Top of controller shall be within 72 inches of finished floor.
- G. Application-Specific Controllers:
 1. Quantity and location of application-specific controllers shall be determined by DDC system manufacturer to satisfy requirements indicated.
 2. For controllers not mounted directly on equipment being controlled, install controllers in a protected location that is easily accessible by operators.

3.07 ENCLOSURES INSTALLATION

- A. Install the following items in enclosures, to comply with indicated requirements:
 1. Gateways.
 2. Routers.

3. Controllers.
 4. Electrical power devices.
 5. UPS units.
 6. Relays.
 7. Accessories.
 8. Instruments.
 9. Actuators
- B. Attach wall-mounted enclosures to wall.
- C. Align top of adjacent enclosures.
- D. Install continuous and fully accessible wireways to connect conduit, wire, and cable to multiple adjacent enclosures. Wireway used for application shall have protection equal to NEMA 250 rating of connected enclosures.

3.08 ELECTRIC POWER CONNECTIONS

- A. Connect electrical power to DDC system products requiring electrical power connections.
- B. Design of electrical power to products not indicated with electric power is delegated to DDC system provider and installing trade. Work shall comply with NFPA 70 and other requirements indicated.
- C. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers" for electrical power circuit breakers.
- D. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for electrical power conductors and cables.
- E. Comply with requirements in Section 260533 "Raceways and Boxes for Electrical Systems" for electrical power raceways and boxes.

3.09 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements in Section 260553 "Identification for Electrical Systems" for identification products and installation.
- B. Install engraved phenolic nameplate with unique identification on face for each of the following:
1. Operator workstation.
 2. Printer.
 3. Gateway.
 4. Router.
 5. DDC controller.
 6. Enclosure.
 7. Electrical power device.
 8. UPS unit.
 9. Accessory.
- C. Install engraved phenolic nameplate with unique instrument identification on face of each instrument connected to a DDC controller.
- D. Install engraved phenolic nameplate with identification on face of each control damper and valve actuator connected to a DDC controller.
- E. Where product is installed above accessible tile ceiling, also install matching engraved phenolic nameplate with identification on face of ceiling grid located directly below.
- F. Where product is installed above an inaccessible ceiling, also install engraved phenolic nameplate with identification on face of access door directly below.
- G. Warning Labels:

1. Shall be permanently attached to equipment that can be automatically started by DDC control system.
2. Shall be located in highly visible location near power service entry points.

3.10 CONTROL WIRE, CABLE AND RACEWAYS INSTALLATION

- A. Comply with NECA 1.
- B. Comply with TIA 568-C.1.
- C. Wiring Method: Install cables in raceways and cable trays. Conceal raceway and cables except in unfinished spaces.
 1. Install plenum cable in environmental air spaces, including plenum ceilings.
 2. Comply with requirements for cable trays specified in Section 260536 "Cable Trays for Electrical Systems."
 3. Comply with requirements for raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
- D. Wiring Method: Conceal conductors and cables in accessible ceilings, walls, and floors where possible.
- E. Field Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Install lacing bars and distribution spools.
- F. Conduit Installation:
 1. Install conduit expansion joints where conduit runs exceed 200 feet, and conduit crosses building expansion joints.
 2. Coordinate conduit routing with other trades to avoid conflicts with ducts, pipes and equipment and service clearance.
 3. Maintain at least 3-inch separation where conduits run axially above or below ducts and pipes.
 4. Limit above-grade conduit runs to 100 feet without pull or junction box.
 5. Do not install raceways or electrical items on any "explosion-relief" walls, or rotating equipment.
 6. Do not fasten conduits onto the bottom side of a metal deck roof.
 7. Flexible conduit is permitted only where flexibility and vibration control is required.
 8. Limit flexible conduit to 3 feet long.
 9. Conduit shall be continuous from outlet to outlet, from outlet to enclosures, pull and junction boxes, and shall be secured to boxes in such manner that each system shall be electrically continuous throughout.
 10. Direct bury conduits underground or install in concrete-encased duct bank where indicated.
 - a. Use rigid, nonmetallic, Schedule 80 PVC.
 - b. Provide a burial depth according to NFPA 70, but not less than 24 inches.
 11. Secure threaded conduit entering an instrument enclosure, cabinet, box, and trough, with a locknut on outside and inside, such that conduit system is electrically continuous throughout. Provide a metal bushing on inside with insulated throats. Locknuts shall be the type designed to bite into the metal or, on inside of enclosure, shall have a grounding wedge lug under locknut.
 12. Conduit box-type connectors for conduit entering enclosures shall have an insulated throat.
 13. Connect conduit entering enclosures in wet locations with box-type connectors or with watertight sealing locknuts or other fittings.
 14. Offset conduits where entering surface-mounted equipment.

15. Seal conduit runs used by sealing fittings to prevent the circulation of air for the following:
 - a. Conduit extending from interior to exterior of building.
 - b. Conduit extending into pressurized duct and equipment.
 - c. Conduit extending into pressurized zones that are automatically controlled to maintain different pressure set points.
- G. Wire and Cable Installation:
 1. Cables serving a common system may be grouped in a common raceway. Install control wiring and cable in separate raceway from power wiring. Do not group conductors from different systems or different voltages.
 2. Install cables with protective sheathing that is waterproof and capable of withstanding continuous temperatures of 90 deg C with no measurable effect on physical and electrical properties of cable.
 - a. Provide shielding to prevent interference and distortion from adjacent cables and equipment.
 3. Install lacing bars to restrain cables, to prevent straining connections, and to prevent bending cables to smaller radii than minimums recommended by manufacturer.
 4. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIMM, "Cabling Termination Practices" Chapter. Install lacing bars and distribution spools.
 5. UTP Cable Installation:
 - a. Comply with TIA 568-C.2.
 - b. Do not untwist UTP cables more than 1/2 inch from the point of termination, to maintain cable geometry.
 6. Identify each wire on each end and at each terminal with a number-coded identification tag. Each wire shall have a unique tag.
 7. Provide strain relief.
 8. Terminate wiring in a junction box.
 - a. Clamp cable over jacket in junction box.
 - b. Individual conductors in the stripped section of the cable shall be slack between the clamping point and terminal block.
 9. Terminate field wiring and cable not directly connected to instruments and control devices having integral wiring terminals using terminal blocks.
 10. Install signal transmission components according to IEEE C2, REA Form 511a, NFPA 70, and as indicated.
 11. Keep runs short. Allow extra length for connecting to terminal boards. Do not bend flexible coaxial cables in a radius less than 10 times the cable OD. Use sleeves or grommets to protect cables from vibration at points where they pass around sharp corners and through penetrations.
 12. Ground wire shall be copper and grounding methods shall comply with IEEE C2. Demonstrate ground resistance.
 13. Wire and cable shall be continuous from terminal to terminal without splices.
 14. Use insulated spade lugs for wire and cable connection to screw terminals.
 15. Use shielded cable to transmitters.
 16. Use shielded cable to temperature sensors.
 17. Perform continuity and meager testing on wire and cable after installation.

18. Do not install bruised, kinked, scored, deformed, or abraded wire and cable. Remove and discard wire and cable if damaged during installation, and replace it with new cable.
19. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
20. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
21. Protection from Electro-Magnetic Interference (EMI): Provide installation free of (EMI). As a minimum, comply with the following requirements:
 - a. Comply with BICSI TDMM and TIA 569-C for separating unshielded cable from potential EMI sources, including electrical power lines and equipment.
 - b. Separation between open cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:
 - 1) Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
 - 2) Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
 - 3) Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.
 - c. Separation between cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
 - 1) Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
 - 2) Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
 - 3) Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
 - d. Separation between cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
 - 1) Electrical Equipment Rating Less Than 2 kVA: No requirement.
 - 2) Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
 - 3) Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
 - e. Separation between Cables and Electrical Motors and Transformers, 5 kVA or 5 HP and Larger: A minimum of 48 inches.
 - f. Separation between Cables and Fluorescent Fixtures: A minimum of 5 inches.

3.11 DDC SYSTEM I/O CHECKOUT PROCEDURES

- A. Check installed products before continuity tests, leak tests and calibration.
- B. Check instruments for proper location and accessibility.
- C. Check instruments for proper installation on direction of flow, elevation, orientation, insertion depth, or other applicable considerations that will impact performance.
- D. Check instrument tubing for proper isolation, fittings, slope, dirt legs, drains, material and support.
- E. For pneumatic products, verify that air supply for each product is properly installed.
- F. Control Damper Checkout:
 1. Verify that control dampers are installed correctly for flow direction.
 2. Verify that proper blade alignment, either parallel or opposed, has been provided.
 3. Verify that damper frame attachment is properly secured and sealed.
 4. Verify that damper actuator and linkage attachment is secure.
 5. Verify that actuator wiring is complete, enclosed and connected to correct power source.
 6. Verify that damper blade travel is unobstructed.
- G. Control Valve Checkout:

1. For pneumatic valves, verify that pressure gages are provided in each air line to valve actuator and positioner.
 2. Verify that control valves are installed correctly for flow direction.
 3. Verify that valve body attachment is properly secured and sealed.
 4. Verify that valve actuator and linkage attachment is secure.
 5. Verify that actuator wiring is complete, enclosed and connected to correct power source.
 6. Verify that valve ball, disc or plug travel is unobstructed.
 7. After piping systems have been tested and put into service, but before insulating and balancing, inspect each valve for leaks. Adjust or replace packing to stop leaks. Replace the valve if leaks persist.
- H. Instrument Checkout:
1. Verify that instrument is correctly installed for location, orientation, direction and operating clearances.
 2. Verify that attachment is properly secured and sealed.
 3. Verify that conduit connections are properly secured and sealed.
 4. Verify that wiring is properly labeled with unique identification, correct type and size and is securely attached to proper terminals.
 5. Inspect instrument tag against approved submittal.
 6. For instruments with tubing connections, verify that tubing attachment is secure and isolation valves have been provided.
 7. For flow instruments, verify that recommended upstream and downstream distances have been maintained.
 8. For temperature instruments:
 - a. Verify sensing element type and proper material.
 - b. Verify length and insertion.

3.12 DDC SYSTEM I/O ADJUSTMENT, CALIBRATION AND TESTING:

- A. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.
- B. Provide a written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.
- C. For each analog instrument, make a three-point test of calibration for both linearity and accuracy.
- D. Equipment and procedures used for calibration shall comply with instrument manufacturer's written instructions.
- E. Provide diagnostic and test equipment for calibration and adjustment.
- F. Field instruments and equipment used to test and calibrate installed instruments shall have accuracy at least twice the instrument accuracy being calibrated. An installed instrument with an accuracy of 1 percent shall be checked by an instrument with an accuracy of 0.5 percent.
- G. Calibrate each instrument according to instrument instruction manual supplied by manufacturer.
- H. If after calibration indicated performance cannot be achieved, replace out-of-tolerance instruments.
- I. Comply with field testing requirements and procedures indicated by ASHRAE's Guideline 11, "Field Testing of HVAC Control Components," in the absence of specific requirements, and to supplement requirements indicated.
- J. Analog Signals:
 1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.

2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.
 3. Check resistance signals for temperature sensors at zero, 50, and 100 percent of operating span using a precision-resistant source.
- K. Digital Signals:
1. Check digital signals using a jumper wire.
 2. Check digital signals using an ohmmeter to test for contact making or breaking.
- L. Control Dampers:
1. Stroke and adjust control dampers following manufacturer's recommended procedure, from 100 percent open to 100 percent closed and back to 100 percent open.
 2. Stroke control dampers with pilot positioners. Adjust damper and positioner following manufacturer's recommended procedure, so damper is 100 percent closed, 50 percent closed and 100 percent open at proper air pressure.
 3. Check and document open and close cycle times for applications with a cycle time less than 30 seconds.
 4. For control dampers equipped with positive position indication, check feedback signal at multiple positions to confirm proper position indication.
- M. Control Valves:
1. Stroke and adjust control valves following manufacturer's recommended procedure, from 100 percent open to 100 percent closed and back to 100 percent open.
 2. Stroke control valves with pilot positioners. Adjust valve and positioner following manufacturer's recommended procedure, so valve is 100 percent closed, 50 percent closed and 100 percent open at proper air pressures.
 3. Check and document open and close cycle times for applications with a cycle time less than 30 seconds.
 4. For control valves equipped with positive position indication, check feedback signal at multiple positions to confirm proper position indication.
- N. Meters: Check sensors at zero, 50, and 100 percent of Project design values.
- O. Sensors: Check sensors at zero, 50, and 100 percent of Project design values.
- P. Switches: Calibrate switches to make or break contact at set points indicated.
- Q. Transmitters:
1. Check and calibrate transmitters at zero, 50, and 100 percent of Project design values.
 2. Calibrate resistance temperature transmitters at zero, 50, and 100 percent of span using a precision-resistant source.

3.13 DDC SYSTEM CONTROLLER CHECKOUT

- A. Verify power supply.
1. Verify voltage, phase and hertz.
 2. Verify that protection from power surges is installed and functioning.
 3. Verify that ground fault protection is installed.
 4. If applicable, verify if connected to UPS unit.
 5. If applicable, verify if connected to a backup power source.
 6. If applicable, verify that power conditioning units, transient voltage suppression and high-frequency noise filter units are installed.
- B. Verify that wire and cabling is properly secured to terminals and labeled with unique identification.
- C. Verify that spare I/O capacity is provided.

3.14 DDC CONTROLLER I/O CONTROL LOOP TESTS

- A. Testing:
1. Test every I/O point connected to DDC controller to verify that safety and operating control set points are as indicated and as required to operate controlled system safely and at optimum performance.
 2. Test every I/O point throughout its full operating range.
 3. Test every control loop to verify operation is stable and accurate.
 4. Adjust control loop proportional, integral and derivative settings to achieve optimum performance while complying with performance requirements indicated. Document testing of each control loop's precision and stability via trend logs.
 5. Test and adjust every control loop for proper operation according to sequence of operation.
 6. Test software and hardware interlocks for proper operation. Correct deficiencies.
 7. Operate each analog point at the following:
 - a. Upper quarter of range.
 - b. Lower quarter of range.
 - c. At midpoint of range.
 8. Exercise each binary point.
 9. For every I/O point in DDC system, read and record each value at operator workstation, at DDC controller and at field instrument simultaneously. Value displayed at operator workstation, at DDC controller and at field instrument shall match.
 10. Prepare and submit a report documenting results for each I/O point in DDC system and include in each I/O point a description of corrective measures and adjustments made to achieve desired results.

3.15 DDC SYSTEM VALIDATION TESTS

- A. Perform validation tests before requesting final review of system. Before beginning testing, first submit Pretest Checklist and Test Plan.
- B. After approval of Test Plan, execute all tests and procedures indicated in plan.
- C. After testing is complete, submit completed test checklist.
- D. Pretest Checklist: Submit the following list with items checked off once verified:
1. Detailed explanation for any items that are not completed or verified.
 2. Required mechanical installation work is successfully completed and HVAC equipment is working correctly.
 3. HVAC equipment motors operate below full-load amperage ratings.
 4. Required DDC system components, wiring, and accessories are installed.
 5. Installed DDC system architecture matches approved Drawings.
 6. Control electric power circuits operate at proper voltage and are free from faults.
 7. Required surge protection is installed.
 8. DDC system network communications function properly, including uploading and downloading programming changes.
 9. Using BACnet protocol analyzer, verify that communications are error free.
 10. Each controller's programming is backed up.
 11. Equipment, products, tubing, wiring cable and conduits are properly labeled.
 12. All I/O points are programmed into controllers.
 13. Testing, adjusting and balancing work affecting controls is complete.

14. Dampers and actuators zero and span adjustments are set properly.
15. Each control damper and actuator goes to failed position on loss of power.
16. Valves and actuators zero and span adjustments are set properly.
17. Each control valve and actuator goes to failed position on loss of power.
18. Meter, sensor and transmitter readings are accurate and calibrated.
19. Control loops are tuned for smooth and stable operation.
20. View trend data where applicable.
21. Each controller works properly in standalone mode.
22. Safety controls and devices function properly.
23. Interfaces with fire-alarm system function properly.
24. Electrical interlocks function properly.
25. Operator workstations and other interfaces are delivered, all system and database software is installed, and graphic are created.
26. Record Drawings are completed.

E. Test Plan:

1. Prepare and submit a validation test plan including test procedures for performance validation tests.
2. Test plan shall address all specified functions of DDC system and sequences of operation.
3. Explain detailed actions and expected results to demonstrate compliance with requirements indicated.
4. Explain method for simulating necessary conditions of operation used to demonstrate performance.
5. Include a test checklist to be used to check and initial that each test has been successfully completed.

F. Validation Test:

1. Verify operating performance of each I/O point in DDC system.
 - a. Verify analog I/O points at operating value.
 - b. Make adjustments to out-of-tolerance I/O points.
 - 1) Identify I/O points for future reference.
 - 2) Simulate abnormal conditions to demonstrate proper function of safety devices.
 - 3) Replace instruments and controllers that cannot maintain performance indicated after adjustments.
2. Simulate conditions to demonstrate proper sequence of control.
3. Readjust settings to design values and observe ability of DDC system to establish desired conditions.
4. After 24 Hours following Initial Validation Test:
 - a. Re-check I/O points that required corrections during initial test.
 - b. Identify I/O points that still require additional correction and make corrections necessary to achieve desired results.
5. After 24 Hours of Second Validation Test:
 - a. Re-check I/O points that required corrections during second test.
 - b. Continue validation testing until I/O point is normal on two consecutive tests.
6. Completely check out, calibrate, and test all connected hardware and software to ensure that DDC system performs according to requirements indicated.

7. After validation testing is complete, prepare and submit a report indicating all I/O points that required correction and how many validation re-tests it took to pass. Identify adjustments made for each test and indicate instruments that were replaced.

3.16 FINAL REVIEW

- A. Submit written request to Architect when DDC system is ready for final review. Written request shall state the following:
 1. DDC system has been thoroughly inspected for compliance with contract documents and found to be in full compliance.
 2. DDC system has been calibrated, adjusted and tested and found to comply with requirements of operational stability, accuracy, speed and other performance requirements indicated.
 3. DDC system monitoring and control of HVAC systems results in operation according to sequences of operation indicated.
 4. DDC system is complete and ready for final review.
- B. Review by Architect shall be made after receipt of written request. A field report shall be issued to document observations and deficiencies.
- C. Take prompt action to remedy deficiencies indicated in field report and submit a second written request when all deficiencies have been corrected. Repeat process until no deficiencies are reported.
- D. Should more than two reviews be required, DDC system manufacturer and Installer shall compensate entity performing review for total costs, labor and expenses, associated with third and subsequent reviews. Estimated cost of each review shall be submitted and approved by DDC system manufacturer and Installer before making the review.
- E. Prepare and submit closeout submittals when no deficiencies are reported.
- F. A part of DDC system final review shall include a demonstration to parties participating in final review.
 1. Provide staff familiar with DDC system installed to demonstrate operation of DDC system during final review.
 2. Provide testing equipment to demonstrate accuracy and other performance requirements of DDC system that is requested by reviewers during final review.
 3. Demonstration shall include, but not be limited to, the following:
 - a. Accuracy and calibration of I/O points randomly selected by reviewers. If review finds that some I/O points are not properly calibrated and not satisfying performance requirements indicated, additional I/O points may be selected by reviewers until total I/O points being reviewed that satisfy requirements equals quantity indicated.
 - b. HVAC equipment and system hardwired and software safeties and life-safety functions are operating according to sequence of operation. Up to 10 I/O points shall be randomly selected by reviewers. Additional I/O points may be selected by reviewers to discover problems with operation.
 - c. Correct sequence of operation after electrical power interruption and resumption after electrical power is restored for randomly selected HVAC systems.
 - d. Operation of randomly selected dampers and valves in normal-on, normal-off and failed positions.
 - e. Reporting of alarm conditions for randomly selected alarms, including different classes of alarms, to ensure that alarms are properly received by operators and operator workstations.
 - f. Trends, summaries, logs and reports set-up for Project.

- g. For up to three HVAC systems randomly selected by reviewers, use graph trends to show that sequence of operation is executed in correct manner and that HVAC systems operate properly through complete sequence of operation including different modes of operations indicated. Show that control loops are stable and operating at set points and respond to changes in set point of 20 percent or more.
- h. Software's ability to communicate with controllers, operator workstations, uploading and downloading of control programs.
- i. Software's ability to edit control programs off-line.
- j. Data entry to show Project-specific customizing capability including parameter changes.
- k. Step through penetration tree, display all graphics, demonstrate dynamic update, and direct access to graphics.
- l. Execution of digital and analog commands in graphic mode.
- m. Spreadsheet and curve plot software and its integration with database.
- n. Online user guide and help functions.
- o. Multitasking by showing different operations occurring simultaneously on four quadrants of split screen.
- p. System speed of response compared to requirements indicated.
- q. For Each Programmable Application Controller:
 - 1) Memory: Programmed data, parameters, trend and alarm history collected during normal operation is not lost during power failure.
 - 2) Operator Interface: Ability to connect directly to each type of digital controller with a portable operator workstation and PDA. Show that maintenance personnel interface tools perform as indicated in manufacturer's technical literature.
 - 3) Standalone Ability: Demonstrate that controllers provide stable and reliable standalone operation using default values or other method for values normally read over network.
 - 4) Electric Power: Ability to disconnect any controller safely from its power source.
 - 5) Wiring Labels: Match control drawings.
 - 6) Network Communication: Ability to locate a controller's location on network and communication architecture matches Shop Drawings.
 - 7) Nameplates and Tags: Accurate and permanently attached to control panel doors, instrument, actuators and devices.
- r. For Each Operator Workstation:
 - 1) I/O points lists agree with naming conventions.
 - 2) Graphics are complete.
 - 3) UPS unit, if applicable, operates.
- s. Communications and Interoperability: Demonstrate proper interoperability of data sharing, alarm and event management, trending, scheduling, and device and network management. Use ASHRAE 135 protocol analyzer to help identify devices, view network traffic, and verify interoperability. Requirements must be met even if only one manufacturer's equipment is installed.
 - 1) Data Presentation: On each operator workstation, demonstrate graphic display capabilities.
 - 2) Reading of Any Property: Demonstrate ability to read and display any used readable object property of any device on network.

- 3) Set Point and Parameter Modifications: Show ability to modify set points and tuning parameters indicated. Modifications are made with messages and write services initiated by an operator using workstation graphics, or by completing a field in a menu with instructional text.
- 4) Peer-to-Peer Data Exchange: Network devices are installed and configured to perform without need for operator intervention to implement Project sequence of operation and to share global data.
- 5) Alarm and Event Management: Alarms and events are installed and prioritized according to Owner. Demonstrate that time delays and other logic are set up to avoid nuisance tripping. Show that operators with sufficient privileges are permitted.
- 6) Schedule Lists: Schedules are configured for start and stop, mode change, occupant overrides, and night setback as defined in sequence of operations.
- 7) Schedule Display and Modification: Ability to display any schedule with start and stop times for calendar year. Show that all calendar entries and schedules are modifiable from any connected operator workstation by an operator with sufficient privilege.
- 8) Archival Storage of Data: Data archiving is handled by operator workstation and server and local trend archiving and display is accomplished.
- 9) Modification of Trend Log Object Parameters: Operator with sufficient privilege can change logged data points, sampling rate, and trend duration.
- 10) Device and Network Management:
 - a) Display of network device status.
 - b) Display of BACnet Object Information.
 - c) Silencing devices transmitting erroneous data.
 - d) Time synchronization.
 - e) Remote device re-initialization.
 - f) Backup and restore network device programming and master database(s).
 - g) Configuration management of routers.

3.17 ADJUSTING

- A. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.18 DEMONSTRATION

- A. Engage a factory-authorized service representative with complete knowledge of Project-specific system installed to train Owner's maintenance personnel to adjust, operate, and maintain DDC system.
- B. Extent of Training:
 1. Base extent of training on scope and complexity of DDC system indicated and training requirements indicated. Provide extent of training required to satisfy requirements indicated even if more than minimum training requirements are indicated.
 2. Inform Owner of anticipated training requirements if more than minimum training requirements are indicated.
 3. Minimum Training Requirements:
 - a. Provide not less than 3 days of training total.
 - b. Stagger training over multiple training classes to accommodate Owner's requirements. All training shall occur before end of warranty period.

- C. Training Schedule:
 - 1. Schedule training with Owner **20** business days before expected Substantial Completion.
 - 2. Schedule training to provide Owner with at least **10** business days of notice in advance of training.
 - 3. Provide staggered training schedule as requested by Owner.
- D. Training Attendee List and Sign-in Sheet:
 - 1. Request from Owner in advance of training a proposed attendee list with name, phone number and e-mail address.
 - 2. Provide a preprinted sign-in sheet for each training session with proposed attendees listed and no fewer than six blank spaces to add additional attendees.
 - 3. Preprinted sign-in sheet shall include training session number, date and time, instructor name, phone number and e-mail address, and brief description of content to be covered during session. List attendees with columns for name, phone number, e-mail address and a column for attendee signature or initials.
 - 4. Circulate sign-in sheet at beginning of each session and solicit attendees to sign or initial in applicable location.
 - 5. At end of each training day, send Owner an e-mail with an attachment of scanned copy (PDF) of circulated sign-in sheet for each session.
- E. Attendee Training Manuals:
 - 1. Provide each attendee with a color hard copy of all training materials and visual presentations.
 - 2. Hard-copy materials shall be organized in a three-ring binder with table of contents and individual divider tabs marked for each logical grouping of subject matter. Organize material to provide space for attendees to take handwritten notes within training manuals.
 - 3. In addition to hard-copy materials included in training manual, provide each binder with a sleeve or pocket that includes a DVD or flash drive with PDF copy of all hard-copy materials.
- F. Organization of Training Sessions:
 - 1. Organize training sessions into logical groupings of technical content and to reflect different levels of operators having access to system. Plan training sessions to accommodate the following three levels of operators:
 - a. Daily operators.
 - b. Advanced operators.
 - c. System managers and administrators.
 - 2. Plan and organize training sessions to group training content to protect DDC system security. Some attendees may be restricted to some training sessions that cover restricted content for purposes of maintaining DDC system security.
- G. Training Outline:
 - 1. Submit training outline for Owner review at least 10 business day before scheduling training.
 - 2. Outline shall include a detailed agenda for each training day that is broken down into each of four training sessions that day, training objectives for each training session and synopses for each lesson planned.
- H. On-Site Training:
 - 1. Owner will provide conditioned classroom or workspace with ample desks or tables, chairs, power and data connectivity for instructor and each attendee.

2. Instructor shall provide training materials, projector and other audiovisual equipment used in training.
 3. Provide as much of training located on-site as deemed feasible and practical by Owner.
 4. On-site training shall include regular walk-through tours, as required, to observe each unique product type installed with hands-on review of operation, calibration and service requirements.
 5. Operator workstation provided with DDC system shall be used in training. If operator workstation is not indicated, provide a temporary workstation to convey training content.
- I. Training Content for Daily Operators:
1. Basic operation of system.
 2. Understanding DDC system architecture and configuration.
 3. Understanding each unique product type installed including performance and service requirements for each.
 4. Understanding operation of each system and equipment controlled by DDC system including sequences of operation, each unique control algorithm and each unique optimization routine.
 5. Operating operator workstations, printers and other peripherals.
 6. Logging on and off system.
 7. Accessing graphics, reports and alarms.
 8. Adjusting and changing set points and time schedules.
 9. Recognizing DDC system malfunctions.
 10. Understanding content of operation and maintenance manuals including control drawings.
 11. Understanding physical location and placement of DDC controllers and I/O hardware.
 12. Accessing data from DDC controllers.
 13. Operating portable operator workstations.
 14. Review of DDC testing results to establish basic understanding of DDC system operating performance and HVAC system limitations as of Substantial Completion.
 15. Running each specified report and log.
 16. Displaying and demonstrating each data entry to show Project-specific customizing capability. Demonstrating parameter changes.
 17. Stepping through graphics penetration tree, displaying all graphics, demonstrating dynamic updating, and direct access to graphics.
 18. Executing digital and analog commands in graphic mode.
 19. Demonstrating control loop precision and stability via trend logs of I/O for not less than 10 percent of I/O installed.
 20. Demonstrating DDC system performance through trend logs and command tracing.
 21. Demonstrating scan, update, and alarm responsiveness.
 22. Demonstrating spreadsheet and curve plot software, and its integration with database.
 23. Demonstrating on-line user guide, and help function and mail facility.
 24. Demonstrating multitasking by showing dynamic curve plot, and graphic construction operating simultaneously via split screen.
 25. Demonstrating the following for HVAC systems and equipment controlled by DDC system:
 - a. Operation of HVAC equipment in normal-off, -on and failed conditions while observing individual equipment, dampers and valves for correct position under each condition.

- b. For HVAC equipment with factory-installed software, show that integration into DDC system is able to communicate with DDC controllers or gateways, as applicable.
 - c. Using graphed trends, show that sequence of operation is executed in correct manner, and HVAC systems operate properly through complete sequence of operation including seasonal change, occupied and unoccupied modes, warm-up and cool-down cycles and other modes of operation indicated.
 - d. Hardware interlocks and safeties function properly and DDC system performs correct sequence of operation after electrical power interruption and resumption after power is restored.
 - e. Reporting of alarm conditions for each alarm, and confirm that alarms are received at assigned locations, including operator workstations.
 - f. Each control loop responds to set point adjustment and stabilizes within time period indicated.
 - g. Sharing of previously graphed trends of all control loops to demonstrate that each control loop is stable and set points are being maintained.
- J. Training Content for Advanced Operators:
- 1. Making and changing workstation graphics.
 - 2. Creating, deleting and modifying alarms including annunciation and routing.
 - 3. Creating, deleting and modifying point trend logs including graphing and printing on an ad-hoc basis and operator-defined time intervals.
 - 4. Creating, deleting and modifying reports.
 - 5. Creating, deleting and modifying points.
 - 6. Creating, deleting and modifying programming including ability to edit control programs off-line.
 - 7. Creating, deleting and modifying system graphics and other types of displays.
 - 8. Adding DDC controllers and other network communication devices such as gateways and routers.
 - 9. Adding operator workstations.
 - 10. Performing DDC system checkout and diagnostic procedures.
 - 11. Performing DDC controllers operation and maintenance procedures.
 - 12. Performing operator workstation operation and maintenance procedures.
 - 13. Configuring DDC system hardware including controllers, workstations, communication devices and I/O points.
 - 14. Maintaining, calibrating, troubleshooting, diagnosing and repairing hardware.
 - 15. Adjusting, calibrating and replacing DDC system components.
- K. Training Content for System Managers and Administrators:
- 1. DDC system software maintenance and backups.
 - 2. Uploading, downloading and off-line archiving of all DDC system software and databases.
 - 3. Interface with Project-specific, third-party operator software.
 - 4. Understanding password and security procedures.
 - 5. Adding new operators and making modifications to existing operators.
 - 6. Operator password assignments and modification.
 - 7. Operator authority assignment and modification.
 - 8. Workstation data segregation and modification.

L. Video of Training Sessions:

1. Provide a digital video and audio recording of each training session. Create a separate recording file for each session.
2. Stamp each recording file with training session number, session name and date.
3. Provide Owner with copies of digital files for later reference and for use in future training.
4. Owner retains right to make additional copies for intended training purposes without having to pay royalties.

END OF SECTION

SECTION 23 52 16
CONDENSING BOILERS

PART 1 GENERAL

1.01 SUMMARY

- A. Section includes gas-fired, condensing boilers, trim, and accessories for generating heating hot water.

1.02 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include rated capacities, operating and shipping weights, furnished specialties, furnished accessories, efficiency curves, pressure drop curves, and warranty information.
- B. Shop Drawings: For boilers, boiler trim, and accessories. Include plans, elevations, sections, and mounting and attachment details.
 - 1. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 2. Include diagrams for power, signal, and control wiring.
 - 3. Piping diagrams indicating valving, gauges, accessories, pipe material, and differentiate between field installed and factory installed piping and accessories.
 - 4. Safety relief valve settings.
 - 5. Include manufacturer and model number of included trim along with catalog information for gauges, burner controller, low water control, stack thermometer, and other trim items.
 - 6. Burner manufacturer and model number indicating turndown, emissions information, inlet gas pressure, and capacities.
 - 7. Indicate valving, gauges, pipe sizes, and vent sizes for gas train piping.
 - 8. Include minimum and maximum NG and/or propane pressures.

1.03 INFORMATIONAL SUBMITTALS

- A. Source quality-control reports.
- B. Field quality-control reports.
- C. Sample Warranty: For special warranty.

1.04 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

1.05 WARRANTY

- A. Manufacturer's Warranty: Manufacturer agrees to repair or replace components of boilers that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period for Fire-Tube Condensing Boilers:
 - a. Leakage and Materials: 10 years from date of Substantial Completion.
 - b. Heat Exchanger Damaged by Thermal Stress and Corrosion: 520 years from date of Substantial Completion.

PART 2 PRODUCTS

2.01 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ASME Compliance: Fabricate and label boilers to comply with 2010 ASME Boiler and Pressure Vessel Code.

- C. ASHRAE/IES 90.1 Compliance: Boilers shall have minimum efficiency according to "Gas and Oil Fired Boilers - Minimum Efficiency Requirements."
- D. DOE Compliance: Minimum efficiency shall comply with 10 CFR 430, Subpart B, Appendix N.
- E. UL Compliance: Test boilers for compliance with UL 795. Boilers shall be listed and labeled by a testing agency acceptable to authorities having jurisdiction.
- F. CSA Compliance: Test boilers for compliance with CSA B51.

2.02 FORCED-DRAFT, FIRE-TUBE CONDENSING BOILERS

- A. Manufacturers: Subject to compliance with requirements, provide boilers by one of the following:
 - 1. Aerco.
 - 2. Advanced Thermal Hydronics.
 - 3. Cleaver Brooks.
 - 4. Fulton.
 - 5. Laars
 - 6. Lochinvar.
 - 7. Patterson-Kelley.
 - 8. Riello.
 - 9. Viessmann.
- B. Description: Factory-fabricated, -assembled, and -tested, fire-tube condensing boiler with heat exchanger sealed pressure tight, built on a steel base, including insulated jacket; flue-gas vent; combustion-air intake connections; water supply, return, and condensate drain connections; and controls. Water-heating service only.
- C. The primary pressure vessel design and construction shall be in accordance with Section IV of the ASME Code for heating boilers. The maximum design temperature shall be 250 deg F.
- D. Heat Exchanger: Nonferrous, corrosion-resistant combustion chamber.
- E. Pressure Vessel: Carbon steel with welded heads and tube connections.
- F. Burner: Natural gas, forced draft, modulating operation with a minimum 10:1 turndown without loss of combustion efficiency.
 - 1. Burner shall meet SCAQMD (South Coast Air Quality Management District) and emit less than 30 PPM NOx, at 3% excess oxygen and less than 400 PPM carbon monoxide at 3% excess oxygen.
- G. Blower: Centrifugal fan to operate during each burner firing sequence and to pre-purge and post-purge the combustion chamber.
 - 1. Motors: Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
 - a. Motor Sizes: Minimum size as indicated; if not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.
 - 2. The forced draft combustion boiler will require a vent utilizing AL-29-4C or CPVC as allowed by boiler manufacturer. The boiler is capable of drawing combustion air from the room or ducted outside.
 - 3. The boiler shall be capable of ducted exhaust and combustion to the outside.
- H. Gas Train: Combination gas valve with manual shutoff and pressure regulator.
- I. Ignition: Spark ignition with 100 percent main-valve shutoff with electronic flame supervision.
- J. Casing:
 - 1. Jacket: Sheet metal with snap-in or interlocking closures.

2. Control Compartment Enclosures: NEMA 250, Type 1A.
3. Finish: Baked-enamel or Powder-coated protective finish.
4. Insulation: Minimum 1/2-inch-thick, mineral-fiber or polyurethane-foam insulation surrounding the heat exchanger; provide thickness as required to meet heat losses.
5. Combustion-Air Connections: Inlet and vent duct collars.
6. Steel mounting base with lifting lugs.

2.03 TRIM

- A. Include devices sized to comply with ASME B31.9.
- B. Aquastat Controllers: Operating, firing rate, and high limit.
- C. Safety Relief Valve: ASME rated, Section IV, side outlet type safety valve(s) per ASME requirements.
- D. Pressure and Temperature Gage: Minimum 3-1/2-inch-diameter, combination water-pressure and -temperature gage. Gages shall have operating-pressure and -temperature ranges, so normal operating range is about 50 percent of full range.
- E. Boiler Air Vent: Manual.
- F. Drain Valve: Minimum NPS 3/4 hose-end gate valve.
- G. Combustion chamber temperature and pressure gauge.
- H. A condensate drain connection in the exhaust outlet.
- I. A neutralization condensate drain kit will be provided to collect and drain the flue gas condensate.
- J. If connections are flanged, they shall be 150 psig connections.

2.04 CONTROLS

- A. Boiler operation controls shall be in accordance with ASME CSD-1, latest edition.
- B. Refer to Section 230923 "Direct Digital Control (DDC) System for HVAC."
- C. Refer to drawings for sequence of operations.
- D. Boiler operating controls shall include the following devices and features:
 1. Touch screen display factory mounted displaying status, setpoints, configuration, programming parameters, boiler control and monitoring, history, diagnostics, modulation percentage, and screen saver.
 2. Control transformer.
 3. Set-Point Adjust: Set points shall be adjustable.
 4. Sequence of Operation: Electric, factory-fabricated and field-installed panel to control burner firing rate to maintain space temperature in response to thermostat with heat anticipator located in heated space.
 - a. Include automatic, alternating-firing sequence for multiple boilers to ensure maximum system efficiency throughout the load range and to provide equal runtime for boilers.
- E. Burner Operating Controls: To maintain safe operating conditions, burner safety controls limit burner operation.
 1. High Cutoff: Manual reset stops burner if operating conditions rise above maximum boiler design temperature.
 2. Low-Water Cutoff Switch: Electronic probe shall prevent burner operation on low water. Cutoff switch shall be manual-reset type.
 3. Blocked Inlet Safety Switch: Manual-reset pressure switch field mounted on boiler combustion-air inlet.

4. High and low gas pressure switches shall prevent burner operation on low or high gas pressure, manually reset on the control interface.
 5. Block drain switch shall prevent burner operation when tripped, manually reset on the control interface.
 6. Low air pressure switch shall prevent burner operation on low air pressure, manually reset on the control interface.
 7. Audible Alarm: Factory mounted on control panel with silence switch; shall sound alarm for above conditions.
- F. Building Automation System Interface: Factory install hardware and software to enable building automation system to monitor, control, and display boiler status and alarms.
1. Hardwired Points:
 - a. Monitoring: On/off status, common trouble alarm.
 - b. Control: On/off operation, hot-water-supply temperature set-point adjustment.
 - c. Analog control: remote firing rate.
 2. A communication interface with building automation system shall enable building automation system operator to remotely control and monitor the boiler from an operator workstation. Control features available, and monitoring points displayed, locally at boiler control panel shall be available through building automation system.
 - a. Protocol to be BACnet IP.
 - b. An authorized factory technician shall provide no less than 6 hours of technical labor on site per each piece of equipment, a minimum of 2 hours to assist the ECC electrician, and a minimum of 2 hours to assist the ECC programmer.
- G. Each boiler shall include an electric, single seated combination safety shutoff valve/regulator with proof of closure switch in the gas train. Each boiler shall incorporate dual over temperature protection with manual reset, in accordance with ASME Section IV and CSD-1.

2.05 ELECTRICAL POWER

- A. Single-Point Field Power Connection: Factory-installed and -wired switches, motor controllers, transformers, and other electrical devices necessary shall provide a single-point field power connection to boiler.
1. House in NEMA 250, Type 1 enclosure.
 2. Wiring shall be numbered, and color coded to match wiring diagram.
 3. Install factory wiring outside of an enclosure in a metal raceway.
 4. Field power interface shall be to non-fused disconnect switch.
 5. Provide branch power circuit to each motor and to controls with a disconnect switch or circuit breaker.
 6. Provide each motor with overcurrent protection.

2.06 VENTING KITS

- A. Venti Kit: Complete system, ASTM A 959, Type 29-4C stainless steel, pipe, vent terminal, thimble, indoor plate, vent adapter, condensate trap and dilution tank, and sealant.
1. PVC / CPVC is an allowable material for boiler venting. Refer to manufacturers requirements.
- B. Combustion-Air Intake: Room combustion air intake kit by boiler manufacturer.
- C. Condensate neutralization drain piping to be galvanized, stainless steel, or Schedule 40 CPVC, Copper, or carbon steel. PVC pipe materials are not acceptable.

2.01 CONDENSATE-NEUTRALIZATION UNITS

- A. Description: Factory-fabricated and -assembled condensate-neutralizing capsule or tank assembly of corrosion-resistant plastic material with threaded or flanged inlet and outlet pipe

connections. Device functions to prevent acidic condensate from damaging grain system. It is to be piped to receive acidic condensate discharged from condensing boiler and neutralize it by chemical reaction with replaceable neutralizing agent. Neutralized condensate is then piped to suitable drain.

- B. Capsule or Tank features:
 - 1. All corrosion-resistant material.
 - 2. Suitable for use on all natural gas boilers.
 - 3. Includes initial charge of neutralizing agent.
 - 4. Neutralizing agent to be easily replaceable when exhausted.
 - 5. Inlet and outlet pipe connections.
 - 6. Top easily removed for neutralizing agent replacement.
 - 7. Internal baffles to channel flow for complete neutralization.
 - 8. Integral bypass to prevent condensate backflow into appliance.

2.02 SOURCE QUALITY CONTROL

- A. Burner and Hydrostatic Test: Factory adjust burner to eliminate excess oxygen, carbon dioxide, oxides of nitrogen emissions, and carbon monoxide in flue gas and to achieve combustion efficiency; perform hydrostatic test.
- B. Test and inspect factory-assembled boilers, before shipping, according to ASME Boiler and Pressure Vessel Code.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Before boiler installation, examine roughing-in for concrete equipment bases, anchor-bolt sizes and locations, and piping and electrical connections to verify actual locations, sizes, and other conditions affecting boiler performance, maintenance, and operations.
 - 1. Final boiler locations indicated on drawings are approximate. Determine exact locations before roughing-in piping and electrical connections.
- B. Examine mechanical spaces for suitable conditions where boilers will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 BOILER INSTALLATION

- A. Equipment Mounting:
 - 1. Install boilers on cast-in-place concrete equipment base(s), minimum 4 inches high. Comply with requirements for equipment bases and foundations specified in Division 23 Section "Common Work Results for HVAC." Equipment bases shall extend a minimum of 4" beyond equipment on each side.
 - 2. Comply with requirements for vibration isolation and seismic-restraint devices specified in Section 230548 "Vibration and Seismic Controls for HVAC."
 - 3. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."
- B. Install gas-fired boilers according to NFPA 54.
- C. Assemble and install boiler trim.
- D. Install electrical devices furnished with boiler but not specified to be factory mounted.
- E. Install control wiring to field-mounted electrical devices.
- F. Furnish and install permanent label or equipment tag with boiler designation.

3.03 CONNECTIONS

- A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to boiler to allow service and maintenance.
- C. Install condensate drain piping to condensate-neutralization unit and from neutralization unit to nearest floor drain. Piping shall be at least full size of connection. Install piping with a minimum of 2 percent downward slope in direction of flow. Provide isolation valve if required by manufacturer's installation instructions.
- D. Connect gas piping to boiler gas-train inlet with isolation valve and union. Piping shall be at least full size of gas-train connection. Provide a reducer if required.
- E. Connect hot-water piping to supply- and return-boiler tapings with shutoff valve and union or flange at each connection.
- F. Install piping from safety relief valves to nearest floor drain.
- G. Boiler Venting:
 - 1. Install flue venting kit and combustion-air intake. Use only materials as defined in the written installation instructions. Comply with requirements of Division 23 Section "Breechings, Chimneys, and Stacks." Utilize insulated 24 gauge G90 galvanized steel ductwork for combustion air unless noted otherwise.
 - 2. Connect full size to boiler connections.
- H. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."
- I. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."


3.04 FIELD QUALITY CONTROL.

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing. Report results in writing to Engineer of Record.
- B. Perform the following tests and inspections:
 - 1. Perform installation and startup checks according to manufacturer's written instructions.
 - 2. Leak Test: Hydrostatic test. Repair leaks and retest until no leaks exist.
 - 3. Operational Test: Start units to confirm proper motor rotation and unit operation. Adjust air-fuel ratio and combustion.
 - 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - a. Check and adjust initial operating set points and high- and low-limit safety set points of fuel supply, water level, and water temperature.
 - b. Set field-adjustable switches and circuit-breaker trip ranges as indicated.
- C. Boiler will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.
- E. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.05 DEMONSTRATION

- A. Engage a factory-authorized service representative for boiler startup and to train Owner's maintenance personnel to adjust, operate, and maintain boilers.

END OF SECTION



1 ROOF MECHANICAL PLAN
1/8" = 1'-0"

GENERAL NOTES

- A REFER TO SHEET M-000 FOR GENERAL MECHANICAL NOTES, SYMBOLS AND ABBREVIATIONS.
- B REFER TO DRAWING M-500 SERIES FOR MECHANICAL DETAILS.
- C REFER TO DRAWING M-600 SERIES FOR MECHANICAL SCHEDULES.
- D PROVIDE AIR VENTS WHEREVER REQUIRED TO REMOVE AIR FROM SYSTEM AND WHERE SHOWN ON DRAWINGS.
- E SHEET METAL CONTRACTOR TO PROVIDE DUCT ACCESS DOORS FOR FIRE DAMPERS, MOTORIZED DAMPERS, AIR FLOW MEASURING STATIONS, AND ON BOTH SIDES OF THE REHEAT COILS. COORDINATE WITH MECHANICAL CONTRACTOR AND GENERAL TRADES CONTRACTOR.
- F COORDINATE ALL SHUT-DOWNS, DELIVERY, AND STORAGE OF MATERIALS, ETC. WITH OWNER'S REPRESENTATIVE.
- G PROVIDE AIR VENTS WHEREVER REQUIRED TO REMOVE AIR FROM SYSTEM AND WHERE SHOWN ON DRAWINGS.
- H CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WORK WITH ALL OTHER TRADES. SEE SPECIFICATION FOR ADDITIONAL REQUIREMENTS RELATED TO COORDINATION.
- J CONTRACTOR SHALL BE RESPONSIBLE FOR CHEMICAL TREATMENT OF SYSTEMS.
- K CONTRACTOR SHALL BE RESPONSIBLE FOR TESTING, FLUSHING AND FILLING OF PIPING AND SYSTEMS AS REQUIRED.

SHEET KEYNOTES

1 TERMINATE BOILER FLUE PER MEC REQUIREMENTS
2 ROOF IS UNDER WARRANTY. ALL ROOF WORK TO BE COMPLETED BY DANCO ROOFING SERVICES, INC.




REVISIONS
1 07/15/2025 Addendum #1

06/27/2025
FRONTIER SCHOOLS
FRONTIER ELEMENTARY SCHOOL BOILER & AHU REPLACEMENT
811 S RAILROAD ST, BROOKSTON, IN 47923
CONSTRUCTION DOCUMENTS



CONSTRUCTION DOCUMENTS
06/27/2025
krM JOB NO.
25032
DRAWN BY
ACB
DRAWING NAME
ROOF MECHANICAL PLAN

DRAWING NO.
M102



1 ENLARGED MECHANICAL PLAN
1/4" = 1'-0"

GENERAL NOTES

- A REFER TO SHEET M-000 FOR GENERAL MECHANICAL NOTES, SYMBOLS AND ABBREVIATIONS.
- B REFER TO DRAWING M-500 SERIES FOR MECHANICAL DETAILS.
- C REFER TO DRAWING M-600 SERIES FOR MECHANICAL SCHEDULES.
- D PROVIDE AIR VENTS WHEREVER REQUIRED TO REMOVE AIR FROM SYSTEM AND WHERE SHOWN ON DRAWINGS.
- E SHEET METAL CONTRACTOR TO PROVIDE DUCT ACCESS DOORS FOR FIRE DAMPERS, MOTORIZED DAMPERS, AIR FLOW MEASURING STATIONS, AND ON BOTH SIDES OF THE REHEAT COILS. COORDINATE WITH MECHANICAL CONTRACTOR AND GENERAL TRADES CONTRACTOR.
- F COORDINATE ALL SHUT-DOWNS, DELIVERY, AND STORAGE OF MATERIALS, ETC. WITH OWNER'S REPRESENTATIVE.
- G PROVIDE AIR VENTS WHEREVER REQUIRED TO REMOVE AIR FROM SYSTEM AND WHERE SHOWN ON DRAWINGS.
- H CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WORK WITH ALL OTHER TRADES. SEE SPECIFICATION FOR ADDITIONAL REQUIREMENTS RELATED TO COORDINATION.
- J CONTRACTOR SHALL BE RESPONSIBLE FOR CHEMICAL TREATMENT OF SYSTEMS.
- K CONTRACTOR SHALL BE RESPONSIBLE FOR TESTING, FLUSHING AND FILLING OF PIPING AND SYSTEMS AS REQUIRED.

SHEET KEYNOTES

- 1 REPLACEMENT AND INSTALLATION OF HEATING WATER SYSTEM IN ITS ENTIRETY IS BASE BID INCLUDING DPT SHOWN ON M402.
- 2 INSTALL BOILERS ON EXISTING CONCRETE PAD.
- 3 PIPE BOILER DRAIN AND CONDENSATE NEUTRALIZATION DRAIN TO EXISTING FLOOR DRAIN.
- 4 12" BOILER FLUE UP. SEE M102. TERMINATE BOILER FLUE PER MFG INSTALLATION REQUIREMENTS.
- 5 BOILERS TO USE ROOM AIR FOR COMBUSTION INTAKE. PROVIDE NEW ACTUATOR FOR EACH EXISTING COMBUSTION AIR INTAKE AND INTERLOCK COMBUSTION AIR DAMPERS WITH EACH BOILER TO OPEN PRIOR TO FIRING AND CLOSE AFTER BOILER SHUTDOWN. EXISTING HEATING WATER SYSTEM OF ENCLOSURE TO BE REUSED.
- 7 REFER TO SHEET P401 FOR CONTINUATION.
- 8 BOILER EMERGENCY STOP (BY TCC), MOUNTED 4'-0" AFF.
- 9 2-1/2" HEATING WATER SYSTEM MINIMUM FLOW VALVE. PROVIDE SHUT-OFF VALVE ON BOTH SIDES OF CONTROL VALVE FOR MAINTENANCE AND VALVE REMOVAL. INSTALL VALVE TIGHT TO WALL. PIPING OFFSET HAS BEEN SHOWN FOR CLARITY.
- 10 1" HEATING WATER SYSTEM MAKE-UP WATER LINE.
- 11 CAP PENETRATION IN WALL WHERE EXISTING BOILER FLUE WAS REMOVED.
- 12 MAKE-UP WATER METER. SEE M902.



REVISIONS

1 07/15/2025 Addendum #1

06/27/2025
FRONTIER SCHOOLS
FRONTIER ELEMENTARY SCHOOL BOILER & AHU REPLACEMENT
811 S RAILROAD ST, BROOKSTON, IN 47923
CONSTRUCTION DOCUMENTS



CONSTRUCTION DOCUMENTS
06/27/2025
krM JOB NO.
25032
DRAWN BY
ACB
DRAWING NAME
**MECHANICAL
ENLARGED PLANS**

DRAWING NO.
M401



1 ENLARGED MEZZANINE LEVEL ELECTRICAL PLAN
1/4" = 1'-0"

GENERAL NOTES

- A REFER TO SHEET E-000 FOR GENERAL ELECTRICAL NOTES, SYMBOLS AND ABBREVIATIONS.
- B CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF MECHANICAL EQUIPMENT WITH THE MECHANICAL CONTRACTOR. EXACT ELECTRICAL REQUIREMENTS SHALL BE FIELD VERIFIED AGAINST THE EQUIPMENT NAME PLATE DATA. THE CONTRACTOR SHALL MAKE APPROPRIATE ADJUSTMENTS OF FEEDER CIRCUITS AS REQUIRED.

SHEET KEYNOTES

- 1 NEW AHU-2. PROVIDE DUCT SMOKE DETECTOR IN SUPPLY DUCT AND CONNECT TO FIRE ALARM SYSTEM TO ACTIVATE UPON ALARM.
- 2 NEW COMBINATION VFD/DISCONNECT SWITCH AHU-2 SF VFD. CONTRACTOR SHALL CONNECT EXISTING CIRCUIT IN PLACE FED FROM PANEL PP1. UPDATE DIRECTORY IN PANEL WITH NEW EQUIPMENT DESIGNATION. ROUTE 3 #10, #10 G, 3/4" C TO NEW AHU-2.
- 3 NEW VAV TRANSFORMER. ROUTE 2 #12, #12 G, 3/4" C TO NEW 20A, 1P CIRCUIT BREAKER TO BE INSTALLED IN EXISTING PANEL BR.
- 4 NEW HVAC CONTROL PANEL AHU-2 TOP. CONTRACTOR SHALL CONNECT EXISTING CIRCUIT TO NEW PANEL. UPDATE DIRECTORY IN PANEL WITH NEW EQUIPMENT DESIGNATION.
- 5 PROVIDE NEW SMOKE DETECTOR IN RETURN DUCT.



REVISIONS	ADDENDUM #1
1	07/15/2025


06/27/2025
FRONTIER SCHOOLS
FRONTIER ELEMENTARY SCHOOL BOILER & AHU REPLACEMENT
811 S RAILROAD ST, BROOKSTON, IN 47923
CONSTRUCTION DOCUMENTS



CONSTRUCTION DOCUMENTS
06/27/2025
krM JOB NO.
25032
DRAWN BY
Author

DRAWING NAME
ENLARGED ELECTRICAL PLANS

DRAWING NO.
E401

[illegible]