



Addendum #6
Vernon Township Public Library
McCordsville Branch Buildout

Date: December 9, 2025
Project: Vernon Township Public Library – McCordsville Branch Buildout
Project #: 24025
Pages: 1 of 1 (8-1/2x11) pages
Bid Dates: **FRIDAY, December 12, 2025 at 2:00 pm (prevailing local time)**

General Note:

The original Specifications and Drawings dated October 28, 2025 for the project referenced above are amended as noted in this Addendum No. 6. Receipt of this Addendum and any subsequent Addenda must be acknowledged on the Bid Form. Items changed or added by this addendum are to take precedence over the items or descriptions of the work in the project manual and the drawings. Items not mentioned in this addendum are to remain as described in the original plans and specifications.

Drawing Items:

Sheet E1-1 Electrical Plan

1. The breaker for the alternate air handler on the roof to be 40 amp 1 phs. 208 volt.

Sheet MP1-1 HVAC & Plumbing Plan

1. The added Unit on the roof to be an alternate. The refrigerant lines to be run directly from the outdoor unit to each air handler. Separate lines for each FCU. See roof penetration detail on addendum #4. Roof penetration according to roof manufacturers recommendation. The owner will supply the roof membrane manfctr. name so all penetration & work on the roof can be done according to there recommendations. Durable nylon rope can be used for a tie down of the unit. From outside unit to the concrete blocks.
 2. The base bid for the two added air handlers is as its shown on this sheet. Separate refrigerant lines from the existing BDU location to the new FCU location, Coordinate with the LG on the refrigerant line sizes.
-

Attachments:

1. None

END