



Primary Engineering, Inc.
2828 Lake Ave.
Fort Wayne, Indiana 46805
260-424-0444 ph
www.primary-eng.com



Addendum: **3**

Date: **08/27/2026**

Project: **PFW Chiller #2 Replacement 2026**

Comm #: **26814**

The following items shall be incorporated into the specifications and drawings and are considered to be integral to the bid documents for the project. Acknowledgement of receipt of this addendum is required on the bid form.

Item #1: Questions:

A. Question: Is the roof under warranty?

Response: Yes. Installed in 2013 with 20 year warranty. Roof material is Soprema membrane installed by Slatile Roofing, South Bend.

B. Question: Is the piping to be painted?

Response: Yes, 232113, 3.2, H calls for all chilled water piping to be painted. This section shall be modified by this addendum to also include the condenser water piping. Match existing color scheme.

Item #2: Specification Section 232113 Hydronic Piping

A. Revise paragraph 3.2, H. to read as follows:

- "All steel interior chilled **and condenser water** piping shall be painted with (2) coats of rust inhibitive paint equal to Rustoleum. Primer coat shall be white. Top coat shall match existing color scheme, with semi-gloss finish. Touch up all scuff marks and voids after assembly and prior to insulation."