Corporate Office
8720 Castle Creek Pkwy E Dr., Suite 400
Indianapolis, IN 46250
www.eticagroup.com

# ADDENDUM NO. 4

**Client:** City of Elwood
**Municipal Building Renovation**

Issue Date: November 5, 2026

This Addendum forms a part of the Bidding Documents and modifies the original Bidding Documents dated November 2, 2026, and any previously issued Addenda, as noted herein.

Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to acknowledge receipt may subject the Bid to disqualification.

All provisions of the original Bidding Documents shall remain in effect except as specifically modified by this Addendum.

## CONTENTS

****Please provide two copies in your sealed bid****

**ADDENDUM NO. 4** **PAGES 1**

**ATTACHMENTS**

10 05113 – Metal Lockers

## CHANGES TO THE SPECIFICATIONS

1. **10 05113 – Metal Lockers**
    a. Add Spec Section

END OF ADDENDUM NO. 4

BLANK SHEET

# SECTION 10 05113– METAL LOCKERS

## PART 1 - GENERAL

### 1.1 SUMMARY

A. Section Includes:

1. Locker benches.

B. Related Requirements:

1. Section 105113.13 "Coin-Operated Metal Lockers" for coin-operated lockers used in public facilities for temporary storage of personal belongings.

### 1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at project site.

### 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of bench.

B. Samples: For each color specified, in manufacturer's standard size.

C. Samples for Initial Selection: Manufacturer's color charts showing the full range of colors available.

D. Samples for Verification: For the following products, in manufacturer's standard size:

1. Locker benches.

E. Product Schedule: For benches.

### 1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For adjusting, repairing, and replacing locker doors and latching mechanisms to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver benches until spaces to receive them are clean, dry, and ready for their installation.

1.8 FIELD CONDITIONS

A. Field Measurements: Verify actual dimensions of recessed openings by field measurements before fabrication.

1.9 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of work specified in other Sections to ensure that benches can be supported and installed as indicated.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain locker benches and accessories from single source from single locker manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Accessibility Standard: For locker benches indicated to be accessible, comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" ICC A117.1.

2.3 LOCKER BENCHES

A. Basis-of-Design Product: Subject to compliance with requirements, provide ASI Storage Solutions, an ASI Group company; Locker Benches or comparable product by one of the following:

1. AJW Architectural Products.
2. Hadrian Manufacturing Inc.

B. Provide bench units with overall assembly height of 17-1/2 inches

C. Bench Tops: Manufacturer's standard one-piece units, with rounded corners and edges.

1. Size: Minimum 9-1/2 inches wide by 1-1/2 inches

2. Black core phenolic with smooth finish.

a. Color: As selected by Architect from manufacturer's full range.

D. Movable-Bench Pedestals: Manufacturer's standard supports, with predrilled fastener holes for attaching bench top, complete with fasteners, and as follows:

1. Stainless Steel:

a. 2-inch- diameter steel tubing, 0.060-inch- thick stainless steel tube, shaped into trapezoidal form. Bottom 14 inches wide with four mounting holes.
b. Finish: No. 4, brushed.

E. Materials:

1. Stainless Steel Plate, Sheet, and Strip: ASTM A240/A240M or ASTM A666, Type 304.
2. Steel Tube: ASTM A500/A500M, cold rolled.
3. Phenolic: Phenolic composite panel.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

A. Examine walls and floors or support bases, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

A. Movable Benches: Place benches in locations indicated on Drawings.

3.3 ADJUSTING

A. Clean, lubricate, and adjust hardware. Adjust doors and latches to operate easily without binding.

3.4 PROTECTION

A. Protect benches from damage, abuse, dust, dirt, stain, or paint. Do not permit use during construction.

B. Touch up marred finishes or replace benches that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by manufacturer.

END OF SECTION 10 05113