

Delaware 103 – Bridge Replacement

Pre-bid Contractor questions received on or before 9/28/2026:

Q: Is there a set contract completion date requirement for Bridge 103 in Delaware County?

A: The contract completion date will be set for 10/31/2027. A contract addendum is forthcoming.

Q: What material is being used to backfill the cored holes for the piling?

A: Class A Concrete shall be used to backfill the cored holes within the limits of the rock (Est. El. 929 to 937). In accordance with ISS 701.14 and 701.15, this concrete not be measured for payment, and the cost shall be included in the other pay items within ISS 701.

Q: What diameter is the encasement for the piling in the piers?

A: Pile encasement diameter shall be 2'-0" minimum in accordance with Standard Drawing No. E-701-BPIL-01.